

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO., LTD**

Office of the Executive Engineer, EHV Project Division, Aurangabad.

Office Address: 104, 1<sup>st</sup> Floor, New Administrative Building,  
132kV Harsool s/s premises, Aurangabad-431008

E-mail Id : ee2610@mahatransco.in, eeconstabd@gmail.com

No.EE/EHV/Const/Div/Abad/Tech/1561,

Dt: 10.10.2023

**E-Enquiry**

To,

-----  
-----

**Sub:** E-Enquiry for work of maintenance of 33 kV Ektuni- Thaptitabda line in r/o 33kV auxiliary supply at 400 kV Thaptitanda sub-station.

Dear Sirs,

Sealed quotations are invited in separate envelope duly superscribed with the above subject, so as to reach this office on or before 17.10.2023 upto 15.00 Hours for the above said work subject to the terms and conditions detailed below -

**TERMS AND CONDITIONS**

1. **Scope of Work:** The scope of works includes maintenance works of 33 kV Ektuni- Thaptitabda line in r/o 33kV auxiliary supply at 400 kV Thaptitanda sub-station.
2. The unit rates should be quoted on firm quotation basis including cost of materials, all taxes, labour charges and T&P etc. required for execution of work.
3. All required T&P, machinery, manpower etc. shall be arrange by you. No labour assistance or T & P or equipment will be provided by the MSETCL.
4. The contractor should have experience of 33kV line maintenance in last two year and experience certificate from competent authority of MSEDCL not below the rank of Executive Engineer should be attached with the offer. Also GST registration, Shop Act, PAN, TIN etc statutory licenses are to be submitted with offer.
5. While submitting the quotation, the contractor should pay E.M.D of Rs.2551/- by cash or DD of any nationalized/schedule bank in favor of EE, EHV Project Division, Aurangabad payable at Aurangabad in this office and the money receipt number thereof should be superscribed on the envelope.
6. The firm rates should be quoted in figures and total amount should be quoted in figures as well as in words.
7. If any damage is occurred to the contractor's Equipment/T&P, any accident to your labours/personnel & if any theft/loss, the MSETCL will not be responsible in any way.



8. An Income Tax & as applicable taxes will be deducted from your bill.
9. The work should be completed within 30 days working days from the date of handing over of work site, failure of which a penalty equal to 1% per week subject to the maximum of 5% of the ordered value will be levied.
10. The work should be strictly carried out as per standard specifications and upto the entire satisfaction of the Engineer-in-charge.
11. Security deposit: You will have to pay security deposit @ 10% of total work order value immediately after award of work Order.
12. The terms and conditions enumerated in the M.S.E.T.C.L's booklet "Tender and Contract for Works" will be applicable in this case and will be binding on the contractor entirely.
13. The undersigned reserves the rights to accept or reject any or all the Quotation without assigning any reason thereof.
14. MSETCL reserves the right to add additional terms & condition of contract during the finalization of work order.
15. The Quantities enumerated in the attached schedule 'A', 'B' & 'C' are approximate and payment will be made against actual executed quantities.
16. The work should be strictly carried out as per standard specifications and upto the entire satisfaction of the Engineer-in-charge.

Thanking you,

Yours faithfully

(A. C. Pathak)

**Executive Engineer**  
EHV Projects Division,  
Aurangabad  
o/c

**Encl. Schedule 'A'.**

**Copy s.w.r to**

The Superintending Engineer, EHV Projects Circle, Aurangabad

**Copy to:**

The Manager (F&A) EHV Projects Division, Aurangabad

Notice Board of EHV Projects Division, Aurangabad

# Maharashtra State Electricity Transmission Company Ltd.

EHV Project Division Aurangabad

Sub- Providing, Fixing & maintenance of 33 kV Thaptitanda line from 765 kV Ektuni Substation to 400 kV Thaptitanda Substation, Under EHV Project Division Aurangabad.

## Annexure-(A) Materials & Labour portion in r/o HT 33 kV Line

Sr.No.	Description of Material	Unit	Qty	Unit Rate	Amount	Remarks
<b>Supply Portion</b>						
1	RSJ 152x152, 11 m long	No.	0.00			
2	RSJ 116x100, 10 m long	No.	0.00			
3	MS Channel 100x50x6 mm	Kg.	0.00			
4	M.S.Channel 75x40x6 mm	Kg.	0.00			
5	33 KV Top Fitting	No.	10.00			
6	MS angle 50x50x6 mm	Kg.	0.00			
7	M.S. Flats(50 X 10mm)	Kg.	0.00			
8	33 kV Pin Insulators with G.I. Pins	No.	50.00			
9	Disc Insulator 11 KV 70 KN	No.	54.00			
10	G.I.Nut Bolts	Kg.	50.00			
11	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	18.00			
12	AAAC 100 mm2	Mtrs.	250.00			
13	H.T.Stay Set	No.	6.00			
14	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	60.00			
15	G.I.Wire 8 SWG/ 6 SWG	Kg.	130.00			
16	Sleve Joints	No.	0.00			
17	Danger Board in yard.	No.	0.00			
18	Earthing Sets H.T	No.	18.00			
19	Concreting ration 1:3:6	cmt.	5.00			
20	G.I.Barbed Wire 'A' type.	Kg.	0.00			
21	Black bituminous paint	Ltr.	0.00			
22	Red Oxide Paint for 2 coats	Ltr.	0.00			
23	Aluminium Paint for 1 coat	Ltr.	0.00			
24	Sundries	LS	1.00			
<b>Erection Portion</b>						
1	Trimming Tree branches fallen HT lines	LS	6			
2	HT stay sets incl con 1:4:8 ratio -0.3	EA	6			
3	Repl of damaged earthing	No.	18			
4	Repl of tilted/dameged Top clip	No	10			
5	Repl of faulty Pin insulator	No	50			
6	Repl of faulty Disc insulator	No	54			
7	HT stay sets re-fixing & bind, labour	EA	18			
8	Restrining of loose span cond 0.06 ACSR & above	Set	30			
9	Repl of faulty jumper	No	30			
10	Straightning of tilted pole RSJ pole	No.	40			

Sd  
Executive Engineer  
EHV Project Division Aurangabad