

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
CIN NO-U40109MH2005SGC153646

Executive Engineer, MSETCL, EHV O&M Dn., Sangli Office building, Vishrambag, Tal- Miraj Dist. Sangli- 416415 Contact No. –0233-2305816 (O), 0233- 2304872 (P), 0233-2304873 (F) E-mail ID – ee3120@mahatransco.in Website – www.mahatransco.in

Ref No. EE/EHV O&M/Dn/SGL/T/No. **1468**

Date **10/11/2023**

TO WHOM SO EVER IT MAY CONCERN
BUDGETARY OFFER FOR ESTIMATE

Please find herewith a detail schedule “A” & Scope of Control room wiring at 220KV Miraj S/Stn EHV O&M Division, Sangli.

All interested & experienced bidders are requested to submit their best lowest budgetary offer on the **Mail ID:-ee3120@mahatransco.in** for the same upto Dtd.17/11/2023. Taxes should be quoted distinctly if any.

Please note that this budgetary offer is for estimation purpose only.

SCHEDULE 'A' (SCOPE OF WORK)

Sr. No.	Description	Unit	Qty	Rate Per Unit	% GST
1	Point wiring : Providing and fixing of light point wiring in PVC casing capping by using 1.5 sq.mm. multistrand wire with modular type switches fixed in PVC boxes with necessary fixtures and fastening and labour, complete as directed by engineer in-charge.	Point	140		
2	Point wiring: Providing and fixing of Fan point wiring in PVC casing capping by using 1.5 Sp.mm multistranded wire with modular type switches fixed in PVC boxes with necessary fixtures and fastening and labour complete as directed by engineer in-charge	Point	60		
3	Providing and fixing modular type dimmer	No.	60		
4	Providing and fixing modular switch boards with fuse indicator	No.	70		
5	Providing and fixing of wall fan	No.	4		
6	Providing and fixing fan 1200mm long high speed (five star rating)	No.	10		
7	Providing and fixing stand fan	No.	4		
8	Providing and fixing exhaust fan.	No	4		
9	Point wiring: Providing and fixing of plug point with modular type switches fixed in PVC boxes with necessary fixtures and fastening and labour, complete as directed by engineer in-charge.	No.	100		
10	Point wiring: Providing and fixing of power plug point wiring in PVC casing capping by using 2.5 sq.mm. multistrand wire with modular type switches fixed in PVC boxes with necessary fixtures and fastening and labour, complete as directed by engineer in-charge.	No.	40		
11	Running cable 4sq.mm.*2 mains with earthing 1sq.mm per meter	per Mtr	200		
12	Running cable 6sq.mm.*2 mains with earthing 1sq.mm per meter	per Mtr	200		

Sr. No.	Description	Unit	Qty	Rate Per Unit	% GST
13	Telephone 2pair/5pair/computer cable/speaker/camera cable per meter	per Mtr	20		
14	Providing and fixing circuit box 16Amp/32 Amp MCB etc including all labour charges etc,	No.	4		
15	Providing erthing using Cu. Plate and earthing powder (Bentonite)	No	20		
16	Providing and fixing Ding Dong bell with point wiring including casing capping extra wire for point etc completed	No	4		
17	Providing and fixing 2*2 POP light	No	20		
18	Providing and fixing 20W LED tube sets.	No	120		
19	5Amp plug on board. Providing and fixing of 5 A Plug lighting plug/ 3 pins 5 Amp Switch & plug	No	100		
20	15 Amp plug on board. Providing and fixing of ISI mark Anchor or equivalent make 15 A Power Plug erected on polypropylene ISI mark Board with MS screw.	No	40		
21	6 to 32 Amp TPN MCB fixing	No	20		
22	Single phase DB 6 way to 8 way	No	30		
23	Single phase DB 12 way to 18 way	No	10		
24	TPN DB 4way to 6way	No	10		
25	TPN DB 8way to 12 way	No	10		
26	6 to 32amp DP MCB fixing	No	10		
27	Removal of old wiring & Boards	LS	4		

Note:-1. Please Clearly Mention Taxes & Other Conditions.

2. Material should be ISI Mark & Reputed Mfg.

3. Electrical appliances must be energy efficient.

Yours faithfully,

Sd/
Executive Engineer,
M.S.E.T.C.Ltd,
EHV O&M Dn, Sangli