



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of The Executive Engineer
400 KV R.S O&M Division, Kalwa
PO Box No. 5 Airoli
Navi Mumbai 400 708
Phone No. 022-27601893, 94
E-Mail :-ec7140@mahatransco.in
CIN No.U40109MH2005SGC153646.

EE/400KV/RS/O&M/Dn/KLW/Tech/23-24/

000844

Date:-22.11.2023

E-ENQUORY

(Through MSETCL webpage)

To,
WHOM SO EVER IT MAY CONCERN


Sub:- Enquiry for auto changeover of DG set (250kVA) with LT panel automation at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa.
.....submission of budgetary offers thereof.

This office has to prepare estimate for auto changeover of DG set (250kVA) with LT panel automation at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa. It is requested to offer your favorable budgetary offer for the subject work as detailed in the enclosed price estimate.

1. **DUE DATE:-** The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office on or before due date i.e. 29.11.2023.
2. **QUOTED RATES :-** The quoted rate should include the cost of all skilled & unskilled labour, and also the requisite consumables, T&P and all incidental charges such as traveling / transportation, accommodation etc.
3. **DOCUMENT SUBMISSION:-** The bidder should submit all the supporting and accompanying documents (i. e. PAN, GST certificate, Shop & Establishment certificate etc.) required for execution of work in sealed Envelope to this office.
4. **Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

Thanking you.

Yours faithfully,


Pankaj A. Shelar
Executive Engineer
400KV R.S. (O&M) Dn. Kalwa

Encl: Schedule 'A'.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
400KV RS O&M DN KALWA

Schedule A

Sub:- Auto changeover of DG set (250kVA) with LT panel automation at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa.

Supply Portion


Sr. No.	Description	Unit	Ex Rate	GST	Unit Rate
1	Supply of 4 pole, 1000Amp EDO ACB	EA			
2	4 pole auxiliary contactor 230 VAC	EA			
3	Add on contactor block	EA			
4	Voltage monitor	EA			
5	On delay timer	EA			
6	6A single pole MCB	EA			
7	Auto manual switch	EA			
8	Push Button	EA			
9	Indication lamp	EA			
10	1.5 sq.mm wire	Mtr			

Service Portion

1	Labour charges for designing of auto changeover scheme, Implementation of scheme on paper (drawing) with legends, symbols, identification of wires & submission of same for approval & associated work.	EA			
2	Labour charges for removal of existing ACB & Busbar installation of new ACB with retrofitting in proper manner by expert person.	EA			
3	Labour charges for installation of all contactors, timers, voltage monitors, push buttons, MCBs, Auto manual switches etc. & wiring of the same as per approved drawing & associated work.	EA			
4	Labour charges for testing & commissioning of entire scheme.	EA			

② Note: Please mentioned in the budgetary offers that the Ex-works rates are inclusive of other taxes (i.e Freight & insurance, Labour cess etc.) or exclusive of other taxes)

① Before submitting budgetary offer the agency should visit to 400 KV Kalwa site & understand the nature of work to be done.


 Executive Engineer
 400KV R.S. (O&M) Dn, Kalwa