

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD

(CIN No.- U40109MH2005SGC153646)



From:- The Executive Engineer

Name of Office:- 400 K.V.R.S.Dn. New Koyna

Office address:- A/p- Pimpli (Bk), Tal-Chiplun, Dist: Ratnagiri - 415 604

Contact No:- 7447440852

Email Id:- ee3140@mahatransco.in

Ref: EE/400KV/RSDN/NK/Tech/ NO 0 6 0 9

Date: 2 2 DEC 2023

E-Enquiry

Sub:- Enquiry for supply of Digital Multimeter, Digital Clamp on meter & Digital Earth Tester at 400 KV RS Dn, New Koyna.

Please offer your reasonable rates for the of Digital Multimeter, Digital Clamp on meter & Digital Earth Tester at 400Kv R.S Div New Koyna as detailed in Schedule 'A' enclosed.

- 1. DUE DATE: The quotations complete in all respects, duly sealed & super Scribed should be submitted to this office before 17:00 hrs on Dtd. 29/12/2023.
- 2. QUOTED RATES: Rates should be inclusive of all such as material required If any, Labour charges Etc. The taxes applicable if any should be quoted Distinctly.
- 3. TECHNICAL QUALIFYING CONDITIONS:
- i) Annual Income Tax Return for last three years
- ii) Valid Electrical Contractors License.
- iii) Insurance of Labour & registration
- iv) Shop Act license or NOC from Gram panchayat
- v) GST Registration Certificate.
- vi) Certificate of performance of work done for supply of Digital Multimeter or Digital Clamp on meter or Digital Earth Tester.
- 4. COMPLETION PERIOD: Within 04 weeks from the date of order.
- 5. SECURITY DEPOSIT: The successful bidder will have a pay an amount equivalent to 5% of the contract value towards security deposit at Circle Office Karad.
- 6. All the terms & conditions as per company's rule including M.S.E. T.C.L. Booklet tender & contract tor supply are applicable in this case also.
- 7. The under signed reserves the right to cancel the quotations/work or part of it without assigning any reason thereof.

Executive Engineer 400 KV R. S. Div, New Koyna

Copys. w. Rs. to:-

1) The Superintending Engineer, EHV (O&M) Circle, Karad.

Copy to:-

1) Dy Manager (F&A), New Koyna

2) Addl.EE (Maint), 400KV R.S Dn, New Koyna

3) M/F.



MAHARASHTRA STATE ELECTRICITY TRANS. CO. LTD. 400 KV RS. Division, New Koyna

SCHEDULE 'A'

Sub: - Supply of Digital Multimeter, Digital Clamp on meter & Digital Earth Tester at 400 KV RS Dn, New Koyna.

Schedule 'A'

| Sr. no | Particulars | Unit | Qty | Rate per Qty | Amount |
|-----------|---|------|-----|-----------------|--------|
| 1. | Digital Multimeter: Specifications:-True RMS reading, Min.6000 counts, with LED backlight, Handled/portable, AC/DC upto600 volts with 0.1 V resolution; Min. 3 digits with accuracy 0.5% AC/DC current up to 10A (Fused) with min. 0.0.1 A resolution; Min. 3 digits with accuracy 1%, Frequency, Capacitance, Diode, Resistance, measurements, Continuity with beepere, Supply:-9 V battery, Test leads-CAT III/ CAT IV 600 V Make-Fluke/Motwani preferable. | Nos | 2 | | |
| 2. | Digital Clamp on meter: Specification:-0.01 mA resolution, 0.02 EMC & EN61010-1 compliant (30mA-300mA) & (30Amp -300Amp 40 mm Jaw size Digital Display Make- Fluke/Motwani preferable. | Nos | 2 | | |
| 3. | Digital earth tester: Specifications:- 31/2 digit LCD Display with max reading 1999. 3 terminal and 4 terminal Measurement Method. Earth Resistance Range Measurement Rechargeable Internal Ni-MH Battery. Earth Measurement Voltage up to 200V. Ratio Metric Synchronous Rectification. Make-Fluke/Motwani preferable. | Nos | 1 | | |
| | TOTA | | | | |

Executive Engineer
400KV R.S Dn New Koyna