



**MAHA TRANS CO**  
MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

**CIN No.U40109MH2005SGC153646**

<b>Name of Office :- 400 kV RS Division, Kumbhargaoon, Nanded.</b>
<b>Office Address :- Office of the Executive Engineer, Nanded- Hyderabad Highway, Near Kapsi Gumfa, Kumbhargaoon Tq. Loha Dist. Nanded</b>
<b>Contact No. :- 7030941703 / 8554995348.</b>
<b>Email :- <a href="mailto:ee2270@mahatransco.in">ee2270@mahatransco.in</a>; ee400kvkumbhargaoon@gmail.com</b>
<b>Ref. No. EE/400kV RS/Div./K'gaon/Nanded/TS/File No.43/No. 510</b>
<b>Date :- 26.12.2023</b>

### **Re- E-Enquiry**

**To,**

**Subject:- Re-E-Enquiry for the work of Supply & Erection of Light Mast Tower (21 Meter height) at 400KV RS Kumbhargaoon, (Nanded )**

Dear Sir,

Sealed & super scribed quotation are invited from supplier/vendors for the work of Schedule "A" on following terms & conditions:- under 400KV RS Division Kumbhargaoon (Nanded).

- 1. Scope of work:** As per Schedule "A".
- 2. The quotation should be sent under sealed cover duly super scribed as QUOTATION FOR the work of Supply & Erection of Light Mast Tower (21 Meter height) at 400KV RS Kumbhargaoon, (Nanded). The quotation complete in all respects i.e. Offer rates should be filled in given work Schedule "A" format copy, Duly signed, sealed & super scribed, along with covering letter of bidder/agency with above mentioned subject. (Enquiry No. \_\_\_\_ be quoted).**
- 3. Quoted Rate:** The bidder has to submit percentage bid for the particulars mentioned in Schedule "A".
- 4. Important Dates:** Quotations invited from **27.12.2023 from 10:00 Hrs**, so as to reach this office up to **02.01.2024 up to 18:00 hrs** and the same will be Opened on the same day, if possible. Quotation received after due date will not be considered. This office is not responsible for any postal delay.
- 5. Order value:** The Order value is limited to Rs. 7, 23,288.0/- (In Words: Rs. Seven Lakhs Twenty Three Thousand Two Hundred & Eighty Eight Only) inclusive of all taxes.
- 6. Taxes:** Taxes will be paid & recovered, as per rules.

7. **Payment:-** On completion of work, agency to submit the bill in triplicate (Indicating PAN No., GST Reg. No.) along with MOM & test certificates (if any), and advance stamp receipt, towards AEE, 400 kV S/s Maint. Unit Kumbhargaoon, Nanded, who will record the bill as per actual work done.
8. **Paying Office:** - No advance payment shall be made in any case. However payment against this contract will be effected by Executive Engineer, 400 kV R S Division Kumbhargaoon, Nanded within reasonable time as per funds availability & after satisfactory completion of work.
9. **Security Deposit:-** Security deposit i.e. 5% of order value to be paid within 7 days in terms of cash/DD to the office of the Executive Engineer, 400 kV R S Division Kumbhargaoon, Nanded from the date of issue of order.
10. **Signing of Contract:-** Agreement contract between MSETCL authority & you should be carried out on Rs.500 bond paper within 7 days from the date of receipt of the work order. You will have to borne the charges for agreement bond.
11. **Validity of Offer:-** The offer should be valid for our acceptance for a period of 120 days from the Due date of same.
12. The rates should be quoted excluding / including of taxes. The taxes if any should be quoted extra.
13. **Documents required:-** The rate offer must be accompanied with the following documents duly attested & signed by the Agency.
  - A. Valid proof of Electrical Contractor License.
  - B. Valid Proof Shop Act registration / Udyog Adhar Certificate.
  - C. Valid proof of GST registration.
  - D. Valid PAN Card.
  - E. ITR for the FY 2023-24.
  - F. The Bidder should have, in last five years executed the similar work i.e. Supply & Erection of LMT tower OR Erection of EHV Bays/Lines. The colour photo of Experience Certificates from the officer not below the rank of Executive Engineer for having successfully executed, should be attached.
14. **Penalty:** The execution of work of 'Schedule-A' in all respect to be completed within 90 days from the date of receipt of this office order, otherwise penalty @ 1% per week subject to max.10% of the order amount will be levied at the discretion of the Competent Authority.
15. **Material & Workmanship:** - Should be standard as per the specifications & work should be performed up to the full satisfaction of Engineer incharge.

16. Before quoting rates, agency if needed may inspect the site.

17. **Quantity:** - Quantity shown in Schedule "A".

18. Please quote your **PAN & GST No.** in the quotation & provide **HSN code** for material to be supplied.

19. **Guarantee Period:** Agency to give guarantee for the workmanship for the period of 24 months.

20. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever

21. All the MSETCL's general terms & conditions for purchase will be binding on you.

Thanking you.

Encl.:- Schedule "A"

Yours faithfully,

**-SD-**  
**(D.B.Rajurkar)**  
**Executive Engineer**  
**400 kV R S Division Kumbhargaoon**  
**Nanded**

**Copy SWRT:-**

1. The Chief Engineer, EHV PC O&M Zone Aurangabad.
2. The Superintending Engineer, EHV O&M Circle Parli V.

**Copy to:-**

1. The Dy.Mgr (F&A), 400 kV R S Division Kumbhargaoon, Nanded
2. Website:- [www.mahatransco.co.in](http://www.mahatransco.co.in)

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**  
**400 kV RS Division, Kumbhargaoon, Nanded.**

**Schedule "A"**

**Subject:-** Work of Supply & Erection of Light Mast Tower (21 Meter height) at 400KV RS Kumbhargaoon, (Nanded,)

<b>Sr. No</b>	<b>Particulars</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate / Unit In Rs.</b>
<b>SUPPLY PORTION:-</b>				
1	Galvanised Gantry structure, equipment support Structure, Lighting Mast (21 Meter) with foundation bolts.	MT	2.6	
2	Galvanised Nuts & Bolts	MT	0.05	
3	200W LED Light	NOS	8	
4	3.5C x 35 sq. mm Aluminium, Armoured FRLS cable	KM	1	
5	AC lighting DB (Outdoor)	NO	1	
6	Ear thing Strips for Earth Mat 75 x 12 mm, MS	MT	0.5	
7	Earthing Strips for Risers. 50 x 8 mm, G.I.	MT	0.1	

<b>ERECTION PORTION :-</b>				
1	Galvanised Gantry structure, equipment support Structure, Lighting Mast (21 Meter) with foundation bolts.	MT	2.6	
2	Galvanised Nuts & Bolts	MT	0.05	
3	200W LED Light	NOS	8	
4	3.5C x 35 sq. mm Aluminium, Armoured FRLS cable	KM	1	
5	2C x 2.5 sq. mm Copper, Armoured FRLS cable	KM	1	
6	AC lighting DB (Outdoor)	NO	1	
7	Earthing Strips for Earth Mat 75 x 12 mm, MS	MT	0.5	
8	Earthing Strips for Risers. 50 x 8 mm, G.I.	MT	0.1	

Note:

- 1) Whether Rate/Unit is Inclusive of Labour Cess @ 1% \_\_\_\_\_.
- 2) Whether Rate/Unit is Inclusive of GST @ 18% \_\_\_\_\_.
- 3) If Taxes Not mentioned the Rate/Unit is considered as inclusive of all Taxes.

Signature of Agency  
With Rubber Stamp

**-SD-**  
**(D.B.Rajurkar)**  
Executive Engineer  
400 kV RS Division Kumbhargaoon, Nanded