

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,
EHV PC O&M ZONE, KARAD

Administrative Building
1st Floor Vijaynagar
Karad, 415114
Dist : Satara



Tel (O) : 02164 255054
(P) : 02164 646056
Fax : 02164 255186
E-mail:
cekarad@mahatransco.in

CE/EHV PC O&M/ZONE/KRD/T/384

Date :- 06.03.2024

Short SRM E-Enquiry

Sub- SRM E-Enquiry for Supply Installation & Commissioning of 82.5 KVA/66KW, 415 V Smart DG SET alongwith required accessories at EHV PC O&M Zone, Karad.

Ref- RFX No.7000030540.

Dear Sirs,

The offers from reputed & authorized dealers/channel partners are invited for the Supply Installation & Commissioning of 82.5 KVA/66KW, 415 V Smart DG SET alongwith required accessories at EHV PC O&M Zone, Karad, as per terms & conditions of Schedule 'A' enclosed herewith.

- DUE DATE:** The quotations complete in all respects, duly sealed & super scribed should be submitted to this office on or up to **11.03.2024, upto 10.00 HRs.**
- QUOTED RATES:** Rates should be inclusive of all such as material required if any, labour charges etc. The taxes applicable if any should be quoted distinctly.
- COMPLETION PERIOD:** 10 days from the date of order.
- VALIDITY OF OFFER:** The offer should be valid for our acceptance for a period of 60 days from the due date of opening.
- ESTIMATED COST:-** The total estimated cost is of Rs. 9,63,706/- (Incl. all taxes)
- The copy of following documents for the work under subject shall be enclosed with your offer.
 - Registration under PAN
 - Registration under GST.
 - Valid registration/ intimation under Bombay Shop & Establishment Act, Udyog Aadhar/Factories Act/Companies Act.
 - Valid Electrical Contractor licenses (If any or undertaking regarding completion of the work from Authorized Electrical Contractor).
 - Certificate of authorization of dealership/channel partner of the OEM.
 - Experience/Performance Certificate for similar type of work carried out in Govt. Sector/PSU's /Hospitals/Hotels
 - Proof of EMD & Tender Fees paid.

The undersigned reserves the right to reject any or all quotations without assigning any reasons.

Thanking you,

Note :- The item No. chosen is for 62.5 KVA DG Set in system for time being however, the requirement is of 82.5 KVA DG Set

Encl: 1. Schedule 'S'.
2. Schedule 'A'.

Yours faithfully,
(Shilpa S. Kumbhar)
Chief Engineer,
EHV PC (O&M) Zone, Karad
SD/-

Copy to: -

- 1) A.G.M. (F&A) PC O&M Zone Karad.
- 2) Notice Board.
M/F T

Schedule (S)
GENERAL TERMS AND CONDITIONS

1.	Taxes & Duties	:	The rates shall be inclusive of all taxes & duties. However GST @ 18% will be paid extra.
2.	Work completion Period.	:	You will have to complete the allotted work during period time as above stipulated period i.e. 15 days, from handing over of the site as per the instructions issued by Executive Engineer, EHV PC O&M Zone, Karad. There may be variations in quantity of actual work as per site required.
3.	Payment.	:	100% payment will be released only after satisfactory completion of work & after receipt bill. Your GST No. & Pan No. shall be quoted on Bills/ Invoice.
4.	Bill.	:	You have to submit your Invoice in triplicate to this office for further action.
5.	Penalty.	:	If the work is not completed within stipulated period of 10 days, the penalty @ 1% per delayed day maximum upto 10 % of contract value will be levied & deducted from your bill.
6.	Tools & Plants.	:	All required T&P, manpower & material is to be arranged by the contractor.
7.	Income tax.	:	Income Tax will be deducted from the bill, as per Govt. Rules.
8.	Insurance.	:	The insurance of your labours will have to be arranged at your cost. If failed to do so any compensation for claim arise will be at your responsibility.
9.	Responsibility.	:	The company will not be responsible for any accidents or damages caused due to the negligence of your personnel. You have to bear the Compensation to your personnel in case of any accident. You will be responsible for the safety of your employees, Insurance, Work Compensation as per Work Compensation Act 1910 & also safety for the general public & Company's property. You will have to observe at the traffic safety rules including providing of notice boards, red danger lamps, watchman etc. wherever required.
10.	Booklet.	:	The work shall be governed as per the Company's prevailing rules, the conditions & rules made under the MSETCL booklet of "Tender & Contract" for works, shall be applicable to this order also.
11.	Dispute.	:	In case of any disputes, the decision of the undersigned shall be final & binding on the contractor.
12.	Terms & Condition	:	a. Bidder should provide a Comprehensive Maintenance Contract for a period of 5 years from commissioning of the project. b. Performance Warranty for Smart DG Set will be for a period of 05 years from commissioning of the project. c. Payment Terms : The 80% payment against supply, 10% against erection balance 10% against commissioning. d. GST:- The GST @ 18% will be applicable. e. Security deposit:-The Security deposit @ 5% of the ex works contract value will be kept till successful operation for a period of 01 (One) year from commissioning.
13.	Jurisdiction.	:	All disputes or differences arising under / out of or in connection with this order shall be subject to exclusive jurisdiction of Karad court only.
14.	Power of Authority.	:	The undersigned reserves the right to cancel the quotations at any stage without assigning any reason whatsoever.

(Shilpa S. Kumbhar)
Chief Engineer
EHV PC (O&M) Zone, Karad
SD/-

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,
EHV PC O&M ZONE, KARAD
Schedule 'A'**

**SRM E- Enquiry for Supply Installation & Commissioning of 82.5 KVA/66KW,
415 V Smart DG SET alongwith required accessories at EHV PC O&M Zone, Karad.**

Sr. No.	Scope of Work	UoM	Qty	Ex Works Amt. in Rs.	Taxes @ %	Total Amt. in Rs.
1	82.5 KVA/66 KW SILENT Diesel Generating Set with acoustic enclosure, Radiator cooled, Diesel Engine developing minimum 101 BHP at 1500 RPM complete with standard accessories & DG Set controller with standard panel coupled to alternator rated at 82.5 KVA/ 66 KW at 415 V, mounted on channel iron based frame complete with fuel tank of suitable capacity, Sub base batteries, AVM & residential silencer.	No.	1			
2	AMF/ ATS panel suitable for 82.5 KVA/ 66 KW	No.	2			
3	Suitable earthing alongwith supply of required material	No.	4			
4	Aluminum/ copper armoured cable of 70 Sqmm of any standard make confirming to IS	Mtr	30			
5	1.5 Sqmm, 4 core standard make sensing cable	Mtr	30			
6	Flexible copper cable for ATS & mains connections	Mtr	30			
7	Lugs, cable, clips & other consumables if any	LS	1			
8	Transportation, unloading of DG set at site	LS	1			
9	Labour charges for erection, commissioning, testing, cabling & earthing	LS	1			

Remark :-1. The agency shall quote the rate per unit separately for each item.
2. The taxes such as GST shall be mentioned separately

Seal and signature of Agency

**Chief Engineer,
EHV PC O&M Zone, Karad.
SD/-**