



**MAHARASHTRA STATE ELECTRICITY  
TRANSMISSION COMPANY LIMITED**

**Government of Maharashtra (Undertaking)**

**CIN No. U40109MH2005SGCI53646**

From Executive Engineer,  
400KV R.S. (O&M) Div. Jejuri.

A/P: Jejuri. Tal: Purandhar

Dist: Pune, Pin code-412303

☎ 7447440530 e-mail: [ee6160@mahatransco.in](mailto:ee6160@mahatransco.in)



**EE/400KV/R.S./DIV/JEJURI/ 133**

**DATE: 10.04.2024**

**ENQUIRY**

**(Through MSETCL webpage)**

**TO WHOM SO EVER IT MAY CONCERN**

Dear Sir,

The budgetary offers through mail are invited Work of Annual maintenance of Air Conditioning system(Air Handling unit of 11 ton unit, make-CARRIER Aircon Ltd),15000CFM Boosters (make not available) & 2T Split A.C(make-CARRIER) at 400 kV RS Jejuri. as per Schedule 'A'. You are requested to quote your lowest rate for the said work in schedule "A".

**Scope of Work:** Mentioned in Schedule 'A'

**Schedule 'A'**

<b>Sr. No.</b>	<b>Particular</b>	<b>Unit</b>	<b>Per Unit Rate excluding GST</b>
<b>A</b>	<b>Supply Part of Air Conditioning system (Air Handling unit of 11 ton unit) includes</b>		
1	Contactora of Compressor	EA	
2	Expansion Valve	EA	
3	Compressor Suitable for CARRIER Air Conditioner	EA	
4	Freon Gas R-22	kg	
5	Compressor -V Belt	EA	
6	Air Conditioner Catch Well Filter	EA	
7	Air Conditioner Relay	EA	
8	A.C. O/D unit Fan Motor	EA	
9	A.C. Fan Blade	EA	
10	A.C. LP/HP Pressure Switch	EA	
11	A.C. Single Phase Preventer	EA	
12	11 Ton I/D Unit Blower (Aluminum)	EA	

13	Bearing	EA	
14	3-5 A Relay	EA	
15	T Window A.C. Condenser coil set	EA	
16	Condenser Motor 250-300V AC	EA	
17	½HP 1Ø 50Hz Motor	EA	
18	¾" Cu Pipe - A.C.	EA	
19	3P 415V 250A Power Contactor (CK09BE311)	EA	
20	Electrical panel for 11 Ton AC plant	EA	
21	4C*2.5 Sqmm, copper flexible cable	Mtr	
22	3-Ph, 5.5 Ton Compressor	EA	
23	8" Pulley	EA	
24	Pedestal Bearing (P210)	EA	
<b>B</b>	<b>Supply Part of 2T Split A.C includes</b>		
1	Split A.C. Fan Blower	EA	
2	Split A.C. PCB	EA	
3	Split A.C. I/d Fan Motor	EA	
4	2T Split A.C. O/d unit Fan Motor	EA	
5	2T A.C. Fan Blade	EA	
6	2T Split A.C. Compressor	EA	
7	Split A.C. Running Capacitor	EA	
<b>C</b>	<b>Services of Air Conditioning system (Air Handling unit of 11 ton unit) includes</b>		
1	Maintenance of A.C. Plant which includes Half Yearly maintenance of Central ACs, including cleaning of units, cooling coil, condenser coil, drain pipe, filters. Checking & Rectification in control panel, switch operation, motor operation, gas pressure, Gas Refilling, leakage, vibration etc. Checking of cooling efficiency , LP&HP Pressure switch, control Panel, Compressor terminal Clip, insulation on copper pipe and other general check up,vibration on outdoor unit and servicing in all respect of 6 Nos AC units.	Rate/Visit (EA)	
3	Arresting of Gas Leakage & Filling of Gas	EA	
4	Servicing of 11 Ton I/D Blower	EA	
5	Servicing of 11 Ton I/D Machine pulley	EA	
6	Replacement of contactor	EA	
7	Servicing of 11 Ton I/D machine connecting shaft	EA	
8	Fixing of pedestal Bearing	EA	
<b>D</b>	<b>Services of 2T Split A.C. includes</b>		
1	Repairing & Servicing of of 2T Air Conditioner per month.	EA	

2	Arresting of Gas Leakage & Filling of Gas	EA	
3	Replacement of contactor	EA	
<b>E</b>	<b>Services of 15000 CFM Booster includes</b>		
1	Servicing of 3-Ph 15Hp motor	EA	
2	Booster blower work	EA	
3	Installation of 8" pulley	EA	
4	Servicing of Impeller	EA	
5	Shafting work with fabrication	EA	
6	Canvas Connection work	EA	

**1) Please note that said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

**2) All interested bidders are requested to submit their best reasonable budgetary offer for above works on Email ID: [ee6160@mahatransco.in](mailto:ee6160@mahatransco.in) upto 12:00 Hrs on dtd.15.04.2024**

Thanking you,

Yours Faithfully,

-sd-

S.V.Kulkarni  
**Executive Engineer.**  
**400KV RS DIV Jejuri.**