



**MAHARASHTRA STATE ELECTRICITY
TRANSMISSION COMPANY LIMITED**

Government of Maharashtra (Undertaking)

CIN No. U40109MH2005SGCI53646

From Executive Engineer,
400KV R.S. (O&M) Div. Jejuri.

A/P: Jejuri. Tal: Purandhar

Dist: Pune, Pin code-412303

☎ 7447440530 e-mail: ee6160@mahatransco.in



EE/400KV/R.S./DIV/JEJURI/ 141

DATE: 16.04.2024

ENQUIRY(2nd Call)
(Through MSETCL webpage)
TO WHOM SO EVER IT MAY CONCERN

Dear Sir,

The budgetary offers through mail are invited Work of Annual maintenance of Air Conditioning system(Air Handling unit of 11 ton unit, make-CARRIER Aircon Ltd),15000CFM Boosters (make not available) & 2T Split A.C(make-CARRIER) at 400 kV RS Jejuri. as per Schedule 'A'. You are requested to quote your lowest rate for the said work in schedule "A".

Scope of Work: Mentioned in Schedule 'A'

Schedule 'A'

Sr. No.	Particular	Unit	Per Unit Rate excluding GST
A	Supply Part of Air Conditioning system (Air Handling unit of 11 ton unit) includes		
1	Contactora of Compressor	EA	
2	Expansion Valve	EA	
3	Compressor Suitable for CARRIER Air Conditioner	EA	
4	Freon Gas R-22	kg	
5	Compressor -V Belt	EA	
6	Air Conditioner Catch Well Filter	EA	
7	Air Conditioner Relay	EA	
8	A.C. O/D unit Fan Motor	EA	
9	A.C. Fan Blade	EA	
10	A.C. LP/HP Pressure Switch	EA	
11	A.C. Single Phase Preventer	EA	
12	11 Ton I/D Unit Blower (Aluminum)	EA	

13	Bearing	EA	
14	3-5 A Relay	EA	
15	T Window A.C. Condenser coil set	EA	
16	Condenser Motor 250-300V AC	EA	
17	½HP 1Ø 50Hz Motor	EA	
18	¾" Cu Pipe - A.C.	EA	
19	3P 415V 250A Power Contactor (CK09BE311)	EA	
20	Electrical panel for 11 Ton AC plant	EA	
21	4C*2.5 Sqmm, copper flexible cable	Mtr	
22	3-Ph, 5.5 Ton Compressor	EA	
23	8" Pulley	EA	
24	Pedestal Bearing (P210)	EA	
B	Supply Part of 2T Split A.C includes		
1	Split A.C. Fan Blower	EA	
2	Split A.C. PCB	EA	
3	Split A.C. I/d Fan Motor	EA	
4	2T Split A.C. O/d unit Fan Motor	EA	
5	2T A.C. Fan Blade	EA	
6	2T Split A.C. Compressor	EA	
7	Split A.C. Running Capacitor	EA	
C	Services of Air Conditioning system (Air Handling unit of 11 ton unit) includes		
1	Maintenance of A.C. Plant which includes Half Yearly maintenance of Central ACs, including cleaning of units, cooling coil, condenser coil, drain pipe, filters. Checking & Rectification in control panel, switch operation, motor operation, gas pressure, Gas Refilling, leakage, vibration etc. Checking of cooling efficiency , LP&HP Pressure switch, control Panel, Compressor terminal Clip, insulation on copper pipe and other general check up,vibration on outdoor unit and servicing in all respect of 6 Nos AC units.	Rate/Visit (EA)	
3	Arresting of Gas Leakage & Filling of Gas	EA	
4	Servicing of 11 Ton I/D Blower	EA	
5	Servicing of 11 Ton I/D Machine pulley	EA	
6	Replacement of contactor	EA	
7	Servicing of 11 Ton I/D machine connecting shaft	EA	
8	Fixing of pedestal Bearing	EA	
D	Services of 2T Split A.C. includes		
1	Repairing & Servicing of of 2T Air Conditioner per month.	EA	

2	Arresting of Gas Leakage & Filling of Gas	EA	
3	Replacement of contactor	EA	
E	Services of 15000 CFM Booster includes		
1	Servicing of 3-Ph 15Hp motor	EA	
2	Booster blower work	EA	
3	Installation of 8" pulley	EA	
4	Servicing of Impeller	EA	
5	Shafting work with fabrication	EA	
6	Canvas Connection work	EA	

1) Please note that said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.

2) All interested bidders are requested to submit their best reasonable budgetary offer for above works on Email ID: ee6160@mahatransco.in upto 12:00 Hrs on dtd.22.04.2024

Thanking you,

Yours Faithfully,

-sd-

S.V.Kulkarni
Executive Engineer.
400KV RS DIV Jejuri.