

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

From :
Name of Office : Superintending Engineer
Office Address : EHV (O&M) Circle, Panvel, Takka Colony, Panvel, Dist – Raigad - 410 206.
CIN No. : U40109MH2005SGC153646 **Contact No. :** 27459624/25 (O) ,27459405 (P)
Fax No. : 27458863 **Email ID :** se7200@mahatransco.in , sepanvell@gmail.com

SE/EHV (O&M) Circle/ PNL/Tech/ E-enquiry/ No 00967 Date : 26 APR 2024

Budgetary offer

Sub. : - Budgetary offer for supply of CCTV Camera at Hotline and PID Unit Kharghar, under EHV(O&M)Circle, Panvel.

Ref:- As per MSETCL Circular no. CE/MSETCL/VSH/F&A/No. 1996 dt. 27.07.2023

Dear Sir,

Please offer reasonable rates for the subject work as per the enclosed schedule 'A'. The detailed scope of works is given below. Please note the following:

RFx Number	Budgetary offer
Submission of Sealed and superscribed Quotations	Dt. 29.04.2024@10:00 Hrs to 03.05.2024@ 10:00 Hrs.
Last date submission of Quotation	On or Before Dt.03.05.2024@ 10:00 Hrs
Quotation opening date	03.05.2024@11:00 Hrs.(if possible)
Estimated Cost	

Contact Person :- The Executive Engineer(Admin), EHV(O&M)Circle, Panvel.
Contact No. 09769006131.

TERMS AND CONDITIONS :-

- 1] SCOPE of Work : Budgetary offer for supply of CCTV Camera at Hotline and PID Unit Kharghar , under EHV(O&M)Circle, Panvel as per the Schedule 'A' .
- 2] The prescribed form i.e Schedule 'A' duly filled in with the rates written in words and figures and signed should be sent by Registered post or in person to The Superintending Engineer EHV O&M Circle, Panvel.
- 3] Please Super scribe the offer with the following details :-
A] Quotation for :-
B] Due Date :-
C] Name of the Bidder :-
- 4] Quotations which do not fulfill all or any of the qualifying conditions or are incomplete in any respect are liable to be rejected.


- 5] Bidder should not submit "Conditional Quotations"; Such conditional offer shall liable for rejection.

Not stated herein with all other General Terms and Conditions of the contract with MSETCL will be applicable to this contract too.

Thanking you,

Encl: Schedule 'A'

Yours faithfully,



**SUPERINTENDING ENGINEER
EHV (O&M) CIRCLE, PANVEL**

Copy s.w.r.to:

The Chief Engineer, EHV PC (O&M) Zone, Vashi

Copy to: -

(1) The Manager (F&A). EHV (O&M) Circle, Panvel.

(2) The Adl. Executive Engineer, Hotline unit, Kharghar/PID Unit, Kharghar.


MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV (O&M) CIRCLE, PANVEL.

SCHEDULE 'A'

Sub - Budgetary offer for supply of CCTV Camera at Hotline Unit and PID Unit Kharghar,
under EHV (O&M)Circle, Panvel.

Sr. No.	Material Description	Unit	Qty	Rate	Amount
1	Supply, Installation, Testing & Commissioning of 2MP IP Network TDN IR Bullet Camera, 1/2.7", 2.0 megapixel, progressive scan, CMOS, Colour: 0.01Lux (F2.0, AGC ON) 0Lux with IR, 120dB, 4mm Fixed-focal, Up to 30m (98ft) IR range, Main Stream: 1080P (1920*1080), Max 30fps; 720P (1280*720), Max 30fps Sub Stream: 720P (1280*720), Max 30fps; D1 (720*576), Max 30fps; 640*360,Max 30fps; 2CIF(704*288), Max 30fps; CIF(352*288), Max 30fps;Micro SD, up to 128GB, ONVIF (Profile S, Profile G, Profile T), API, SDK, CE: EN 60950-1, UL: UL60950-1, IEC 60950-1, FCC: FCC Part 15, -30°C ~ 60°C (-22°F ~ 140°F), Humidity: ≤95% RH (non-condensing), Ingression protection: IP67, Vandal resistant: IK10 Make :- Mobotix/Axis/Honeywell/UNV	Nos	6		
2	Supply, Installation, Testing & Commissioning of 8 ch Network Video Recorder Two-way Audio Input 1-ch, RCA, Incoming bandwidth 160Mbps, Outgoing bandwidth 64Mbps, HDMI: 4K (3840x2160)@30, 1920x1080p@60, 1920x1080p@50, 1600x1200@60, 1280x1024@60, 1280x720@60, 1024x768@60 VGA:1920x1080p@60, 1920x1080p@50, 1280x1024@60, 1280x720@60, 1024x768@60, Corridor Mode Screen 3/4/5/7/92 SATA interfaces, Up to 8TB for each disk, VCA Search, Motion, Tampering, Human Body Detection, Video Loss, Alarm Input, Audio Detection, 2 RJ-45 10M/100M/1000M self adaptive Ethernet Interface, USB Interface Rear panel: 1 x USB2.0, 1 x USB3.0 Front panel: 1 x USB2.0, CE, FCC, UL, RoHS, WEEE, EN 55032: 2015, EN 61000-3-3: 2013, EN IEC 61000-3-2: 2019, EN 55035: 2017, FCC Part15 Subpart B, ANSI C63.4 Make :- Mobotix/Axis/Honeywell/UNV	Nos	1		
3	Supply, installation, testing and commissioning of 4TB HDD for storage of all cmaeras for 30 days at in RAID 5	Nos	1		
4	Supply, Supply, installation, testing and commissioning of Rack mountable Layer II Managed Ethernet switch with 8 ports RJ45 10/100/1000 with 2 Fibre Ports complete with required LIU's, LC Couplers, Plates etc complete as per specifications and as required for final installation and commissioning	Rmt	1		
5	Supply, installation, testing & commissioning of Cat 6 cables for CCTV outdoor camera	Nos	150		

6	Supply, Installation, Testing & commissioning of Display screen for Client PC 32" (for 24X7 working operations), LED Flat Screen HD with remote control, HDMI/VGA input and wall mount unit / floor Istand complete with all necessary accessories & peripheral items for civil, electrical works as required.	Rmt	1		
Total					
GST @ 18%					
GRAND TOTAL					



**SUPERINTENDING ENGINEER
EHV (O&M) CIRCLE, PANVEL**