



**MAHATRANSCO**  
Maharashtra State Electricity Transmission Co. Ltd.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

**From:-Office of The Executive Engineer,  
EHV(O&M) Division, Kalwa  
Brahmaputra Building, 2<sup>nd</sup> floor,  
Power House Complex, Post Box No 4, Airoli,  
Thane-Belapur Rd., Navi Mumbai- 400708.  
Tel. : 022- 2760 1919, FAX : 022- 2760 1919  
CIN No: U40109MH2005SGC153646  
Web Site:[www.mahatransco.in](http://www.mahatransco.in)  
E-mail ID – [eekalwa@gmail.com](mailto:eekalwa@gmail.com)**

Ref No.: EE / EHV/ O&M/ KLW/T- / 001007

Date: 26 APR 2024

**ENQUIRY**  
**(Through MSETCL webpage)**

To,  
WHOM SO EVER IT MAY CONCERN

**Sub.:** Enquiry for Supply of fully electronics Weighbridge of digital load cells IP68 having 60Tons capacity under EHV O&M Division Kalwa.  
..... **Submission of budgetary offers thereof**

This office has to be prepare an estimate for the work of supply of digital load cells IP68 rated pre-calibrated 60 Tons capacity load cell with full load capacity accurate at all corners & protection against lightening, rain water, dust etc. It is requested to offer your favorable budgetary rate for the subject work as detailed in the enclosed Price estimate.

- DUE DATE:** - The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office on or before due date i.e., Dt.06.05.2024 The published period of enquiry is from 29.04.2024 to 06.05.24.
- QUOTED RATES:** The quoted rates should include the of fully electronics Weighbridge of digital load cells IP68 having 60 Tons capacity including T&P and all incidental charges such as traveling/ transportation, accommodation etc.
- SCOPE of Work:** Work should be included "Supply of fully electronics Weighbridge of digital load cells IP68 having 60 Tons capacity under EHV O&M Division Kalwa". Scope of work shall also include mobilization & demobilization of manpower & material as required from contractor's base to execution site, labour, Supervisor, vehicles, lodging & boarding of engaged. labour, Tools & Plants, material, and any other services required for the execution of subject work.

**4. Technical Specification of work:**

Sr. No.	Description	Ex work Rate
	Supply of weighbridge of digital load cells IP68 having 60Tons capacity include following technology, Scope, Specification etc. 1) Mounting kit	

	2) Digital load cell 3) Junction Box 4) Cables 5) Intelligent indicates with SMS, Email & Pen drive facility. 6) Parallel display 7) Computer & Keyboard 8) MS Platform 9) Printer 10) Warrantee 1 year  <b>Specification: -</b> Capacity – 60Tons., Accuracy – 10Kg, Platform size – 9mtr x 3mtr. 11) Total load cell -6No.	
2	<b>Civil work for load cell &amp; its earthing, including MS Platform</b>	
3	<b>Installation of Weighbridge</b>	
4	<b>Civil work of 10x 10 feet weighbridge cabin with break work 4 side, metal sheet on top 1 door &amp; 2 windows with Vitrified tiles, electrification of rooms, 2 light point, 1 fan point &amp; 2 PowerPoint.</b>	

**Note :- Please mention & consider Labour Cess- Extra, GST-Extra , Freight & Insurance -Extra**

5. **DOCUMENT SUBMISSION:** The bidder should submit all the supporting and accompanying documents required for execution of work in sealed Envelope to this office.
6. **Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

Thanking you,

Yours faithfully,

  
**Executive Engineer,  
 EHV (O&M) Dn., Kalwa.**

- Copy to:** 1) The Manager (F&A), EHV (O&M) Dn., Kalwa.  
 2) Notice board.