

## MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD. CIN NO-U40109MH2005SGC153646

Executive Engineer, MSETCL, EHV O&M Dn., Sangli Office building, Vishrambag, Tal- Miraj Dist. Sangli- 416415 **Contact No.**–0233-2305816 (O), 0233- 2304872 (P), 0233-2304873 (F) **E-mail ID** – <u>ee3120@mahatransco.in</u> **Website** – <u>www.mahatransco.in</u> Ref No. EE/EHV O&M/DN/SGL/T/No. 766 Date **19 JUN 2024** 

## **BUDGETARY OFFER FOR ESTIMATE**

Please find herewith a detail schedule "A" & Scope of Supply of Digital clamp on Multimeter & Mini digital clamp leaker for EHV S/Stn under EHV O&M Division Sangli. All interested & experienced bidders are requested to submit their best lowest budgetary offer on the **Mail ID:-ee3120@mahatransco.in** for the same up to Dtd. 28/06/2024. Taxes should be quoted distinctly if any.

Please note that this budgetary offer is for estimation purpose only.

Sr. No.	Description	Unit	Qty	Rate Per Unit	% GST
1	Digital clamp on Multimeter (Tong tester):- True RMS, AC & DC current 40-600-1000 A, Resolution 0.1, 0.01, 1 A respectively. AC & DC voltage:- 600 V Resistance 4000 ohm, 6000 count display Clamp opening 37 mm with pouch Supply 9 V Battery Test leads- CAT III/CAT IV600 V with pouch	No.	19		
2	Mini digital clamp leaker (AC leakage clamp-on- meter) :- Display- 31/2 digit LCD Jaw size- Maximum up to 40mm Ø. Resolution- 0.01 mA resolution for measuring earth leakage currents. Range- 0-30mA/ 300mA/ 30 mA/ 300 A Size- Pocket size. Meter should measure leakage current & load current. Supply 9 V Battery	No.	4		

## SCHEDULE 'A' (SCOPE OF WORK)

Note:-1. Please Clearly Mention Taxes & Other Conditions.

2. Material should be ISI Mark & Reputed Mfg. mention Make, Model Data Sheet etc.

Yours faithfully, Sd/ Executive Engineer, M.S.E.T.C.Ltd, EHV O&M Dn, Sangli