



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
(CIN No. U40109MH2005SGC153646)

 <p>MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.</p>	<p>Name Of Office: EHV Projects Division ,Nasik Office Address: Prakash Kumbh Administrative building, Block No.08, Old Saikheda Road, Near Durgamata Temple, Jail Road, Nasik (422 101) Contact No.: 2403141 (O), 2403143(F) e-mail: ee5610@mahatransco.in ; Website: www.mahatransco.in</p>	 <p>वित्त श्रीतन्त्र्याभिषेक शके ३५०</p>
--	---	---

EE/EHV/PROJ/DIV/NSK/Tech/

No - 0899

Date:

11 JUL 2024

Srm e-enquiry

To,

Sub: SRM e-enquiry for work of shifting of 11kV line passing though newly proposed 400/220kV Pimpalgaon (Sarole) S/s, G. No 326/A, Sarola, Tal Niphad, Dist Nashik.

Ref: Addl EE/ EHV/Proj/SS/Sub-dn/NSK/20 Dt 11.01.2024

Dear Sir,

Online bids through Mahatransco SRM e-enquiry system from registered agencies in MSETCL SRM E-tendering system (website <https://srmetender.mahatransco.in>) are invited for work of shifting of 11kV line passing though newly proposed 400/220kV Pimpalgaon (Sarole) S/s, G. No 326/A, Sarola, Tal Niphad, Dist Nashik.

RFx No: 7000031892

Last date of bid is: 09.07.2024 till 10:00Hrs


TERMS & CONDITIONS:

1. **Scope of work:** The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule-B**.
2. The rates should be quoted on firm quotation basis including labor charges, T&P etc. required for execution of the work, transportation charges, & taxes if any.
3. All the instruments, T&P, vehicles, labors etc. shall be arranged by agency. No T&P or labor will be provided by the MSETCL.
4. The Contractor should furnish details of
 - i) Experience of similar nature of work of HT/LT line in the organization MSETCL/MSEDCL/Govt/Semi Govt,
 - ii) Electrical Contractor License,
 - iii) Bombay shop act certificate,
 - iv) GST Registration certificate,
 - v) PAN, TAN
 - vi) EMD & Tender fee paid proof etc. along with online bid.
5. Taxes will be applicable as per rule.

6. 10% Security Deposit is to be deposited in Crossed DD/Cheque before commencement of work. The same shall be refunded to you after the satisfactorily Completion of the work.
7. MSETCL will not be responsible If any damage is occurred to the contractor's equipment/T&P OR any accident to contractor's labors /personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.
8. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labor due to wrong operation shall be recovered from the bill.
9. Income tax will be deducted as per prevailing rules from the bill & a certificate to that effect will be issued to the contractor.
10. The work should be completed within 10 days from the date of handing over of clear work site, failure of such; penalty equal to ½ % per delayed week subject to the maximum of 10% of the ordered value will be levied.
11. The work should be strictly carried out as per standard specifications and up to the entire satisfaction of the Engineer-In charge.
12. The contractor will be abiding by the Rules & Regulations in force in respect of his employees & workmen under the Workmen's Compensation Act & the Contract Labor Act etc. He should be a registered contractor & documentary evidence of the same should be produced.
13. As per provision of 'Mumbai Mudrank Adhinyam, 1958 clause No.34' an agreement on appropriate value of stamp paper (not less than Rs 500/-) shall have to be executed with MSETCL for execution of contract satisfactorily before commencing work. The amount of the fees for such an agreement shall be borne by contractor.
14. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved by the undersigned.
15. The quantities enumerated in attached Schedule 'B' are approximate & payment will be made against actual executed quantities.
16. The rates quoted should be valid for 60 days.
17. Idle charges for any reason will not be accepted.
18. Not contained herein all other terms and conditions of MSETCL will be applicable to this enquiry
19. In case of any dispute regarding this contract, the jurisdiction of the court will be Nashik.

Thanking you,

Your's faithfully,


f Executive Engineer
EHV Projects Division
MSETCL, Nasik.
[o/c signed by EE]

Copy s.w.r.to,

1) The Superintending Engineer, EHV Projects Circle, MSETCL, Nasik.

Copy to,

1) The Manager (F&A), EHV Projects Division, MSETCL, Nasik.

2) Notice Board.

Schedule B

Sub: Work of shifting of 11kV line passing through newly proposed 400/220kV Pimpalgaon (Sarole) S/s,
G. No 326/A, Sarola, Tal Niphad, Dist Nashik.

Sr. No.	Particulars	Unit	Qty	Unit Rs.	Amount Rs.
A	Cost of material				
1	PSC Pole 9 Mtr (200kg)	No.	13		
2	11kV Guarding channel MS 75x40	Kg	110		
3	MS Channel 75x40x6 mm	Kg	100		
4	MS Angle 50x50x6 mm	Kg	60		
5	11kV V Cross arm with clamp	No.	13		
6	11kV Top fitting with clamp	No.	13		
7	MS Flats (50x10mm)	Kg	40		
8	11kV Pin insulators with G.I. Pins	No.	39		
9	Disc Insulators 11kV 70KN	No.	15		
10	Strain Hardware for 55 sq mm AAAC	Set	15		
11	AAAC 55 mm ²	km	2.7		
12	HT stay set	Set	6		
13	GI stay wire 7/4mm (8 SWG)	Kg	60		
14	Earthing sets HT	Set	15		
15	GI barbed wire 'A' type	Kg	50		
16	Danger Board in yard	No.	15		
17	Concreting ration 1:3:6	cmt	10		
18	GI wire 8 SWG/6 SWG	Kg	50		
19	GI Nut Bolts	Kg	30		
20	Sundries	LS	1		
21	Rabit to rabit equivalent AAAC	No.	3		
B	Dismantling of material				
1	HT LT fabrication removal	kg	120		
2	PSC pole	No.	8		
3	Removing of old conductor of any size, coiling and stacking etc & crediting with sdn/SO store	Span	9		
4	Transportation, loading & loading unloading on dismantled material (upto 5km)	Per pole	4		
5	Transportation, loading & loading unloading on dismantled material (beyond 5km) for 6km	Per pole/km	48		
C	Erection cost on material - 15%				
	Total cost of estimate (A+B+C)				

[Signature]
Executive Engineer
EHV Projects Division
MSETCL, Nasik.

[olc signed by EE]