



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

Office of The Executive Engineer  
400 KV R.S O&M Division, Kalwa  
PO Box No. 5 Airoli  
Navi Mumbai 400 708  
Phone No. 022-27601893, 94  
E-Mail :-ee7140@mahatransco.in  
CIN No.U40109MH2005SGC153646.

EE/400KV/RS/O&M/Dn/KLW/Tech/24-25/

000643

Date:- 06 AUG 2024

E-ENQUORY

(Through MSETCL webpage)

To,  
WHOM SO EVER IT MAY CONCERN


Sub:- Enquiry for Supply & installation of L&T/Siemens/Havels make ACB Retrofitting work under 400KV R S O&M Dn Kalwa.  
.....submission of budgetary offers thereof.

This office has to prepare estimate for L&T make ACB Retrofitting for various maintenance activities at 400 KV RS Kalwa and 220kV RS Kalwa under 400KV R S O&M Dn Kalwa. It is requested to offer your favorable budgetary offer for the subject work as detailed in the enclosed price estimate.

- 1. DUE DATE:-** The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office on or before due date i.e. 12.08.2024.
- 2. QUOTED RATES :-** The quoted rate should include the cost of all skilled & unskilled labour, and also the requisite consumables, labour cess, F&I,T&P and all incidental other charges such as traveling / transportation, accommodation etc.
- 3. DOCUMENT SUBMISSION:-** The bidder should submit all the supporting and accompanying documents (i. e. PAN, GST certificate, Shop & Establishment certificate etc.) required for execution of work in sealed Envelope to this office.
- 4. Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

Thanking you.

Yours faithfully,

  
Pankaj A. Shelar  
Executive Engineer  
400KV R.S. (O&M) Dn. Kalwa

Encl: Schedule 'A'.




MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.  
400KV RS O&M DN KALWA

Schedule A

Sub:- Supply & installation of L&T/Siemens/Havels make ACB Retrofitting work under 400KV R S O&M Dn Kalwa.

| Sr. No. | Description  | Unit | Ex Rate | Unit Rate |
|---------|--|------|---------|-----------|
| 1       | Supply of L&T/Siemens/Havels make Omega ACB Frame-1, 1000A, 4 pole, Electrical draw out type with MTX1.5G release for protection.  | Nos. |         |           |
| 2       | Supply of Retrofitting material such as Electrolytic grade Aluminum busbar suitable for 1000A rating along with wiring material, Indication lamp etc.  | Nos. |         |           |
| 3       | Service charges for carrying out L&T/Siemens/Havels make ACB retrofitting by dismantling and disconnection of existing Havells make ACB craddle, Busbar, control wiring etc. Fixing of New L&T ACB craddle with required modification to match existing ACB busbar etc. Fabrication of new busbar links to match existing Main busbar and cable end busbar using Cutting m/c, Punch m/c, Hydraulic Bending m/c etc. Carrying out control wiring for Electrical ON/OFF operation of ACB. Charging of ACB. | Job  |         |           |
| 4       | Design, Supply and Installation of Interlock logic scheme for Auto changeover in case of failure of any incomer with bus coupler and DG power using PLC relay logic Automation. Also carrying out interconnection cabling and wiring to PLC.   | Job  |         |           |

  
Executive Engineer  
400KV R.S. (O&M) Dn, Kalwa