

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

From: Executive Engineer, EHV O&M Division Boisar  
Office address: Office Of the Executive Engineer, MSETCL, EHV O&M Division Boisar, Khairaphata,  
At Vidyanagar, Post Saravali, Tal. & Dist. Palghar.  
Pin 401 501  
Contact No.: (O) 9167640570  
CIN No: U40109MH2005SGC153646  
Website: [www.mahatransco.in](http://www.mahatransco.in)  
Email Id. [ee7130@mahatransco.in](mailto:ee7130@mahatransco.in)

Ref. No.: EE/EHV/O&M/DN/BSR/Tech/Budgetary Offers/1499

Date: 25.10.2024

**Extension of Enquiry for Budgetary Offers**

To,  
WHOM SO EVER IT MAY CONCERN

**Sub.:** Budgetary Offer for replacement of existing 0.4 ACSR Conductor along with Hardware by equivalent 0.4 ACSS Bus Conductor & associated clamps & connectors required for 132kV A & B Bus at 220kV Boisar-II S/S under EHV O&M Division Boisar.

**Ref.:** EE/EHV/O&M/DN/BSR/Tech/Budgetary Offers/1131 dated 02.08.2024.

This office has to prepare estimate for replacement of existing 0.4 ACSR Conductor along with Hardware by equivalent 0.4 ACSS Bus Conductor & associated clamps & connectors required for 132kV A & B Bus at 220kV Boisar-II S/S under EHV O&M Division Boisar. It is requested to offer your favorable budgetary rate for the subject work as detailed in the enclosed Price estimate.

- 1) **DUE DATE:** The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office **on or before due date i.e. 04.11.2024 till 1:00 pm. If budgetary offers received after due date will not be accepted by this office.**
- 2) **QUOTED RATES:** The quoted rates should include the cost of all skilled & unskilled Labour, and also the requisite consumables, T&P and all incidental charges such as traveling/transportation, accommodation etc.
- 3) **SCOPE of Work:** Work should be invariably “replacement of existing 0.4 ACSR Conductor along with Hardware by equivalent 0.4 ACSS Bus Conductor & associated clamps & connectors required for 132kV A & B Bus”. Scope of work shall also include mobilization & demobilization of manpower & material as required from contractor’s base camp to execution site, labour, Supervisor, vehicles, lodging & boarding of engaged labor, Tools & Plants, material and any other services required for the execution of subject work.
- 4) **Technical Specification of work:**  
484.50 mm<sup>2</sup> ACSS Zebra Conductor and its hardware

5) **DOCUMENT SUBMISSION:** The bidder should submit all the supporting and accompanying documents (i.e., technical specification, drawing etc.) required for execution of work in sealed Envelope to this office.

6) **Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

Encl.: Schedule 'A'



(Rajesh Dakhane)  
Executive Engineer  
EHV O&M Division Boisar

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

**EHV O&M Division Boisar**

**Schedule 'A'**

**Sub:** Estimate for replacement of existing 0.4 ACSR Conductor along with Hardware by equivalent 0.4 ACSS Bus Conductor & associated clamps & connectors required for 132kV A & B Bus at 220kV Boisar-II S/S under EHV O&M Division Boisar.

<b>Sr. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Ex-Works Rate.</b>
1)	0.4 ACSS Conductor - 484.50mm <sup>2</sup> (484.50mm <sup>2</sup> cross section)	km	
2)	DSN H/w suitable for 484.50mm <sup>2</sup> ACSS Zebra conductor.	No.	
3)	T Connector Twin-Single with Palm & Nut Bolts suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
4)	T Connector Twin-Twin with Palm & Nut Bolts suitable for 484.50 mm <sup>2</sup> Zebra conductor.	No.	
5)	Twin Spacer (225mm, 140mm) suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
6)	Repair Sleeves suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
7)	DTN H/w suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
8)	Mid Span Joint suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
9)	Isolator palm suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
10)	Bimetallic plates suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
11)	BPI clamp suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
12)	BPI support suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
13)	CB Palm (12 holes) suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
14)	CT clamp with palm suitable for 484.50 mm <sup>2</sup> ACSS Zebra conductor.	No.	
15)	L Type spacer plate suitable for twin connection spacing distance 225mm.	No.	

- Note:**
- 1) Ex-Works rates should be exclusive of Labour cess@1% & Freight & Insurance@2% etc.).
  - 2) Applicable Taxes should be quoted separately.
  - 3) The Budgetary offer should be valid for 120 days from due date of opening.
  - 4) Preference shall be given to MSETCL's registered vendors having subject experience.
  - 5) Lowest rates of respective material/services from all budgetary offers will be considered for preparation of estimate, however abnormally high or low rates will not be considered. Please be noted.



(Rajesh Dakhane)  
Executive Engineer  
EHV O&M Division Boisar

**Copy to:**

- 1) The Dy. Manager (F&A), EHV O&M Division Boisar.
- 2) Notice Board, Division Office, EHV O&M Division Boisar.