



|   |   |  |
|---|---|--|
|  <p><b>MAHATRANSCO</b><br/>Maharashtra State Electricity Transmission Co. Ltd.</p> | <p><b>OFFICE OF THE EXECUTIVE ENGINEER<br/>EHV PROJECTS DIVISION-III, SOLAPUR</b><br/><b>CIN. NO. U40109MH2005SGC153646</b><br/>M.S.E.T.Co. Ltd, 132 kV, Navives S/Stn.<br/>Premises Old mill Compound, Solapur-413001<br/>E-Mail: ee6630@mahatransco.in<br/>Phone No. (0217) 2320181</p> |  |
|---|---|--|

No. EE/EHV/PD-III/Solapur/1395

Date: 21/11/2024

## Re-ENQUIRY

**Sub:-** Re-enquiry for shifting of 33 kV line at Gut no 168/1, Jeurwadi, Tq. Karmala, Dist. Solapur.

Sealed and superscripted quotations are invited for the work as detailed below with subject to following terms & conditions.

### TERMS & CONDITIONS:

- 1) The rate should be quoted on firm quotations basis.
- 2) The rate should be provided as per schedule A format as enclosed with clear bifurcations of taxes.
- 3) The Total work amount should be limited to **Rs. 8,45,000/-** only (Rs. Eight Lakhs Fourty Five Thousand only).
- 4) Your sealed quotations should reach this office on or before up to **Dt.-27/11/2024**.
- 5) Quotation shall be sent under sealed cover duly subscribed as our Enquiry No & Quotation for "**E-enquiry for shifting of 33 kV line at Gut no 168/1, Jeurwadi, Tq. Karmala, Dist. Solapur.**" in block letters.
- 6) The service provider should provide similar work experience certificate.
- 7) The offer shall be valid for acceptance for the period of **3** months from the date of submission.
- 8) The entire work as per the scope in schedule "A" is to be completed within a period of 30 days from the date of handing over of the clear site for work.
- 9) All the documents i.e. PAN card, GST registration, etc. and other accompanying documents like Shop Act, Electrical Contractor License, similar work experience, shall bear the authorized signature of agency, failing which the offer will be liable for rejection.
- 10) The material shall be guaranteed for a period of **One year (01 Year)** from the date of supply. If any defect is observed during guarantee period the same will have to be replaced / attended free of cost or as specified by manufacturer whichever is higher.
- 11) If contractor fails to execute the order, it will be treated as breach of contract & contract will be terminated & order will be cancelled by forfeiting the EMD/Security Deposit.

- 12) The material supplied for this work must be in line with MSETCL specifications & its inspection should be arranged by you before fixing it on site.
- 13) Permission from Electrical Inspector should be arranged from your end.
- 14) If any ROW arises contractor should resolve the same. MSETCL will provide only necessary technical co-operation as per MSETCL term & conditions.
- 15) Engineer in charge: The Additional Executive Engineer, EHV Lines Projects Subdivision, MSETCL, Pandharpur shall be the Engineer-in-charge for execution of this work
- 16) Material Inspection: The undersigned or our authorized representative will be free to visit the contractor site stores and also verify the materials in custody of the contractor as and when required at any time.
- 17) Manpower & T& P: All the instruments, T&P, vehicles, labors etc. required for this work shall be arranged by agency. No T&P or labour will be provided by the MSETCL.
- 18) Accident & loss: If any accident is occurred to your staff during the execution of work, the whole responsibility lies on you. Also if any loss is occurred during the work to the MSETCL's property, the whole cost of equipments will be recovered from your bills or anywhere pending with MSETCL.
- 19) Contractor's Employees: Contractor should employ & provide only such employees who are skilled & experienced for execution & supervision of such type of works.
- 20) Jurisdiction of court: In case of dispute if any, legal jurisdiction of the Court shall be in Solapur only.
- 21) The undersigned has reserved the right to modify or cancel the order at any stage without assigning any reason thereof and without any liability on MSETCL.

Thanking You,

**Sd/-**  
(Mr. S.F. Deshmukh)  
Executive Engineer  
EHV Proj. Div-III, Solapur

Encl:- Schedule A

Copy s.w.rs.to:-

1) The Superintending Engineer, EHV Projects Circle, Pune -

Copy to

1) The Manager (F&A), Proj. Div-III, Solapur

2) The Addl. Executive Engineer EHV S/Stn Proj. S/Dn, Pandharpur

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.  
EHV PROJECTS DIVISION-III, SOLAPUR.**

**Schedule A**

**Sub:-** Re-enquiry for shifting of 33 kV line at Gut no 168/1, Jeurwadi, Tq. Karmala, Dist. Solapur.

| Sr No | Description of Material                                     | Unit | Qty  | Rate / Un (Rs.) | Amount |
|-------|---|------|------|-----------------|--------|
| 1     | RSJ 152x152.12 m Inn <sub>e</sub>                           | No.  | 9    |                 |        |
| 2     | RSJ 152x152,11 m long                                       | No.  | 1    |                 |        |
| 3     | 33 KV V Cross Arm.  | No.  | 3    |                 |        |
| 4     | 33 KV Top Fitting   | No.  | 3    |                 |        |
| 5     | Cutpoint channel -33/22 KV                                  | Kg   | 2    |                 |        |
| 6     | MS Channel 100x50x6 mm                                      | Kg.  | 250  |                 |        |
| 7     | M.S.Channel 75x40x6 mm                                      | Kg.  | 58   |                 |        |
| 8     | MS angle 50x50x6 mm   | Kg.  | 80   |                 |        |
| 9     | MS Flat 75x10 mm  | Kg.  | 30   |                 |        |
| 10    | G.I.Nut Bolts   | Kg.  | 50   |                 |        |
| 12    | 33 kV Pin Insulators with G.I. Pins                         | NO   | 27   |                 |        |
| 13    | Disc Insulator 11 KV 70 KN                                  | No.  | 66   |                 |        |
| 14    | AAAC100 mm2   | Rmt  | 3150 |                 |        |
| 15    | Strain Hardware for Dog O.I or Equ.AAAC.                    | No.  | 22   |                 |        |
| 16    | H.T.Stay Set  | No.  | 3    |                 |        |
| 17    | G.I.Stay Wire 7/4mm(8 SWG)                                  | Kg.  | 30   |                 |        |
| 18    | G.I.Wire 8 SWG/ 6 SWG                                       | Kg.  | 45   |                 |        |
| 19    | Danger Board in yard.                                       | No.  | 9    |                 |        |
| 20    | Earthing Sets H.T   | Set  | 9    |                 |        |
| 21    | G.I.Barbed Wire 'A' type.                                   | Kg   | 45   |                 |        |
| 22    | Black Bituminus Paint                                       | Ltr. | 4    |                 |        |
| 23    | Red Oxide Paint for 2 coats                                 | Ltr. | 12   |                 |        |
| 24    | Aluminium Paint for one coats                               | Ltr. | 4    |                 |        |
| 25    | Concreting ration 1:3:6                                     | cmt. | 8    |                 |        |
| 26    | Sundries  | L.S. | 5    |                 |        |
|       | <b>Total</b>  |      |      |                 |        |
| A     | <b>Cost of Material (To be taken as per Cost Data 22-3)</b> |      | =    |                 |        |
| B     | Erection charges (Labour)                                   |      | —    | 15%             |        |
| C     | Dismantling   |      | =    |                 |        |
| D     | <b>Total Estimate Cost (without GST)</b>                    |      | =    |                 |        |
| E     | GST   |      | =    | 18%             |        |
| F     | <b>Sub-Total-I</b>  |      | =    |                 |        |

**Sd/-**  
(Mr. S.F. Deshmukh)  
Executive Engineer  
EHV Proj. Div-III, Solapur