



| | | |
|---|--|--|
|  <p>MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.</p> | <p>OFFICE OF THE EXECUTIVE ENGINEER EHV PROJECTS DIVISION-III, SOLAPUR CIN. NO. U40109MH2005SGC153646 M.S.E.T.Co. Ltd, 132 kV, Navives S/Stn. Premises Old mill Compound, Solapur-413001 E-Mail: ee6630@mahatransco.in Phone No. (0217) 2320181</p> |  |
|---|--|--|

No. EE/EHV/PD-III/Solapur/1394

Date: 21/11/2024

Re-ENQUIRY

Sub:- Re-enquiry for providing HT line for 3ph connection at 132 kV Barshi TSS.

Sealed and superscripted quotations are invited for the work as detailed below with subject to following terms & conditions.

TERMS & CONDITIONS:

- 1) The rate should be quoted on firm quotations basis.
- 2) The rate should be provided as per schedule A format as enclosed with clear bifurcations of taxes.
- 3) The Total work amount should be limited to 3.47 Lakhs Rupees only.
- 4) Your sealed quotations should reach this office on or before up to **Dt.- 28/11/2024.**
- 5) Quotation shall be sent under sealed cover duly subscribed as our Enquiry No & Quotation for **"Re-enquiry for providing HT line for 3ph connection at 132 kV Barshi TSS"** in block letters.
- 6) Service provider has to submit Certificate of Experience for the execution of similar work in Govt. Organization as well as private sector duly signed by the officer not below the rank of Executive Engineer or equivalent in case of Govt. works or from authorized authority of Private sector along with copies of work orders mentioned in the certificate for private sector work.
 - a) *One work order for work mentioned above, with completed work cost not less than the amount equal to 60% of the estimated cost.*
 - OR**
 - b) *ii) Two work orders for work mentioned above, with completed works each costing not less than the amount equal to 30% of the estimated cost.*
 - OR**
 - c) *iii) Three work orders for work mentioned above, with completed works each costing not less than the amount equal to 20% of the estimated cost.*
- 7) The offer shall be valid for acceptance for the period of **3** months from the date of submission.
- 8) The entire work as per the scope in schedule "A" is to be completed within a period of 60 days from the date of handing over of the clear site for work.

- 9) All the documents i.e. PAN card, GST registration, ITR- Balance sheet & GST return for last 3 financial years (2020-21, 2021-22 & 2022-23) etc. and other accompanying documents like Shop Act, Electrical Contractor License & labor license shall bear the authorized signature of agency, failing which the offer will be liable for rejection.
- 10) The material shall be guaranteed for a period of **One year (01 Year)** from the date of commissioning. If any defect is observed during guarantee period the same will have to be replaced / attended free of cost or as specified by manufacturer whichever is higher.
- 11) If contractor fails to execute the order, it will be treated as breach of contract & contract will be terminated & order will be cancelled by forfeiting the EMD/Security Deposit.
- 12) The material supplied for this work must be in line with MSEDCL/MSETCL specifications & its inspection should be arranged by you before fixing it on site.
- 13) Permission from Electrical Inspector should be arranged from your end.
- 14) If any ROW arises contractor should resolve the same. MSETCL will provide necessary technical co-operation as per MSETCL term & conditions.
- 15) Engineer in charge: The Additional Executive Engineer, EHV S/Stn Projects Subdivision Pandharpur shall be the Engineer-in-charge for execution of this work.
- 16) Material Inspection: The undersigned or our authorized representative will be free to visit the contractor site stores and also verify the materials in custody of the contractor as and when required at any time.
- 17) Manpower and T & P: All the instruments, T&P, vehicles, labors etc. required for this work shall be arranged by agency. No T&P or labour will be provided by the MSETCL.
- 18) Accident & loss: If any accident is occurred to your staff during the execution of work, the whole responsibility lies on you. Also if any loss is occurred during the work to the MSEDCL/MSETCL's property, the whole cost of equipments will be recovered from your bills or anywhere pending with MSETCL.
- 19) Contractor's Employees: Contractor should employ & provide only such employees who are skilled & experienced for execution & supervision of such type of works.
- 20) Jurisdiction of court: In case of dispute if any, legal jurisdiction of the Court shall be in Solapur only.
- 21) The undersigned has reserved the right to modify or cancel the order at any stage without assigning any reason thereof and without any liability on MSETCL.

Thanking You,

Sd/-

(Mr. S.F. Deshmukh)
Executive Engineer
EHV Proj. Div-III, Solapur

Encl:- Schedule A

Copy s.w.rs.to:-

1) The Superintending Engineer, EHV Projects Circle, Pune

Copy to

1) The Manager (F&A), Proj. Div-III, Solapur

2) The Addl. Executive Engineer EHV S/Stn Proj. S/Dn, Solapur.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV PROJECTS DIVISION-III, SOLAPUR**

'Schedule A'

E-enquiry for providing HT line for 3ph connection at 132 kV Barshi TSS.

| Sr. No. | Description of Material (DTC) | Unit | Qty | Ex- Work Rate / Unit (Rs) | 18% GST Amount (Rs)/ Unit | Total Amount (Rs) |
|---------|--|------|-------|---------------------------|---------------------------|-------------------|
| | DTC | | | | | |
| 1 | Dist. transformer 25KVA,11/.433KV | No. | 1 | | | |
| 2 | RSJ 116x100, 9 m long | No | 2 | | | |
| 3 | MS Channel 100x50x6 mm | Kg. | 100 | | | |
| 4 | M.S.Channel 75x40x6 mm | kg. | 44 | | | |
| 5 | MS angle 50x50x6 mm | kg. | 22 | | | |
| 6 | M.S.Flat 50 x 6 mm | kg. | 24 | | | |
| 7 | 11 kV Pin Insulators with G.I. Pins | No. | 3 | | | |
| 8 | Strain Hardware for Dog0.1 or Equ.AAAC. | No. | 3 | | | |
| 9 | L.T.Dist.Boxes 25/63 KVA with MCCB | No. | 1 | | | |
| 10 | L.As. 11 KV (Gapless type) with disconnector | Set. | 1 | | | |
| 11 | H.T.Stay Set | No | 4 | | | |
| 12 | G.I.Stay Wire 7/4mm(8 SWG) | kg. | 25 | | | |
| 13 | Earthing Sets H.T | No. | 3 | | | |
| 14 | 11KV H.G.Fuses | Set. | 1 | | | |
| 15 | 11KV A.B. Switch, 400A | No. | 1 | | | |
| 16 | Danger Board in yard. | No. | 2 | | | |
| 17 | G.I.Wire 8 SWG/ 6 SWG | Kg. | 25 | | | |
| 18 | G.I.Barbed Wire `A' type. | kg. | 15 | | | |
| 19 | DTC Metring with Box, single core L.T. XLPE cable (16 sq.mm., 120 mtr length) and other allied material. | No. | 1 | | | |
| 20 | Sundries | L.S. | 1 | | | |
| | Total Rs | | | | | |
| | | | | | | |
| 1 | Survey | LS | 1 | | | |
| 2 | Concreting ration 1:3:6 | CMT. | 2 | | | |
| 3 | Painting/Hardware & support with numbering of pole | L.S. | 1 | | | |
| | Total Rs | | | | | |
| | | | | | | |
| | HT line | | | | | |
| 1 | RSJ 116x100, 9 m long | No. | 0 | | | |
| 2 | RSJ 116x100, 11 m long | No. | 3 | | | |
| 3 | 11 kv guarding channel MS 75x40 | Kg. | 18.72 | | | |
| 4 | M.S.Channel 75x40x6 mm | Kg. | 21.96 | | | |
| 5 | MS angle 50x50x6 mm | Kg. | 12.96 | | | |
| 6 | M.S. Flats(50 X 10mm) | Kg. | 15 | | | |
| 7 | 11 KV V cross arm with clamp | No. | 3 | | | |

| | | | | | | |
|----|---|------|------|--|--|--|
| 8 | 11 KV Top fitting with clamp | No. | 3 | | | |
| 9 | 11 kV Pin Insulators with G.I. Pins | No. | 9 | | | |
| 10 | Disc Insulator 11 KV 70 KN | No. | 3 | | | |
| 11 | Strain Hardware for 34 Sq.mm AAAC | Set | 3 | | | |
| 12 | ACSR Weassel | Rmt | 567 | | | |
| 13 | H.T.Stay Set | Set | 3 | | | |
| 14 | G.I.Stay Wire 7/4mm(8 SWG) | Kg. | 30 | | | |
| 15 | Earthing Sets H.T | Set | 3 | | | |
| 16 | G.I.Barbed Wire `A' type. | Kg. | 12 | | | |
| 17 | Danger Board in yard. | No. | 3 | | | |
| 18 | Black Bituminus Paint | Ltr. | 1.08 | | | |
| 19 | Red Oxide Paint for 2 coats | Ltr. | 3.6 | | | |
| 20 | Aluminium Paint for 1 coat | Ltr. | 1.62 | | | |
| 21 | G.I.Wire 8 SWG/ 6 SWG | Kg. | 23.4 | | | |
| 22 | G.I.Nut Bolts | Kg. | 14.4 | | | |
| 23 | Sundries | LS | 0.18 | | | |
| 24 | RABIT To RABIT or equivalent AAAC | No | 3 | | | |
| | | | 0.00 | | | |
| 1 | Concreting ration 1:3:6 | Cmt. | 3 | | | |
| | | | | | | |
| a | Total amount (Supply) Rs. | | | | | |
| b | Erection charges (Labour) 15% on total of ex work | | | | | |
| c | 18% GST on Sr. no b | | | | | |
| d | Total amount of Supply + Erection (sr. no a+b+c) | | | | | |
| e | Total Amount (Incl. all taxes) | | | | | |

Sd/-
(Mr. S.F. Deshmukh)
Executive Engineer
EHV Proj. Div-III, Solapur