



(CIN No. U40109MH2005SGC153646)

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
INTRA OFFICE COMMUNICATION

Name of Office	: Executive Engineer, EHV Projects Division, Kolhapur
Office address	: Vidyut Bhavan, Admm. Building, 2nd Floor, Tarabai Park, Kolhapur.
Contact No.	: 0231- 2665320 (P), 0231- 2655937 (O), 0231-2666798 (FAX)
E-Mail	: ee3610@mahatransco.in

Ref. : EE/EHV Projects/Dn./Kop/E-Enquiry/No

No - 1272

Date :

28 NOV 2024

Sub : E-Enquiry for the work of shifting of 3 phase 4 wire LT line -0.48 Kms & supply & erection of 1 Phase 2 wire LT line - 0.15 Kms for up gradation of 110KV SC Mudshingi - Puikhadi Line to 132KV SCDC.

Dear Sir,

The sealed & subscribed quotations are invited for the work of shifting of 3 phase 4 wire LT line -0.48 Kms & supply & erection of 1 Phase 2 wire LT line - 0.15 Kms for up gradation of 110KV SC Mudshingi - Puikhadi Line to 132KV SCDC as per the Schedule 'A' attached herewith subject to following terms & conditions.

TERMS AND CONDITIONS :

- 1) The quotations should reach to this office on or before **07.12.2024 upto 16.00 Hrs.** This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- 2) The contractor has to furnish GST, PAN No. in the offer.
- 3) The following documents shall be submitted with the offer,
 - a. Valid copy of Electrical contractors license issued by Govt. of Maharashtra.
 - b. Registration under works contract Act.
- 4) The bidder should have an experience of more than 3 years in execution of similar work.
- 5) The rates quoted by the bidder, shall be considered as inclusive of GST & all other duties, taxes other levies LW Cess, IT etc. which are payable by the contractor as per statutory regulations.
- 6) Income tax & Labour welfare cess shall be deducted from the bills at prevailing rates, as per Income Tax Act 1961.
- 7) Bids shall remain valid for 60 days after the date of bid opening prescribed by the employer.
- 8) **The estimated amount towards the said work by MSEDCL is 1,89,099/-**
- 9) Security Deposit
Within Fifteen (15) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 5% of the contract value by cash/ cheque/DD.
- 10) Period : The time period for completion of the item under Schedule 'A' under this contract will be 1 Month. The period shall be entitled from date of handing over of the site.

- 11) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.
- 12) Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer after proper measurements and scrutiny of bills at concerned Sub-Division Office.
- 13) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 14) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost.
- 15) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 16) The contractor shall not sub-let the works awarded on him under this contract.
- 17) The contractor shall arrange for posting his own security personnel at his own cost to safeguard the material handed over to him not only at his storage yard but also at the work site till such time the complete job is ultimately handed over to Maharashtra State Electricity Transmission Company Ltd.
- 18) Guarantee - The work executed under this contract shall be guaranteed for 12 months from the date of completion of work.
- 19) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 20) Quotation incomplete in any respect shall be rejected.
- 21) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 22) Quotation received late or with incomplete details against above clauses will not be considered.
- 23) Labour welfare cess /GST/other statutory payment etc. considered in contract value will be deducted at appropriate rate prevailing during tenure of contract.

Thanking You.

Yours faithfully,



**Executive Engineer,
EHV Projects Dn. Kolhapur.**

Encl. : Schedule A.

Copy s.w.rs. to : The Suptd. Engineer, EHV Projects Circle, Kolhapur.

Copy to :

- 1) The Addl. Executive Engineer, EHV Line Projects S/Dn.II, Kolhapur.
- 2) The Manager (F&A) EHV Projects Dn. Kolhapur.
- 3) Notice Board.
- 4) MSETCL, Website.

M/F.

EHV PROJECTS DIVISION, KOLHAPUR


"SCHEDULE - A"

Name of Work : The work of shifting of 3 phase 4 wire LT line - 0.48 Kms & supply & erection of 1 Phase 2 wire LT line-0.15 Kms for up gradation of 110KV SC Mudshingi - Puikhadi Line to 132KV SCDC .

Sr. No.	Description of work	Unit	Quantity	Amount In Rs.
1	Shifting of 3 phase 4 wire LT line -0.48 Kms & supply & erection of 1 Phase 2 wire LT line-0.15 Kms for up gradation of 110KV SC Mudshingi- Puikhadi Line to 132KV SCDC Dist. Kolhapur including supply & erection of 7 Nos. RSJ poles, stay wire, brackets, angles, G.I. Flat Shackle Insulators, Earthing sets, hardwares, Nut bolts all required material alongwith required civil foundation painting & all allied works. As per the Annexure - I, as directed by the Engineer Incharge.	No	LS	

Note : (1) All the required T&P shall be arranged by the contractor.

(2) The work shall be executed strictly as per the norms of MSEDCL.


Executive Engineer,
EHV Projects Dn. Kolhapur.

EHV PROJECTS DIVISION, KOLHAPUR

"ANNEXURE - I"

Sr. No.	Description of Materials Required	Unit	Quantity
1 a	LT pole RSJ 125X70X6mmX8 Rmt,13Kg/Rmt	No.	7
b	MLT pole RSJ Stud	Kg.	2
2	L. T. Stay set	Set	5
3	L. T. Stay wire 7/10 swg	Kg	40
4	L.T. Stay Insulator	NO.	5
5	L.T.Stay clamps 2.97KG(F 50X10)	pair	5
6	L.T.Shackle Insulators	No.28	28
7	L.T.Hardware 0.732Kg(F 50X6) Rate	pair	40
8	U CLAMPS	No.	40
9	AL Bobbin	No.	12
10	G.I. Nutbolts	Kg.	10
11	AAAC conductor Weasle of 55S qm	No.	0.15
12	AAAC Conductor weasle	No.	0.15
13	L.T. Earthing Set	Set	2
14	Concreting of pole & stays	Km.	6



**Executive Engineer,
EHV Projects Dn. Kolhapur.**