

**OFFICE OF THE :-
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administrative Building, first Floor,
wing no.102, Chhatrapati Sambhajnagar, Ph. No.(0240) 2331429,
E-mail :ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ CSN /Tech

000664

Date:- 3 DEC 2024

E-enquiry

To,

.....
.....
.....

Sub: E-Quotation Enquiry for the Work of Construction of 02 No of CTR FPFES foundation & Allied civil works at 220 KV S/S MIDC Jalna, Dist. Jalna.

Dear Sir,

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Mahatransco Administrative Building, first Floor, wing no.102, Chhatrapati Sambhajnagar on or **before dated.09/12/2024 Time 13.00 Hrs.**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(15)Days** from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.


Note: Vendors are requested to taking note that Work is of Urgent nature, should be start immediately and to be completed within given time limit, failing of which suitable action will be taken.

- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub Division, MSETCL, Chhatrapati Sambhajanagar. to the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit **Rs.32,000/-**(5% of quotation value) as security deposit in cash/ DD/FDR of any nationalized Bank within 7 days from the date of receipt of work order, failing which EMD will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.

- 18) The contractor who is registered vendor in MSETCL has to pay earnest money to Rs.6400/- in cash/RTGS/NEFT any Nationalized Bank in favor of Executive Engineer(C) EHV CCCM Division, MSETC Ltd. Chhatrapati Sambhajanagar. And Money Receipt shall be obtained from Account Section EHV CCCM Division, Chhatrapati Sambhajanagar. If the MR Copy of EMD required amount is not found in the envelop the quotation will be rejected. The Bank Account Details are as follows Bank of Baroda Account No.04600200000009 IFSC Code: BARB0AURANG, Chhatrapati Sambhajanagar- 431001
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) Special condition: The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is **Rs.6,30,807.31/-** only. (Inclusive of all Taxes)
- 23) Contractor has to submit Civil Works Registration Certificate, GST registration certificate, EMD paid receipt, PAN Card, & Work Experience certificate, as a mandatory documents at the time of submission of Quotation.
- 24) Agency is instructed to subscribe on top of envelop "**Quotation for the work of - Name of work**" and detail address along with valid e-mail ID and contact number. Please note that the any correspondence in regard to the work if any will be done through e-mail only. Hence agency's are requested to provide the valid e-mail currently in use for the communication and to check the e-mail ID regularly for to get information of communication if any. This office will not be responsible, if office unable to communicate to you due to invalid e-mail provided by you.
- 25) As per revised circular issued by Dy. Directorate of Insurance Maharashtra State vide letter No. क्र.प्रविनी- 2314/ देयक कपात रकम/ संकीर्ण/ अभि-3,दिनांक.31/03/2015, MSETCL/CO/C&M/PT/TKC-II/No.8450 dtd.30.11.2022, Government Resolution (GR) No.Sankirn-2018/pr.kr.47/CR-174/ Vima Prashasan dtd. 13.09.2022 issued by Government of Maharashtra Finance section the contractor shall, apart from other relevant insurance, submit labour insurance amounting to Rs.1% of Work Order Amount to EHV CCCM Division, MSETCL, Chhatrapati Sambhajanagar before starting of the work. The insurance cover shall be procured by the contractor from "विमा संचालनालय, महाराष्ट्र राज्य, गृहनिर्माण भवन, २६४, पहिला मजला, कलानगर समोर, वांद्रे (पूर्व), मुंबई-४०००५१(दूरध्वनी क्र.२६५९०४०३ व फॅक्स क्रमांक.२६५९२४६१".)

- 26) The Vendor should be registered with the MSETCL while submitting the quotation and registration number should be mentioned on top of envelope. The Vendors are requested to take note that quotation received without details of the valid registration of MSETCL will not be considered and will be rejected.

Encl: Schedule 'B'



(S.M. Banait)

Executive Engineer (C)
EHV CCCM Division, MSETCL,
Chhatrapati Sambhajanagar.

Copy S.W.R.S. to :

1. The Chief Engineer, EHVP.C. (O&M) Zone MSETCL Chhatrapati Sambhajanagar.
 2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Chhatrapati Sambhajanagar.
- ...This is as per approval vide Ltr. No.1217 Dtd.03.12.2024.

Copy to:

1. The Addl. Executive Engineer (C) EHV CCCM Sub Division, MSETCL, Jalna.
2. The Dy. Manager (F&A) EHV CCM Division Chhatrapati Sambhajanagar. The amount of this work is Chargeable to sanctioned estimate No.T-17 Dtd.03.12.2024 FY 2024-25 under R&M Budget
3. Notice Board

OFFICE OF THE :-

EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administrative Building, first Floor,
wing no.102, Chhatrapati Sambhajanagar, Ph. No. (0240) 2331429,
E-mail :ee2710@mahatransco.in CIN: U40109MH2005SGC153646



(e-Enquiry)

QUOTATION NOTICE

The sealed percentage rate quotations are invited for the following works from the Civil Contractors registered with PWD, Railway and such other department and experienced in similar civil works as above. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Chhatrapati Sambhajanagar on **or before Dtd 09.12.2024 up to 13:00 hrs.**

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Sr. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	The Work of Construction of 02 No of CTR FPFES foundation & Allied civil works at 220 KV S/S MIDC Jalna, Dist. Jalna.	Rs.6,30,807.31/-	Rs.6,400/-	15 Days


(S.M. Banait)

Executive Engineer (C)
EHV CCCM Division, MSETCL
Chhatrapati Sambhajanagar

Copy S.W.R.S. to :

1. The Chief Engineer, EHVP.C. (O&M) Zone MSETCL Chhatrapati Sambhajanagar.
 2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Chhatrapati Sambhajanagar.
- ...This is as per approval vide Ltr No.1217 Dtd.03.12.2024.

Copy to:

1. The Addl. Executive Engineer (C) EHV CCCM Sub Division, MSETCL, Jalna.
2. The Dy. Manager (F&A) EHV CCM Division Chhatrapati Sambhajanagar. The amount of this work is Chargeable to sanctioned estimate No.T-17 Dtd:03.12.2024 FY 2024-25 under R&M Budget
3. Notice Board

**OFFICE OF THE :-
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administrative Building, first Floor,
wing no.102, Chhatrapati Sambhajnagar, Ph. No. (0240) 2331429,
E-mail :ee2710@mahatransco.in CIN: U40109MH2005SGC153646



Name of Work: The Work of Construction of 02 No of CTR FPFES foundation & Allied civil works at 220 KV S/S MIDC Jalna, Dist. Jalna on quotation basis.

Estimated Amount: Rs.6,30,807.31/- (Inclusive of All Taxes)



(S.M. Banait)

Executive Engineer (C)
EHV CCCM Division, MSETCL
Chhatrapati Sambhajnagar.

Declaration of Contractor:

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor

Full Address:

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
EHV Civil Construction Cum Maintenance Division, Chhatrapati Sambhajnagar.
220 KV MIDC S/stn

Name of Work:- Construction of CTR Foundation & allied civil works at 220 KV S/S MIDC, Dist. Jalna.

ABSTRACT

Sr. No	Activity No.	Particulars	Unit	Quantity	Rate (Rs.)	Add 18% GST on col 6	final Rate col6 +col7	Amount (Rs.)
1	2	3	4	5	6	7	8	9
1	50013068	Excavation for foundation in earth, soils of all types sand, gravel and soft murum including removing the excavated material upto a distance of 50 m. beyond the building area and all lifts stacking and spreading as directed, dewatering, shoring, strutting and preparing the bed for the foundation and necessary back filling, ramming, watering (Including shoring and strutting) etc. complete. (Lift Upto 1.50 Metre) Spec. No. : Bd.A 1 Page No.259)	Cum	11.00	208.04	37.45	245.49	2700.39
3	50013069	Excavation for foundation in hard murum and boulders including removing the excavated materials up to a distance 50 meters, beyond the building area and stacking and spreading as directed dewatering preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) Spec.No. : Bd.A 3 Page No.259	Cum.	21.00	253.26	45.59	298.85	6275.85
5	50013071	Excavation for foundation in soft rock and old cement and lime masonry foundations including removing the excavated materials upto a distance of 50 meters beyond the building area and stacking as directed including dewatering preparing the bed for the foundation and necessary back filling with available earth murum, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m) Spec No. : Bd.A 4 Page No.259	Cum.	20.00	431.15	77.61	508.76	10175.20
7	50013073	Excavation for foundation in hard rock by chiseling, wedging, line drilling, etc. including trimming and leveling the bed, removing the excavated materials upto a distance of 50 meters beyond the building area stacking as directed, dewatering and back filling with available earth/ murum ramming, watering, complete. (Lift upto 1.5 m) Spec No. : Bd.A 6 Page No.260	Cum.	103.50	1313.54	236.44	1549.98	160422.93
9	50013138	Providing and laying in situ cement concrete of 1:4:8 proportion with trap/ granite/ quartzite/ gneiss metal in foundation including necessary form work, compacting and curing etc. complete. (without SCADA ons (Natural sand / VSI sand finely washed etc	Cum	3.00	6159.64	1108.74	7268.38	21805.14
10	50013153	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering, formwork ,cover blocks, laying/pumping, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, without SCADA. With fine aggregate (Crushed sand VSI Grade)	Cum	9.00	7146.40	1286.35	8432.75	75894.75
11	50013156	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).without SCADA complete. With fine aggregate (Crushed sand VSI Grade)	Cum	2.00	14248.74	2564.77	16813.51	33627.02
12	50013182	Providing and fixing in position T.M.T. bar reinforcement (Produced from iron ore and made through blast furance route as per IS 1786-2008) of various diameters for reinforced cement concrete pile caps, footings, foundation, slabs, beams, columns, canopies, stair case, newels, chajja, lintels, pardi, copings, fins, arhes etc. as per detailed designs, drawings and schedules including cutting bending, hooking the bars, binding with wires or tack welding and supporting as required complete. Spec No. : Bd.F.17 Page No.306.	MT	0.72	90151.52	16227.27	106378.79	76592.73
13	50013144	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade)	Cum	0.10	6930.67	1247.52	8178.19	817.82

Sr. No	Activity No.	Particulars	Unit	Quantity	Rate (Rs.)	Add 18% GST on col 6	final Rate col6 +col7	Amount (Rs.)
1	2	3	4	5	6	7	8	9
14	50013147	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), without. With fine aggregate (Crushed sand VSI Grade)	Cum	1.00	7151.43	1287.26	8438.69	8438.69
15	50013241	Providing sand faced plaster externally in cement mortar using Kharsalia/Kasaba or similar type of sand, in all positions including base coat of 15mm thick in C.M. 1:4 using waterproofing compound at 1kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8mm thick in C.M. 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete. Bd.L.7 Page No.367.	Sq.m	14.00	663.58	119.44	783.02	10962.28
16	50013075	Filling in plinth and floors with approved excavated materials in 15 cm to 20 cm layers including watering and compaction complete. Spec No. : Bd.A.10 Page No.262	Cum	1.00	120.60	21.71	142.31	142.31
17	50013076	Filling in plinth and floors with contractors soil sand or murum in 15 cm to 20cm. layers including watering and compaction complete. Bd.A.11 Page No.263	Cum	129.00	1211.62	218.09	1429.71	184432.59
18	50013340	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to the plastered surfaces including one coat of primer scaffolding if necessary, cleaning and preparing the surface, watering for two days complete. Bd.O.8 Page No.408.	Sq.m	14.00	79.40	14.29	93.69	1311.66
25	50014008	Cutting down the thorny bushes (Wali babule etc.) having girth from 5 cm to 20 cm including removing their roots, stacking and conveying the materials upto 1.00 km, removing vegetation including levelling ground as directed for both sides of road etc. complete as directed by Engineer in charge. Spec. No. As directed by Engineer in charge.	Sq.m	50.00	7.04	1.27	8.31	415.50
26	50013081	Conveying materials obtained from road cutting including all lifts, laying in layers, breaking clods, dressing to the required lines, curves, grades and section for a lead of over 300m. to 500m from the site of excavation to the site of deposition as directed by Engineer in charge. Spec. No. Rd.18, Page No.197.	Cum	15.00	394.97	71.09	466.06	6990.90
27	50013814	Supplying and spreading stone Dust of trap stone at the sub station site, conveying stacking and spreading in uniform thickness of 50 mm including all leads,	Cum	3.00	1417.99	255.24	1673.23	5019.69
28	50004665	Supplying and spreading 25 to 40 mm size machine crushed trap stone metal free from impurities as directed by Engineer - in - charge in the switchyard including conveying stacking and spreading in uniform thickness of 65 mm including all leads, loading, unloading, watering and manually compaction etc. complete. (Stack measurement will be paid)	Cum	3.00	1655.67	298.02	1953.69	5861.07
29	50004664	Supplying and spreading 20 mm size machine crushed trap stone metal free from impurities as directed by Engineer - in - charge in the switchyard including conveying stacking and spreading in uniform thickness of 35 mm including all leads, loading, unloading, watering and manually compaction etc. complete. (Stack measurement will be paid)	Cum	2.00	1655.67	298.02	1953.69	3907.38
30	50014208	Providing and placing in position R.C.C. collars of 800 mm dia X 600 mm length R C. C pipe for earthing, pits including transportation etc. complete (Total balance)	Nos	3.00	2328.30	419.09	2747.39	8242.17
31	50004678	Providing and fixing M-15 (1:4:8) concrete block of size 400 X 200 X 200 mmsize along the edge of metal line in position including necessary excavation including applying white wash in two coats etc complete. at all leads and lifts as directed by Engineer in-charge. (Spec. No. As directed by Engineer in-charge)	Rmt	1.00	413.83	74.49	488.32	488.32
32	50004138	Dressing Leveling of sub-station yard by way of cutting / filling of ground including removing the shrubs / bushes including the removal of roots if any in order to prepare the surface to receive metal spreading. Up to depth of 300 mm details as per APPENDIX - E. , Sr. No. F 1 to 3 as per PWD red book specifications. (Total balance)	Sq.m	50.00	10.05	1.81	11.86	593.00

Sr. No	Activity No.	Particulars	Unit	Quantity	Rate (Rs.)	Add 18% GST on col 6	final Rate col6 +col7	Amount (Rs.)
1	2	3	4	5	6	7	8	9
33	50013985	Labour charges for fixing in position M.S.bolts of various sizes with the help of M.S.templates including providing, fabricating, transporting the templates bolts, nuts, etc. to site at the desired position leveling the templates and bolts as directed including tying fixing the bolts with the help of M.S bar pieces and welding properly with reinforcement of columns for keeping the templates bolts and nuts in position etc. complete including transporting the templates and nuts to contractor's site store after completion of works at his own cost. All T&P required shall be arranged by the contractor all as per directives of Engineer-in-charge including all lead and lift complete.	Per Set of Foundation	8.00	602.75	108.49	711.24	5689.92
Total								630807.31


 Executive Engineer (C)
 EHV CCCM Division, MSETCL
 Chhatrapati Sambhajinagar.