
 <p>MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.</p>	<p>MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD. Government of Maharashtra (Undertaking) (CIN: U40109MH2005SGC153646) OFFICE OF THE EXECUTIVE ENGINEER EHV O&M DIVISION, MANCHAR DSK's Pride , Survey No-170/7B, Pune-Nashik Highway, In front of Rural Health Centre, Manchar , Tq- Ambegaon Dist: Pune-410503 E-mail: ee61A0@mahatransco.in, eemanchar404@gmail.com Ph- 02133-223040/41</p>	
---	---	---

EE/EHV/O&M/Division/Manchar/Tech/No. 928

Date: 13.12.2024

**To,
WHOM SO EVER IT MAY CONCERN**

Subject:-Calling budgetary offers in r/o supply, installation, testing & commissioning of ESE Advance Early Streamer Emission (ESE) type Lightning Arrestor and L.Cat system at various EHV Sub-Stations under EHV O&M Division Manchar.

Dear Sir,

The budgetary offers through e-mail are hereby invited for the above work as per **Schedule 'A'** mentioned below:-

Sr. No.	Particulars	UOM	Ex Rate	GST	Unit Rate
Supply Part					
1	Supply of Advanced Early Streamer Emission (ESE) Type of Lighting Arrestor Covering a radius 110 meter for level 3 protection.	No.			
2	Supply of 2 digit Transient event counter with display digit from 0 to 99 for a minimum count impulse > 1 kAmp (8/20 micro seconds) with degree of protection IP20.	No.			
3	Mast: Supply of 5 meter GI mounting structure with base plate.	No.			
4	Supply of Fast Electrode. GI Earthing Pipe in Pipe technology having outer pipe diameter 88 mm & inner pipe dia 48mm, 1 mtr length & 2 terminal holes of 14 mm diameter.	No.			
5	Supply of Earth Enhancing Compound 1 Bag of 25 Kgs as per IS 1350 / AHPA guideline's. The PH value of Compound should be 7.59, Moisture% by mass should be 8.91 & Solubility in 1:1HCL should be 32.29%.	Bag			
6	Supply of 70 sq.mm single Core copper Flexible cable.	Mtr.			
7	Supply of 25 x 3 GI Strip	Mtr.			
8	Supply of connector to isolate supporting Mast & ESE Air terminal. The Dimensions of connector should be Top Diameter 75mm, height 65 mm, Bottom diameter 57 mm.	No.			
9	Supply of Disconnecting link with box to separate earthing system from air terminal system for regular inspection of earthing system	No.			
10	Supply of Guy Ropes, D-clamps, Insulators fasteners, fan-Hook	Set			
Service Part					
1	Labour Charges for installation & Testing of Fast Electrode Tercel Lightning Arrestor System	Job			

Note:- Rate shall be valid for 60 days from the date of submission of offer.

You are requested to quote your best reasonable rate for the above work. The Terms & Conditions are as follows.

Terms & Conditions:-

- 1) The rate should be quoted on firm quotation basis.
- 2) The rates should be exclusive of all taxes. Taxes should be quoted extra.
- 3) You are requested to submit your best reasonable budgetary offer as per Schedule 'A' for above works on **E-mail ID: ee61A0@mahatransco.in up to 11:00 Hrs on dtd. 21.12.2024.**
- 4) Following documents should be submitted along with your offer:-
 - a) Shop Act / Udyog Aadhar Registration Certificate.
 - b) Work Experience Certificate for similar nature of works in MSETCL/MSEDCL/ in any Power Utility or in Private Company in India.
- 5) **Please note that said budgetary offer is only for estimate purpose & will not be considered for any bidding & no work order will be issued based on this offer.**

Thanking you,

Yours Faithfully

Sd/-
(S R Wagh)
Executive Engineer
EHV O&M Division Manchar