

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
(CIN No. U40109MH2005SGC153646)

The Executive Engineer, EHV O&M Division, Kolhapur.
Near Market Yard, Bapat Camp, Kolhapur-416005
Phone:- (O) 0231)-2651529, 2680171, Email:-ee3210@mahatransco.in

EE/EHVO&M/DN/KOP/T/LP/ 2288

Date.24.12.2024.

E -ENQUIRY

Sub : E- Enquiry for work of route survey of EHV lines under EHV O&M DN, Kolhapur.

Dear Sirs,

Sealed and clearly written quotations are invited from the experienced agencies for work of route survey of EHV lines under EHV O&M DN, Kolhapur on item rate basis, so as to reach the office of Executive Engineer, MSETCL, EHV O&M Division, Bapat Camp, Kolhapur **upto:01.01.2025 up to 16:00 Hrs.**

Terms & Conditions::

1	PRICES :	The rates will be accepted as per Schedule A with work at various EHV Line subdivision under EHV O&M Division, Kolhapur.
2	SCOPE OF THE WORK :	Scope of the work will be executed as per schedule of the work order. Immediately after receipt of the work order, the contractor shall take prompt action in planning the work in consultation with the concerned In-charge. He should also take steps for timely procurement of the necessary material and tools and plant. The program should be finalized quickly. Having finalized the program, the schedule shall be strictly adhered to. The work should be carried out to the full satisfaction for Executive Engineer or his authorized representative. Work should be started within 2 days from the Dt. of intimation from the concern subdivision incharge.
3	TAXES :	Rates are inclusive of all the taxes. 1% labour cess & 2 GST TDS will be deduct from your bills.
4	AGREEMENT BOND :	Submit agreement bond on stamp paper of Rs. 500/- . cost of stamp paper borne by you only.
5	SECURITY DEPOSIT :	Security Deposit 10% of the order value submit to this office in form of Cash/BG/DD/Chq. The security deposit will be refunded only after completion of guarantee period & NOC from respective substation In-charge. If BG is to be submitted Govt stamp duty of 0.1% of SD amount is to be paid.
6	SPECIFICATION :	Work should be carried out as per specification in enclosed Schedule 'A'
7	RISK PURCHASE:	In case of failure to execute the order, the same will be purchased from other agency at our description and difference in cost will be recovered from the tenderer in addition to forfeiture of S.D.
8	QUANTITY & QUALITY :	Quantity & Quality as per schedule A & Specifications and is tentative.

9	INCOME TAX :	As per govt. rule Income tax at source will be recovered from your bill as per rules. Your Income tax No. may be informed to this office
10	TERMS OF PAYMENT :	The bills should be submitted in triplicate to Concern In-charge. 100% payment will be made on production of following document & completion of ERP activities. A) Invoice B) Work completion report. C) Guarantee Certificate.
11	WORKING PERIOD :	Work should be started within 2 days from the Dt. of intimation from the concern subdivision incharge & work should be completed within 10 days .
12	PENALTY FOR LATE DELIVERY :	If agency fails to report concern subdivision incharge within 2 days from the Dt. of intimation & if work started & not completed with 10 days, penalty @ ½ % of the work order amount will be implemented, maximum up to 10% of the work order amount.
13	DEDUCTION :	Any amount or amounts which become payable by the contractor to the MSETCL under particular contract may be deducted by the purchaser from any amount / amounts due or becoming due by him to the contract under the same or any other contract.
14	JURISDICTION :	All disputes or difference arising out of in connection with the contract, if concluded, shall be subject to the exclusive jurisdiction of Kolhapur court.
15	PAN No./ GST :	Please mentioned PAN No./ GST Registration No. if applicable / PF No. & ESI No. if applicable on the bill otherwise bill will be kept pending.
16	TRANSPORTATION :	Transportation of material and expert manpower will be at your cost only.
17	GENERAL T&C :	You are also deemed to be fully aware of the Company's general conditions of contract for work and any ignorance of any of the conditions will not exempt you from your liability to abide by the same.
18	SUBLETTING :	You shall not sub-contract without the prior written permission of the company.
19	GUARANTEE PERIOD	Work is of survey nature, hence guarantee is not applicable.
20	Estimated Amt	Total Estimated Amount limited upto Rs. 5,00,000/- (Incl. Of all Taxes)
21	Validity of work order	Validity of work order will be 12 months from the Dt of issue of work order.

Note Following documents should be Submitted with quotations only :

Sr. No.	Particular
1	Registration under GST
2	Proof regarding Income Tax Return for the FY 2022-23.
3	Certificate having successfully executed Route Survey of EHV lines work or line erection work or AMC of EHV lines will be considered from the rank of Executive Engineer or above.
4	PAN Card copy.

**Executive Engineer,
EHV O&M Division, Kolhapur**

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
(CIN No. U40109MH2005SGC153646)

The Executive Engineer, EHV O&M Division, Kolhapur.
Near Market Yard, Bapat Camp, Kolhapur-416005
Phone:- (O) 0231)-2651529, 2680171, Email:-ee3210@mahatransco.in

work of route survey of EHV lines under EHV O&M DN, Kolhapur.
Schedule A

Sr No.	Details of Documents	Unit	SAP no	Rates per unit Excl of LC and GST	Labour r cess @1%	Rate Incl. LC	GST on Rate Incl. LC	Rates per unit Incl of LC and GST	Quote rates in % basis Above /Below At Par Incl of LC and GST
1	Preliminary survey with GPS, theodilite / total station, marking route on topo sheets and village map representing actual field condition etc, in all respect	Kms	50003230	7231	72.31	7303.49	1314.62	8618.13	
2	Detail survey including tower spotting and tower profiles. Detail survey with GPS, total station, digital theodilite etcalong the approved alignment, preparation of profile, tower spotting, tower schedules and soil resistivity, marking of route on topo sheet and village map, collection of 7/12 of the corridor, identification of forest/ hatching to minimise the forest etc., and submission of KML	Kms	50003231	16576.10	165.76	16741.86	3013.53	19755.40	

3	Check survey to carry out the checks as per approved profiles with digital theodolite, total substation, GPS etc., and location marking by fixing three pegs in alignment for suspension tower and by fixing five pegs in bisection for angle tower including bush cutting along the centre line of alignment and repeg marking if necessary etc. complete in all respect. Check survey including revision of profile if required.	Kms	50014580	7008.69	70.08	7078.78	1274.18	8352.95	
---	--	-----	----------	---------	-------	---------	---------	---------	--

Note:

- 1) Above rates are Incl. of LC & GST.
- 2) Please quote rates in % basis.
- 3) Qty vary as per site conditions.

**Executive Engineer
EHV O&M Division Kolhapur**