



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
(CIN No.U40109MH2005SGCI53646)**

 <p>MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.</p>	<p>Office of the Executive Engineer EHV O & M Division-I, Pune Block No.406, Admin Building, 3rd Floor, Rasta Peth, Pune 411011 Phone No : 7447440351 E- mail- ee6140@mahatransco.in</p>	 <p>ॐ नमो भगवते वासुदेवाय स्वतंत्रता श्रिताज्यामिषेक शके ३५०</p>
---	--	---

EE/EHV O&M Dn.-I/Pune/Tech./ 2363

Date:26.12.2024

TO WHOM SO EVER IT MAY CONCERN

Subject: Calling of Budgetary offer Extention-1 -supply, installation & commissioning of 11 kV Gas Insulated Substation (GIS) modules at 132 kV Ganeshkhind Substation under EHV O&M Division-I, Pune.

Dear Sir,

The Budgetary offer through e-mail are hereby invited for the above work as per schedule-A enclosed.

All are requested to quote your best reasonable rates for above work.

The Terms and conditions as below:

- 1) The rate quoted should be valid for 120 days (minimum)
- 2) The rate should be quoted on firm quotation basis.
- 3) The rates should be exclusive of all taxes. Taxes should be quoted extra.
- 4) Following documents should be submitted along with your offer: -
 - a. Shop Act / Udyog Aadhar Registration Certificate.
 - b. Work Experience Certificate for similar nature of works in MSETCL/MSEDCL/ in any Power Utility or in Private Company in India.

You are requested to submit your best reasonable budgetary offer as per Schedule-A, for above works on E-mail ID: ee6140@mahatransco.in up to 11:00 Hrs on dtd. 02.01.2025

This budgetary offer is invited only for estimation purpose and same will not be considered for any bidding OR other activity.

**S/d/-
(V.V. Borkar)
Executive Engineer
EHV O & M Division –I, Pune**

MAHARSHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED

Supply, installation & commissioning of 11 kV Gas Insulated Substation (GIS) modules at 132 kV Ganeshkhind Substation under EHV O&M Division-I, Pune.

Schedule-A

Sr. No.	Particulars of Work	Unit	Ex-Works Unit Rate	GST @18%	Unit Rate with GST
Material Part:					
1	<p>Transformer LV Bay Module (11 kV) : Each module comprising of the following :</p> <p>3 phase Circuit Breaker with vacuum interrupters in gas filled switchgear housing complete with operating mechanism, 2500A -1 No.</p> <p>Disconnecter: 3Phase,Single Pole, three position disconnector to work as Disconnecter & earthing switch complete with manual & motor driven operating mechanism 2000A-1 Set.</p> <p>Current Transformer: 4 Core, Multi ratio, single phase current transformer with 1600-800/1A, 4C CT Ratio (1 Set - 3 Nos.) [PS, PS, 0.2S, PS]</p> <p>Bus Bar- Single bus arrangement: Main Bus - with 2000A ratings</p> <p>Cable end unit (Plug in type) with capacitive voltage indicator system: 3 Phase, Single pole, Plug in type cable termination - 4 Runs of 630 sq.mm or 5 Runs of 400 sq.mm. (for each phase - 1 (Set))</p> <p>Local Control Cubicle for GIS module, gas monitoring device, barriers pressure switches etc as required. Can be part of GIS.</p>	No.			

2	<p>11 KV Line Bay Module (With 9 kV-10 kA GIS Surge Arrestor): Each module comprising of the following :</p> <p>3 phase Circuit Breaker with vacuum interrupters in gas filled switchgear housing complete with operating mechanism, 2500A -1 No.</p> <p>Disconnecter: 3Phase, Single Pole, three position disconnector to work as Disconnector & earthing switch complete with manual & motor driven operating mechanism 2000A-1 Set.</p> <p>Current Transformer: 4 Core, Multi ratio, single phase current transformer with 400-200/1A, 3C CT Ratio (1 Set - 3 Nos.) [PS, PS, 0.2S]</p> <p>Bus Bar- Single bus arrangement: Main Bus - with 2000A ratings</p> <p>Cable end unit (Plug in type) with capacitive voltage indicator system: 3 Phase, Single pole, Plug in type cable termination - 2 Runs of 400 sq.mm for each phase - 1 (Set)</p> <p>Local Control Cubicle for GIS module, gas monitoring device, barriers pressure switches etc as required. Can be part of GIS</p> <p><u>NOTE:</u> The bus and the equipment may be with single phase or 3 phase enclosure.</p>	No.			
3	<p>11 KV Bus Sectionalizer Bay module: Each module comprising of the following :</p> <p>3 phase Circuit Breaker with Vacuum interrupters in gas filled switchgear housing complete with operating mechanism, 2500A -1 No.</p> <p>Disconnecter: 3 Phase, Single Pole, three position disconnector to work as disconnector & earthing switch complete with manual & motor driven operating mechanism 2000A - 1 Set.</p> <p>Current Transformer: 4 Core, Multi ratio, single phase current transformer with 1600-800/1A, 4C CT Ratio (1 Set - 3 Nos.) [PS, PS, 0.2S, PS]</p> <p>Bus Bar- Single bus arrangement: Main Bus - with 2000A ratings</p> <p>Cable end unit (Plug in type) with capacitive voltage indicator system: 3 Phase, Single pole, Plug in type cable termination - 2 Runs of 400 sq.mm for each phase - 1 (Set)</p> <p>Local Control Cubicle for GIS module, gas monitoring device, barriers pressure switches etc as required. Can be part of GIS</p>	No.			

	<u>NOTE:</u> The bus and the equipment may be with single phase or 3 phase enclosure.				
4	<p>11 KV PT Bay Module (1 for each section): Each module comprising of the following:</p> <p>Disconnecter: 3 Phase, Single Pole, three position disconnecter to work as disconnecter & earthing switch complete with manual & motor driven operating mechanism 1600A - 1 Set.</p> <p>Potential Transformer: 3 Core, Multi ratio, single phase potential transformer 11KV/ √ 3/110V/ √ 3-110V/ √ 3-110V/ √ 3 - 1 Set (3 Nos.) [3P, 3P, 0.2]</p> <p>Bus Bar- Single bus arrangement: Main Bus - 2500A, 50kA/3sec</p> <p>Local Control Cubicle for GIS module, gas monitoring device, barriers pressure switches etc as required.</p>	No.			
Erection, Testing and Commissioning part:					
1	Supervision of GIS & GIB installation testing and commissioning	Set			
2	11 kV GIS bays erection charges per bay	No.			

S/d/-
(V.V. Borkar)
Executive Engineer
EHV O & M Division –I, Pune