

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	: Executive Engineer, EHV O&M Division, Latur.
Office Address	: 132 kV Latur(MIDC) S/s Premises, Near Kirti Gold Mill, MIDC Road, Latur-413512
Contact No.	: 02382-222208 (O), 8956304905/8956304912
Email ID	: eelaturdn@gmail.com, ee2220@mahatransco.in.

Ref. No.: EE/EHV/O&M/LTR/TS/No - 0046

Date: 10 JAN 2025

E-Enquiry

Sub: - E-Enquiry for Work of Providing and Fixing of New High Mast 18 Meter Tower with Lighting Fixtures at 132kV Killari S/S under EHV O&M Division, Latur.

Dear Sirs,

Sealed and super scribed quotations are invited for the work as specification given below. The quotation giving full particulars should reach this office on or before 17.01.2025, up to 15.00 Hrs positively. The Taxation liability should show separately. Rights of cancellation/modification of E-Enquiry at any stage, is reserved at this office.

Schedule 'A'

SN	Particulars	Unit	Qty	Rate per unit (Excluding GST)	Rate Per Unit (Including GST)
X1	X2	A	B	C	D
Supply Portion					
1	Galvanised Gantry structure, equipement	MT	1.57		
2	2x400W HPSV Fixture with control gear	No.	4		
3	1 x 150W HPSV Fixture with Control gear	No.	13		
4	50 x 8 mm, GI Earthing strips	Rmt	210		
5	Cu conductor, 2 core, 2.5 sq.mm steel Armoured, FRLS control cable	Rmt	250		
6	Aluminium conductor, 4 core , 16 sq. mm. Armoured, FRLS power cable	Rmt	120		
7	Supplying and erecting 6 to 32 A, 10kA, SPMCB suitable to fix in 1 module of modular switch in provided box complete & duly concealed with necessary material and connected.	No.	18		
8	Supplying, erecting & marking TPMCB 6A to 32A, with rated short - circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-SWR/MCB	No.	6		
9	Nuts ,Bolts & Washers etc	MT	0.15		

Erection Portion				
1	Erection of LM structure as per drawings on existing foundation with transport of materials required from site stores complete	MT	2.8	
2	Fixing of HPSV / HPMV Lighting fixtures on LM top as directed with suitable fixing arrangement	No.	19	
3	Cabling and termination from LM fixture at Top of LM to the bottom ACDB on both end as directed with provided cables by providing the required lugs & glands	Per Cable	19	
Laying				
	Laying , dressing and clamping of control cable (inclusive of clamping material, cable tie, aluminium sheet clamp etc.)			
4	Aluminium conductor 4C X 16 sq. mm. Armoured, FRLS Control cable	Rmt	120	
5	Aluminium conductor 2C X 2.5 sq. mm. Armoured, FRLS Control cable	Rmt	250	
Termination				
6	Aluminium conductor 4C X 16 sq. mm. Armoured, FRLS Control cable	Per Cable	12	
7	Earthing strips(50x8 GI)220/132/33 KV equipment,gantry, equipment support structure earthing including excavation,backfilling,cutting, bending & drilling of MS/GI flat & welding one end to equipment & another end to earthmat etc	No.	20	
Grand Amount (Including all Taxes) (Rs.)				


Estimated amount for the above work: Rs. 4,99,497.35/- (Including all Taxes & Cess)

Note: - 1. Rate of GST shall be mentioned by Bidder on their Offer with SAC Code.

2. No Conditional bid shall be Accepted.

3. Xerox signed copies of below mentioned documents should be attached along with quotation.

- a) PAN Card.
- b) GST registration Certificate
- c) Bombay Shop Act License
- d) Valid Contractor Electrical License
- e) Experience certificate of carrying out the similar work issued by, not below the rank of Executive Engineer.


Executive Engineer
EHV O&M Division Latur