



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

**From:-Office of The Executive Engineer,
EHV(O&M) Division, Kalwa
Brahmaputra Building, 2nd floor,
Power House Complex, Post Box No 4, Airoli,
Thane-Belapur Rd., Navi Mumbai- 400708.**

Tel. : 022- 2760 1919, FAX : 022- 2760 1919

CIN No: U40109MH2005SGC153646

Web Site:www.mahatransco.in

E-mail ID – eeikalwa@gmail.com

Ref No.: EE / EHV/ O&M/ KLW/T- /00122

Date: - 21.01.2025

ENQUIRY
(Through MSETCL webpage)

To,
WHOM SO EVER IT MAY CONCERN

**Sub.: Enquiry for supply of additional cable for 220KV Mulund- Borivali- Bhandup LILO for increasing reliability and capacity of existing cable equivalent to line conductor.
..... Submission of budgetary offers thereof**

This office has to be prepare an estimate for supply of additional cable for 220KV Mulund- Borivali- Bhandup LILO for increasing reliability and capacity of existing cable equivalent to line conductor It is requested to offer your favorable budgetary rate for the subject work as detailed in the enclosed Price estimate.

1. DUE DATE: - The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office on or before due date i.e., Dt 22.01.2025 The published period of enquiry is from 22.01.2025 to 29.01.2025.

2. QUOTED RATES: The quoted rates should include the supply of additional cable for 220KV Mulund- Borivali- Bhandup LILO for increasing reliability and capacity of existing cable equivalent to line conductor including T&P and all incidental charges such as traveling/ transportation, accommodation etc. Supply of additional cable for 220KV Mulund- Borivali- Bhandup LILO for increasing reliability and capacity of existing cable equivalent to line conductor. Scope of work shall also include mobilization & demobilization of manpower & material as required from contractor's base to execution site, labour, Supervisor, vehicles, lodging & boarding of engaged. labour, Tools & Plants, material, and any other services required for the execution of subject work.

- **Technical Specification of work:**
- **Supply of 250mm Dia HDPE pipe as per following specification**

Sr. No.	Description	Unit	Ex work Rate (rate /ferry)
1	<ul style="list-style-type: none"> • IS 4984:2016 MARK HDPE Pipe • Ourt Dia 250mm tolerance 1.5mm • Wall thickness 12-13mm • Grade PE-100PN 6 SDR 21 (6Kg/ CM2) • Flaring length- 150 ± 5.00mm • Flaring OD- 275 ± 2.50mm 	Per Pipe (6m length pipe)	

Note :- Please mention & consider Labour Cess- Extra, GST-Extra.

- 5. DOCUMENT SUBMISSION:** The bidder should submit all the supporting and accompanying documents required for execution of work in sealed Envelope to this office.
- 6. Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**

Thanking you,

Yours faithfully,
-Sd-
**Executive Engineer,
EHV (O&M) Dn., Kalwa.**

- Copy to:** 1) The Manager (F&A), EHV (O&M) Dn., Kalwa.
2) Notice board.