

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

From: Executive Engineer, EHV O&M Division Boisar
Office address: Office of the Executive Engineer, MSETCL, EHV O&M Division Boisar, Khairaphata, At Vidyanagar, Post Saravali, Tal. & Dist. Palghar.
Pin 401 501
Contact No.: (O) 9167640570
CIN No: U40109MH2005SGC153646
Website: www.mahatransco.in
Email Id. ee7130@mahatransco.in

Ref. No.: EE/EHV/O&M/DN/BSR/Tech/Budgetary Offers/119

Date: 27.01.2025

Enquiry for Budgetary Offers

**To,
WHOM SO EVER IT MAY CONCERN**

Sub.: Budgetary Offer for Dismantling, Erection and commissioning of various 22kV GIS panels at 220/100/22kV Vasai substation S/S under EHV O&M Division Boisar.

This office has to prepare estimate for Dismantling, Erection and commissioning of various 22kV GIS panels at 220/100/22kV Vasai substation S/S under EHV O&M Division Boisar. It is requested to offer your favorable budgetary rate for the subject work as detailed in the enclosed Price estimate.

- 1) **DUE DATE:** The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office **on or before due date i.e. 05.02.2025 till 1:00 pm. If budgetary offers received after due date will not be accepted by this office.**
- 2) **QUOTED RATES:** The quoted rates should include the cost of all skilled & unskilled Labour, and also the requisite consumables, T&P and all incidental charges such as traveling/transportation, accommodation etc.
- 3) **SCOPE of Work:** Work should be invariably “Dismantling, Erection and commissioning of various 22kV GIS panels at 220/100/22kV Vasai substation S/S”. Scope of work shall also include mobilization & demobilization of manpower & material as required from contractor’s base camp to execution site, labour, Supervisor, vehicles, lodging & boarding of engaged labor, Tools & Plants, material and any other services required for the execution of subject work.
- 4) **Technical Specification of work:**
 - a) Dismantling of 6 nos. of 22kV GIS Panel.
 - b) Erection of 7 nos. of 22kV GIS Panel.
 - c) Providing and Fixing of Cable End Termination (Raychem make kit).
 - d) High Voltage Test of 7 nos. of 22kV GIS Panel.
- 5) **DOCUMENT SUBMISSION:** The bidder should submit all the supporting and accompanying documents (i.e., technical specification, drawing etc.) required for execution of work in sealed Envelope to this office.

6) Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.

Encl.: Schedule 'A'



(Rajesh Dakhane)
Executive Engineer
EHV O&M Division Boisar

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
EHV O&M Division Boisar
Schedule 'A'

Sub: Estimate for Dismantling, Erection and commissioning of various 22kV GIS panels at 220/100/22kV Vasai substation S/S under EHV O&M Division Boisar.

Sr. No.	Description	Unit	Ex-Works Rate.
A	Supply Portion		
1)	NKT Paste	Nos.	
2)	Isopropyl Alcohol (IPA)	Ltr.	
3)	Busbar For 2500a Bushing	Nos.	
4)	Inter Panel Coupling Sleeve 2500a	Nos.	
5)	CRC Bottle	Nos.	
6)	Contact Grease (1 Packet = 100 Grm)	Pkt	
7)	Shim plate -3mm	Nos.	
8)	Wipal Cloth (100 Mtr.)	Rol.	
9)	Set of Hardware	Set	
10)	OC/EF relay (Numerical Relay Feeder Protection)	No.	
11)	Motor controller unit with accessories	No.	
12)	VPIS	Nos.	
13)	Semaphore	Nos.	
14)	Aluminium Structure (Drg. No. G4587Q)	Nos.	
15)	Resin Cast LT Current transformer	Nos.	
B	Erection Portion		
1)	Dismantling of 22KV GIS Feeder Panel including labour charges with Disconnection of 22kV, 3CX300Sqmm Power Cable termination from 22kV GIS Panel	No.	
2)	Erection of 22kV GIS Panel including labour charges	No.	
3)	Fixing 22kV, 3CX300 Sq.mm. End Termination Kit in 22kV GIS Panel	No.	
4)	High Voltage Test of 22 kV GIS Bay Panel	No.	
5)	Alternation, Modification, Fabrication for mounting 22 kV GIS Bay Panel	Lot.	
6)	Service of Qualified Engineer (Service charges for Service Engineer of OEM to carry out the Supervision of 22 kV GIS Bay panel of Erection Testing & Commissioning)	Per Day	

- Note:**
- 1) Ex-Works rates should be exclusive of Labour cess@1% & Freight & Insurance@2% etc.).
 - 2) Applicable Taxes should be quoted separately.
 - 3) The Budgetary offer should be valid for 120 days from due date of opening.
 - 4) Preference shall be given to MSETCL's registered vendors having subject experience.
 - 5) Lowest rates of respective material/services from all budgetary offers will be considered for preparation of estimate, however abnormally high or low rates will not be considered. Please be noted.



(Rajesh Dakhane)
Executive Engineer
EHV O&M Division Boisar

Copy to:

- 1) The Dy. Manager (F&A), EHV O&M Division Boisar.
- 2) Notice Board, Division Office, EHV O&M Division Boisar.