

**OFFICE OF THE :-**

**EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building , first Floor,  
wing no.102, Chhatrapati Sambhajnagar, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ CSN/Tech/

**No - 0118**

Date: **25 FEB 2025**

**E-Quotation Enquiry**

To,

.....  
.....  
.....

**Sub:** Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chhatrapati Sambhajnagar.

**Dear Sir,**

Sealed percentage rate quotations are invited from Registered & experienced Architect's for the above work as per schedule enclosed. The quotation should reach to the office of Executive Engineer (Civil) EHV CCCM Division Mahatransco Administration Building, first Floor, wing No.102, Chhatrapati Sambhajnagar on or **before dated.05/03/2025 Time 13.00 Hrs.**

**TERMS AND CONDITIONS:**

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(1) MONTHS** from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then

the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.

- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-II, MSETCL, Chhatrapati Sambhajnagar to the undersigned. Payment will be made within 30 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit **Rs.47,500/-** (5% of quotation value) as security deposit in cash/ DD/FDR of any nationalized Bank within 7 days from the date of receipt of work order, failing which EMD will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The contractor who is registered vendor in MSETCL has to pay earnest money to **Rs.9500/-** in cash/RTGS/NEFT any Nationalized Bank in favor of Executive Engineer(C) EHV CCCM Division, MSETC Ltd. Chhatrapati Sambhajnagar. And Money Receipt shall be obtained from Account Section EHV CCCM Division, Chhatrapati Sambhajnagar. If the MR Copy of EMD required amount is not found in the envelop the quotation will be rejected. The Bank Account Details are as follows Bank of Baroda Account No.**04600200000009** IFSC Code: **BARB0AURANG**, Chhatrapati Sambhajnagar- 431001
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) Special condition: The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is **Rs.9,43,233.55/-** only. (Inclusive of all Taxes)



- 23) Contractor has to submit self attested copies of Valid Architect Association Registration Certificate, GST registration certificate, EMD paid receipt, PAN Card & Similar work Experience certificate, as a mandatory documents at the time of submission of Quotation.
- 24) Agency is instructed to subscribe on top of envelop "Quotation for the work of - Name of work" and detail address along with valid e-mail ID and contact number. Please note that the any correspondence in regard to the work if any will be done through e-mail only. Hence agency's are requested to provide the valid e-mail currently in use for the communication and to check the e-mail ID regularly for to get information of communication if any. This office will not be responsible, if office unable to communicate to you due to invalid e-mail provided by you.
- 25) As per revised circular issued by Dy. Directorate of Insurance Maharashtra State vide letter No. क्र.प्रविनी- 2314/ देयक कपात रक्कम/ संकीर्ण/ अभि-3, दिनांक.31/03/2015, MSETCL/CO/C&M/PT/TKC-II/No.8450 dtd.30.11.2022, Government Resolution (GR) No.Sankirn-2018/pr.kr.47/CR-174/Vima Prashasan dtd. 13.09.2022 issued by Government of Maharashtra Finance section the contractor shall, apart from other relevant insurance, submit labour insurance amounting to Rs.4717/- of Work Order Amount to EHV CCCM Division, MSETCL, Chhatrapati Sambhajnagar before starting of the work. The insurance cover shall be procured by the contractor from "विमा संचालनालय, महाराष्ट्र राज्य, गृहनिर्माण भवन, २६४, पहिला मजला, कलानगर समोर, वांद्रे (पूर्व), मुंबई-४०००५१(दूरध्वनी क्र.२६५९०४०३ व फॅक्स क्रमांक.२६५९२४६१".)
- 26) The Vendor should be registered with the MSETCL while submitting the quotation and registration number should be mentioned on top of envelope. The Vendors are requested to take note that quotation received without details of the valid registration of MSETCL will not be considered and will be rejected.

**Encl:** Schedule 'B'



**(S.M.Banait)**

Executive Engineer (C)  
EHV CCCM Division, MSETCL  
Chhatrapati Sambhajnagar.

**Copy S.W.R.S. to :**

1. The Chief EngineerEHVP.C. (O&M) Zone MSETCL Chhatrapati Sambhajnagar.
2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Chhatrapati Sambhajnagar.  
...This is as per approval vide Ltr. No.226 Dtd.25.02.2025.

**Copy to:**

1. The Addl. Executive Engineer (C), EHV CCCM Sub Division-II, Chhatrapati Sambhajnagar.
2. The Dy. Manager (F&A) EHV CCM Division Chhatrapati Sambhajnagar. The amount of this work is Chargeableto sanctioned estimate no. T-/20 Dtd.25.02.2025 FY 2024-25 Dt. under Admin Budget.
3. Notice Board

**OFFICE OF THE :-**

**EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building , first Floor,  
wing no.102, Chhatrapati Sambhajanagar, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



**(e-Enquiry)**

**QUOTATION NOTICE**

The sealed percentage rate quotations are invited for the following works from the Registered Architects experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Mahatransco Administration Building, first Floor, wing no.102, Chhatrapati Sambhajanagar or before **Dtd.05.03.2025 up to 13.00 hrs.**

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Q. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajanagar.	Rs.9,43,233.55/-	Rs.9500.00/-	1Month



**(S.M. Banait)**

Executive Engineer (C)  
EHV CCCM Division, MSETCL  
Chhatrapati Sambhajanagar

**Copy S.W.R.S. to :**

1. The Chief Engineer, EHVP.C. (O&M) Zone MSETCL Chhatrapati Sambhajanagar
  2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Chhatrapati Sambhajanagar.
- ...This is as per approval vide Ltr. No.226 Dtd.25.02.2025.

**Copy to:**

1. The Addl. Executive Engineer (C) EHV CCCM Sub Division-II Chhatrapati Sambhajanagar
2. The Dy. Manager (F&A) EHV CCM Division Chhatrapati Sambhajanagar / The amount of this work is Chargeable to sanctioned estimate No. T-20/25.02.2025 FY 2024-25 under Admin Budget.
3. Notice Board

**OFFICE OF THE :-**

**EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building , first Floor,  
wing no.102, Chhatrapati Sambhajnagar, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



**Name of Work:** Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajinagar.

**Estimated Amount:** - Rs.9,43,233.55/- (Inclusive of All Taxes)



**(S.M. Banait)**

Executive Engineer (C)  
EHV CCCM Division, MSETCL  
Chhatrapati Sambhajinagar.

**Declaration of Contractor:**

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure) .....% above/below/Estimated Rate (in Words) ..... percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

**Signature of the contractor**

**Full Address:**



**MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED**

**EHV CCCM DIVISION, Chhatrapati Sambhajinagar**

**ABSTRACT**

**Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajinagar**

Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	As per SSR 2022-23		
					Add 18% GST	Rate with GST	AMOUNT
10	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	4.00	NOS	156.78	28.22	185.00	740.00
20	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc.	9.01	CUM	336.68	60.60	397.28	3580.76
30	Removing cement tiles, or marble or polished shahabad floor or dado with out bed concrete including stacking the materials as directed with all leads, lifts etc. complete	64.90	SQM	45.23	8.14	53.37	3463.71
40	Excavation for foundation in earth, soils of all types sand, gravel and soft murum including removing the excavated material upto a distance of 50 m. beyond the building area and all lifts stacking and spreading as directed, dewatering, shoring, strutting and preparing the bed for the foundation and necessary back filling, ramming, watering (Including shoring and strutting) etc. complete. (Lift Upto 1.50 Metre)	2.60	Cum	208.04	37.45	245.49	638.27
50	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	0.50	Cum	6208.03	1117.45	7325.48	3662.74
60	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade finely washed etc)	0.90	Cum	12645.99	2276.28	14922.27	13430.04
70	Providing and fixing in position T.M.T. bar reinforcement (Produced from iron ore and made through blast furnace route as per IS 1786-2008) of various diameters for reinforced cement concrete pile caps, footings, foundation, slabs, beams, columns, canopies, stair case, newels, chajja, lintels, pardi, copings, fins, arches etc. as per detailed designs, drawings and schedules including cutting bending, hooking the bars, binding with wires or tack welding and supporting as required complete. (From Integrated plant only) Spec No. : Bd.F.17 Page No.306.	0.11	MT	90151.52	16227.27	106378.79	11808.05

**MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED**

**EHV CCCM DIVISION, Chhatrapati Sambhajanagar**

**ABSTRACT**

**Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajanagar**

Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	Add 18% GST	As per SSR 2022-23	
						Rate with GST	AMOUNT
80	Providing second class Burnt Brick masonry with conventional/I.S.type bricks in cement mortar 1:4 including scaffolding, racking out joints and watering etc.in pillar of rectangular shapes as shown in the drawings or as directed complete	1.70	cum	8506.78	1531.22	10038.00	17064.60
90	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces, in all position including scaffolding and curing etc. complete.	9.00	cum	295.65	53.22	348.87	3139.83
100	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	10.10	cum	653.64	117.66	771.30	7790.13
110	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete. as directed by Engineer in charge. (putty Asian/birla/ nerolac/berger make)	9.00	Sqm	90.45	16.28	106.73	960.57
120	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	20.00	Sqm	36.18	6.51	42.69	853.80
130	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats includings caffolding,preparing the surface.(excluding primer coat)etc. complete.	63.00	Sqm	100.50	18.09	118.59	7471.17
140	Providing and applying two coats of exterior acrylic emulsion paint conforming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface, applying primer coat ,scaffolding if necessary , and watering the surface for two days etc complete,Including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen functionally, argonomicaly,aesthetically pleasing with prior appproval of Executive Engineer (RTC) and Executive Engineer (C)	7.90	Sqm	262.31	47.22	309.53	2445.29
150	Providing and laying (Kajaria/ Jhonson/ Somany/ Nitco/ Varmora/AGL etc) vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete. (As directed by Engineer in charge)	24.40	Sqm	1189.82	214.17	1403.99	34257.36

**MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED**

**EHV CCCM DIVISION, Chhatrapati Sambhajanagar**

**ABSTRACT**

**Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajanagar**

Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	As per SSR 2022-23		
					Add 18% GST	Rate with GST	AMOUNT
160	Providing and laying (Kajaria/ Jhonson/ Somany/ Nitco/Varmora/AGL etc) vitrified mirror / glossy finish tiles having size 600 mm to 1200mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete,including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen functionally, ergonomically,aesthetically pleasing with prior approval of Executive Engineer (RTC) and Executive Engineer (C) (As directed by Engineer in charge)	41.20	sqm	2161.65	389.10	2550.75	105090.90
170	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing the sharp edges wherever necessary, curing, etc. complete,Including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen functionally, ergonomically,aesthetically pleasing with prior approval of Executive Engineer (RTC) and Executive Engineer (C). (As directed by Engineer in charge)	7.00	Sqm	4407.93	793.43	5201.36	36409.52
180	Providing and fixing 34 mm thick moulded door shutter consisting of solid core single leaf flush door of 30 mm thickness lipped with 15 mm ( 5mm x 3) thick x 30 mm width on one style and top rail and 10 mm (5mm x 2) thick x 30 mm width on other style and bottom rails. The inner panels laminated with 2 mm thick termite proof, water proof and fire resistant moulded PVC sheet with 2,4,6 design in different plain and /or prelim colours on one side after routing the moulded design on flush doors and 2 mm plain and /or pre lam PVC on other side using rubber adhesive on flush door and solvent cement adhesive on the PVC lipping etc. as per direction of Engineer in charge and manufacturers specification and drawing etc. complete,Including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen functionally, ergonomically,aesthetically pleasing with prior approval of Executive Engineer (RTC) and Executive Engineer (C). (As directed by Engineer in charge).	5.10	Sqm	7456.10	1342.10	8798.20	44870.82



**MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED**

**EHV CCCM DIVISION, Chhatrapati Sambhajinagar**

**ABSTRACT**

**Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajinagar**

Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	As per SSR 2022-23		
					Add 18% GST	Rate with GST	AMOUNT
190	Providing and fixing in position (as per 1868 / 1982) Aluminium sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 kg/Rmt. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 kg/Rmt.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Interlocking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineerincharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With colour Anodising without box ,Including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen fuctionally, argonomicaly,aesthetically pleasing with prior appprroval of Executive Engineer (RTC) and Executive Engineer (C). (As directed by	4.00	Sqm	5452.13	981.38	6433.51	25734.04
200	Providing and fixing mild steel grill work for windows, ventilators, etc. 20 kg/sqm as per drawing including fixtures necessary welding and painting with one coat of anticorrosive paint and two coats of oil painting complete. for Design As directed by Engineer in charge (As per approved drawing & design)	4.00	Sqm	2107.49	379.35	2486.84	9947.36
210	providing and applying White cement in the gaps of tiles including all labour etc complete	5.00	Kg	47.51	8.55	56.06	280.30
220	Applying epoxy grout of Dr.Fixit or equivalent to joints of tiles including cutting groove in the joint ,labor as ditected.	5.00	Kg	118.76	21.38	140.14	700.70
230	Providing and fixing PARAS/SUPREME/PLASTO MAKE on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	20.00	RMT	267.33	48.12	315.45	6309.00
240	Providing and fixing PARAS/SUPREME/PLASTO MAKE on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	15.00	RMT	376.88	67.84	444.72	6670.80
250	Providing and fixing CERA/ HINDWARE/ PARRYWARE MAKE C.P. BIB cock with wall flange of approved make including necessary sockets/ union nut etc. complete.	2.00	EA	1113.54	200.44	1313.98	2627.96
260	Providing and fixing CERA/ HINDWARE/ PARRYWARE MAKE C.P. sink cock with raised J" shaped swinging casted spout of approved make including necessary sockets/ union nut etc. complete."	2.00	No.	2155.73	388.03	2543.76	5087.52
270	Providing and fixing CERA/ HINDWARE/ PARRYWARE MAKE C.P. Angular stop clock with wall flange of approved make continental including necessary sockets/union nut etc. complete.	2.00	EA	2700.44	486.08	3186.52	6373.04

**MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED**

**EHV CCCM DIVISION, Chhatrapati Sambhajinagar**

**ABSTRACT**

**Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajinagar**

Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	As per SSR 2022-23		
					Add 18% GST	Rate with GST	AMOUNT
280	Providing and fixing 10cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete.	2.00	No.	1132.64	203.88	1336.52	2673.04
290	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140Kilogramwith frame etc complete.	1.00	EA	10830.89	1949.56	12780.45	12780.45
300	Providing and constructing Brick Masonry Inspection Chamber 60cm x 60cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140Kilogramwith frame etc complete.	1.00	EA	10002.77	1800.50	11803.27	11803.27
310	Providing and fixing PARAS/SUPREME/PLASTO MAKE 160 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.	10.00	Rmt	415.07	74.71	489.78	4897.80
320	Providing and laying for 225mm dia. salt glazed S.W. Pipe including fitting such as bends, tees, single junction, double junctions laying, jointing (including excavation and refilling the trenches) complete	20.00	Rmt	468.33	84.30	552.63	11052.60
330	Providing and laying in position flooring of telephone black/ Amba White/ Catbary brown/ Rubyred/ Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in C.M. 1:3 curing and cleaning etc. complete,Including architecturally and aesthetically recommending , selecting and matching with the other items in this schedule to make the kitchen functionally, ergonomically,aesthetically pleasing with prior approval of Executive Engineer (RTC) and Executive Engineer (C). (As directed by Engineer in charge).	8.00	Sqm	4044.12	727.94	4772.06	38176.48
340	Providing skilled/unskilled labour for completing all unforeseen work as directed by Engineer In-charge.	8.00	Mandays	618.08	111.25	729.33	5834.64
350	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete. Spec. No.: Bd C. 2 Page No. 275	0.10	MT	115405.16	20772.93	136178.09	13617.81
360	Transportation of material along with loading & unloading of material including all labours & lead.	1.00	Trip	5617.95	1011.23	6629.18	6629.18
370	Providing and fixing of cylinder gas pipe in copper material with all necessary fixtures fitting etc., as directed by engineer in charge	1.00	Rm	5025.00	904.50	5929.50	5929.50

MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED							
EHV CCCM DIVISION, Chhatrapati Sambhajinagar							
ABSTRACT							
Name of the work:-Preparation of Architectural Drawing and Conversion of Old Kitchen to Modern Type at RTC Waluj, Chh.Sambhajinagar							
Sr.NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	As per SSR 2022-23		
					Add 18% GST	Rate with GST	AMOUNT
380	PROVIDING, FIXING and architecturally designing Kitchen trolly's for (7m x 0.75 m): stainless steel kitchen trolley in SS 304 grade frame work in stainless steel 20 mm x 20 mm pipe of 18 gauges, stainless steel drawers in 20 mm x 20 mm angle or pipe, stainless steel loose baskets in 6 mm & 3 mm bar. Stainless steel material of "jindal" make, stainless steel sink 700 mm x 450 mm size, panalling for kitchen trolley's in stainless steel sheet material 1 mm thick. " G " profile handles fitted, panel edge banded, 2 burner gas shegadi fitted with all necessary fixtures fitting etc all. (As directed by engineer in charge).	1.00	No	331650.00	59697.00	391347.00	391347.00
390	PROVIDING AND FIXING kitchen chimney in Stainless Steel Kitchen Exhaust Hoods with SS Baffle Filters in 18 gauge thickness sheet UPTO 15 FEET, EXHAUST CHIMNEY DUCT 24"x24" in steel sheet, Suction Capacity 1200 CMH, Material for hood in Grade SS304 JINDAL, with electrical Blower designed for specific kitchen dimension industrial with all necessary fixtures fitting. (As directed by engineer in charge).	1.00	No	65325.00	11758.50	77083.50	77083.50
Total Rs.							943233.55

---Sd---  
Executive Engineer ( C )  
EHV CCCM Division, MSETCL  
Chhatrapati Sambhajinagar.