

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of The Executive Engineer
400 KV R.S O&M Division, Kalwa
PO Box No. 5 Airoli
Navi Mumbai 400 708
Phone No. 022-27601893, 94
E-Mail :-ee7140@mahatransco.in
CIN No.U40109MH2005SGC153646.

Ref: EE/400KV/RS/O&M/Dn/KLW/Tech/25-26/000263 Date:-11.04.2025
E-ENQUORY
(Through MSETCL webpage)

To,
WHOM SO EVER IT MAY CONCERN

Sub:- Enquiry for Supply & installation of Auto changeover logic scheme for DG set with supply & retrofitting of advanced ACB in existing ACDB at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa.
.....submission of budgetary offers thereof.

This office has to prepare estimate for Supply & installation of Auto changeover logic scheme for DG set with supply & retrofitting of advanced ACB in existing ACDB at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa. It is requested to offer your favorable budgetary offer for the subject work as detailed in the enclosed price estimate.

1. **DUE DATE:-** The quotations, complete in all respects, duly sealed & super scribed should be submitted to this office on or before due date i.e. 21.04.2025.
2. **QUOTED RATES:-** The quoted rate should include the cost of all skilled & unskilled labour, and also the requisite consumables, T&P and all incidental charges such as traveling / transportation, accommodation, Freight insurance, labour cess etc.
3. **DOCUMENT SUBMISSION:-** The bidder should submit all the supporting and accompanying documents (i. e. PAN, GST certificate, Shop & Establishment certificate etc.) required for execution of work in sealed Envelope to this office.
4. **Please note that the said budgetary offer is only for estimate purpose & not considered for any bidding & No work order will be issued based on this Enquiry.**


Thanking you.

Yours faithfully,

Pankaj A. Shelar
Executive Engineer
400KV R.S. (O&M) Dn. Kalwa

Encl: Schedule 'A'.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.							
400KV RS O&M DN KALWA							
Schedule A							
Sub:- Supply & installation of Auto changeover logic scheme for DG set with supply & retrofitting of advanced ACB in existing ACDB at 400kV Kalwa Substation under 400kV RS O&M Dn Kalwa.							
Sr. No.	Description	Unit	Ex Rate	F&I @2%	Labour Cess@1%	GST	Unit Rate
1	Supply of L&T make Omega ACB Frame -1, 1000A, 4 pole, Electrical draw out type with MTX 1.5G release for protection.	EA					
2	Supply of Retrofitting material such as Electrolytic grade Aluminium busbar suitable for 1000A rating along with wiring material, Indication lamp etc.	EA					
3	Service charges for carrying out L&T make ACB retrofitting by dismantling and disconnection of existing Havells make ACB cradle, Busbar, control wiring etc. Fixing of New L&T ACB cradle with required modification to match existing ACB busbar etc. Fabrication of new busbar links to match existing Main busbar and cable end busbar using Cutting m/c, Punch m/c, Hydraulic Bending m/c etc. Carrying out control wiring for Electrical ON/OFF operation of ACB. Charging of ACB.	Job					
4	Design, Supply and Installation of Interlock logic scheme for Auto changeover in case of failure of any incomer with bus coupler and DG power using PLC relay logic Automation. Also carrying out interconnection cabling and wiring to PLC.	Job					


 Executive Engineer
 400KV R.S. (O&M) Dn, Kalwa