



MAHA TRANSCO



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of the Executive Engineer,
EHV Projects Division, MSETCL, Nashik
2nd Floor, Block No.08, New Administrative Building, Old Saikheda Road, Near Durga Mata
Mandir, Sailanibaba Bus Stop, Jail Road, Nashik Road, Nashik. 422 101.
Contact No.: 0253-2403141 (O), 2403143 (Fax).
e-mail: ee5610@mahatransco.in

EE/EHV/CONST/DIV/NSK/Tech/

821

Date:

22 MAY 2017

E-enquiry

To,

Sub: Work of Providing and fixing electrical Fixture such as Tube light, fans etc for office of the Projects Sub Divisions at BBLR

Ref: 1) E-mail from Addl EE lines projects S/Dn BBLR on dt 03.05.2017

2) E-mail from Addl EE SS projects S/Dn BBLR on dt 04.05.2017

3) E-mail from Addl EE 400KV lines projects S/Dn BBLR on dt 03.05.2017

Dear Sir,

The sealed & super scribed quotations are invited so as to reach this office on or before **08.06.2017** for Work of Providing and fixing electrical Fixture such as Tube light, fans etc for office of the Projects Sub Divisions at BBLR as per enclosed schedule 'B' and following terms & conditions and subject to approval of the competent authority.

TERMS & CONDITIONS:

1. **Scope of work:** The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule-B**.
2. The rates should be quoted on firm quotation basis for supply of material, erection work, transportation charges, etc. All the rates should be inclusive of all taxes, labour charges, T&P etc. required for execution of the work.
3. All the instruments, T&P, labours etc. shall be arranged by agency. No T&P or labour will be provided by the MSETCL.
4. The Contractor should furnish details of Experience of similar nature of work, Electrical Contractor License, Shop Act, Service Tax Registration certificate. PAN, TAN. etc. along with quotation.
5. The rates should be quoted in figures as well as in words.
6. 5% Security Deposit is to be deposited in Cash/Crossed DD/Cheque before commencement of work. The same shall be refunded to you after the satisfactorily Completion of the work.

7. MSETCL will not be responsible If any damage is occurred to the contractor's equipment/T&P OR any accident to contractor's labours /personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.
 8. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labour due to wrong operation shall be recovered from the bill.
 9. Income tax will be deducted as per prevailing rules from the bill & a certificate to that effect will be issued to the contractor.
 10. The work should be completed within 10 days from the date of handing over of clear work site, failure of such; penalty equal to ½ % per delayed week subject to the maximum of 10% of the ordered value will be levied.
 11. The work should be strictly carried out as per standard specifications and up to the entire satisfaction of the Engineer-In charge.
 12. The contractor will be abiding by the Rules & Regulations in force in respect of his employees & workmen under the Workmen's Compensation Act & the Contract Labour Act etc. He should be a registered contractor & documentary evidence of the same should be produced.
 13. As per provision of 'Mumbai Mudrank Adhinyam, 1958 clause No.34' an agreement on appropriate value of stamp paper shall have to be executed with MSETCL for execution of contract satisfactorily before commencing work. The amount of the fees for such an agreement shall be borne by contractor.
 14. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved by the undersigned.
 15. The quantities enumerated in attached Schedule 'B' are approximate & payment will be made against actual executed quantities.
 16. The rates quoted should be valid for 60 days.
 17. Idle charges for any reason will not be accepted.
 18. Not contained herein all other terms and conditions of MSETCL will be applicable to this enquiry
 19. In case of any dispute regarding this contract, the jurisdiction of the court will be Nashik.
- Thanking you,

Your's faithfully,


Executive Engineer
EHV Projects Division
MSETCL, Nasik.

Copy s.w.r.to,

The Superintending Engineer, EHV Projects Circle, MSETCL, Nasik.

Copy to,

- 1) The Manager (F&A), EHV Projects Division, MSETCL, Nasik.
- 2) The Addl EE EHV lines projects/ SS projects/400KV lines projects Sub division BBLR.
- 3) Notice Board.

Schedule B

Work of Providing and fixing electrical Fixture such as Tube lights, fans etc for office of the Projects Sub Divisions at BBLR.

Sr. No.	Particular	Unit	Qty	Unit Rate(Rs)	Total Amount(Rs)
1	Point wiring for independent plug in PVC trunking (casing capping) with 1.0 sqmm FRLS grade copper wire flush type switch and required accessories as per specification No. WG-PW/SW	Point	93		
2	Supplying & Drawing of 2X1.5 sqmm FR grade copper wires with 1.5 sqmm earthwire in provided concealed pipes point & terminating on moduler accessories in box for point wiring for independent plug as per specification no WG-PW/SW	Point	8		
3	Supplying adaptor for lamp holder 230/240 V A.C. supply	Each	35		
5	Supplying & erecting mains with 2X1.0 sqmm F.R. copper PVC insulated wire laid in provided conduit/trunking / inside pole / bus bars or any other places as per specification No. WGMA/BW	Meter	900		
6	Supplying & erecting mains with 2X2.5 sqmm F.R.L.S copper PVC insulated wire laid in provided conduit/trunking / inside pole / bus bars or any other places as per specification No. WGMA/BW	Meter	800		
7	Supplying and erecting modular type bell indicator ISI mark approved make duly erected on provided plate & box with wiring connections complete	Each	3		
8	Supplying and erecting modular type electronic step regulator for fan two modular ISI mark approved make duly erected on provided plate & box with wiring connections complete	Each	8		
9	supply and erecting 16 to 32A DPMCB suitable to fix in 2 module of modular switch in provided box complete and duly concealed with necessary material and connected	Each	8		
10	supply and erecting regular/ Standard model ceiling fan of 1400 mm sweep complete erected in position as per specification No FG-FN/CF	Each	3		
11	Supplying & Erecting fan clamp of 30X5 mm M.S. flat of Required length & 10 mm M.S. bolt and nuts erected with necessary hook of 10 mm M.S. round bar & painted.	Each	11		

12	Supplying and fixing anchor type fastener fan hook with 2 No. of 10mm dia x 75 mm long with necessary material for ceiling fan	Each	11		
13	Supplying erecting & terminating PVC armored cable 3 core 2.5 sqmm copper conductor continuous 5.48 sqmm (12 SWG) G.I. Earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench / pipe as per Specification No CB-LT/CU	Meter	124		
	Providing & erecting metallic plug & socket enclosures rating 20 Amp SPN/DC/AC box.	No	3		
14	Providing & Fixing ELCB 40 Amp 4P 100 Amp	No	1		
16	supply and erection triple pole and neutral distribution board (9TPNDB) With door surface/ flush mounted suitable for 3 pole MCCB as incommer & outgoing SP MCB (12 Pole) or TP MCB of 4 ways (12 Pole) on iron frame (Vertical busbar type) as per specification No sw-swr/mcb (Item No 5-3-2 page no 81)	No	1		
17	SUPPLY AND ERECTION & MAKING SPMCB 6A to 32A C series for motor power in provided distribution board as per specification NO SW-SWR/MCB { ITEM 5-3-2 Page No 81}	No	15		
18	providing and erecting air circulator 600mm sweep and oscillating type wall mounting 1440 RPM without speed regulator, overheat protection unit totally enclosed flame proof motor suitable for 230/250 Volts single phase, 50 cycle A.C supply with one meter of 3 core lead wire and with E class insulation and marking Sr. No and date of erection (I.No.2-13-7, p.no.60)	No	2		
19	Supply & Erecting earthing system with proper earthing to all wiring used G.I. Plate 600x600x5 mm pipe dia 30 mm bent to be used with proper size earth pit.	No	1		
20	Supplying & erecting compact fluorescent lamp 36 W 230 V to be used with provided ballast	Each	34		

Note- The quantities enumerated in Schedule 'B' are approximate.


 Executive Engineer
 EHV Projects Division
 MSETCL, Nasik.