

MAHARASHTRA STATE ELECT. TRANSMISSION CO. LTD.

From :- Name of Office :- EHV Civil Const. Cum Maint. Division, MSETCL, Amravati Office address :- Vidhyut Bhavan Shivaji nagar Amravati – 444603 Contact No. :- 0721- 2663659 Email Id :- ee1710@mahatransco.in

EEC/EHV/CCCM/Dn./Amt/ Tech/

680

Date 07.10.2017

E-QUOTATION

TO

Sub : - **Waterproofing work at EHV O&M Circle & CCCM Circle Amravati**

Due on : - 16.10.2017

Dear Sir,

Sealed and super scribed Percentage rate quotations are invited so as to reach this office on or before **16.10.2017** up to **15.00** Hours for the execution of various items of works as per the Schedule - 'B' enclosed and as per the terms and conditions given below : -

' TERMS & CONDITIONS '

1. The terms and conditions mentioned in the ' Works and Contract ' Book-let are applicable and copies of same can be purchased by the Contractor (s) on payment of Rs. 50.00 from the office.
2. The work shall have to be completed in all respect within a period of **1 Month** from the date issue of work order , failing which the Contractor will be liable to pay compensation / penalty at Half percent per week maximum up to 10% of the value of the work order.
3. The rates quoted by the Contractors shall include : -
 - i. All tools and plants required for carrying out the job.
 - ii. All labor charges required to execute the job.
 - iii. All temporary works required to complete the work including transportation of all required material to site.
4. The Company shall supply no material. All materials are required to be procured by the Contractor.
5. The work shall have to be carried out as per the 'Standard Specifications' and with best workmanship like manner and to the entire satisfaction of the Engineer-in-charge.
6. The Contractor shall be responsible for all accidents occurred / damages caused during the execution of the work He shall have to make good of the same at his own cost as directed.
7. The Contractor shall be responsible to abide all prevailing labour laws including the Workman Compensation Act.
8. The payment shall be made on the Final Bill basis.
9. The successful Contractor shall have to pay Security Deposit amounting to 5% of work order value.
10. The quantities in the Schedule - 'B' are approximate only and liable for variation.

11. The right to reject any or all quotations without assigning any reasons is reserved.
12. Any clarification pertaining to work shall be had from the undersigned before submitting the quotation.
13. The estimated cost of the work is **Rs. 2,68,246.00/- (Approx)**
14. The Contractor shall have to pay Earnest Money Deposit (**E. M. D**) of **Rs. 2690/-** along with the quotation in the form of D. D. in favour of E.E.(Civil), EHV CCCM Dn. Amravati.
15. The Income-tax and other applicable taxes per prevailing rate & rules shall be deducted from Contractor's bill, GST will be applicable as per GST rules.
16. Jurisdiction and Deduction clauses are applicable.
17. The blank quotation copy shall be available in EHV CCCM Dn. Amt. free of cost, during the working hours from 07.10.2017 to 16.10.2017.
18. The rates quoted shall be inclusive of all taxes etc.

Enclosed : As above.

Sd/-
Executive Engineer (C)
EHV CCCM Division, MSETCL,
Amravati

C.s.w.rs.to :-

- 1) The Superintending Engineer (C), EHV CCCM Circle Amravati

Copy to :-

- 1) The Addl. Executive Engineer (C), EHV CCCM S/Dn. I Amravati.
- 2) The Dy. Manager (F&A), EHV CCCM Dn. Amravati
- 3) Notice Board
- 4) Master File

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV CCCM DIVISION, AMRAVATI

Name of Work – Waterproofing work at EHV O&M Circle & CCCM Circle Amravati.

SCHEDULE B

Sr.No.	Particulars of Item	Unit	Quantity	Rate	Amount
1	Providing and laying jointless Polydee LM, a highly flexible elastometric coating for RCC / cementitious surface for terrace waterproofing on B.B. Coba / R.C.C, after application of TP42 Primer on perfectly clean surface (free from loose dust and foreign matter) application of 1st coat of PolydeeLM @ 700 gms/sqm and applying 2nd coat of Polydee LM @ 700 gms/sqm and finishing the same with sprinkling the AG10 granules on the wet coating. (After finishing covering the treatment with 25mm cement plaster for protection with fibrillated 6mm Plyplast fibre @ 125 gms/sqm to be paid in separate item.) covering 7 years guarantee on Court Fee Stamp Paper of Rs. 100/etc. complete.	Sqm	274	979	2,68,246.00
	Total				2,68,246.00

Sd/-

Executive Engineer (C)
EHV CCCM Division AMRAVATI

I am/ we are ready to execute the above said work :----- % (in fig.)
_____percent (in words) above / below the
estimated cost.

Signature of the contractor