

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD

Name of Office	: Office of the Executive Engineer
Office Address	: 400kV R.S.(O&M) Division, Babhaleshwar, A&P. Pimpri Nirmal, Tq. Rahata, Dist. Ahmednagar – 423107
Contact No.	: 02422 (O) 278173 (R) 278148 (Fax) 278153
Email Id	: ee5130@mahatransco.in
Website	: http://www.mahatransco.in

Ref.No. EE/400kV/RS/Dn/BBLR/Tech/ **No 00848**

Date: **14 NOV 2017**

Sub: - E - Enquiry for work of construction of retaining wall at 400kV Padghe-II line for location no.148 under 400KV Babhaleshwar .

Dear Sir,

With reference to above subject, you are requested to quote lowest possible rate for said work at 400kV R.S., Babhaleshwar as per specification in Schedule – A is attached enclosed herewith with following Terms and Conditions.

SCHEDULE 'A'

Sr.No.	Particulars of Work	Unit	Qty	Unit Rate(Rs.)	Amount Rs.
1	Excavation of land for foundation complete as per standard method. Work including removing of the excavated material upto 50 meters beyond the construction area and lift as specified , stacking and spreading , necessary dewatering etc., preparing the bed for the foundation proposed complete in all respect of size (50x05x05 cubic feet).	CMT			
2	Providing and laying in situ cement concrete in proportion 1:4:8of trap metal for foundation and bedding, including bailing out water manually from work, compacting, curing etc ete as per standard method	CMT			
3	Providing of uncoarsed rubber mesonary of trap store in cement mortar 1:6 in superstructure, including racking out joints, watering and scaffolding etc works complete in all respect as per standard method of construction (size 50x18x3 cubic feet)	CMT			
4	Providing of coping to parapet-by casting in situ cement concrete 1:2:4 as per instructions of Engineer in-charge including of super finish, curing etc works complete	CMT			
5	Providing of flush grooved pointing with cement mortar 1:3 to stone mesonary including scaffolding and curing etc complete as per standard method.	Sq-M			

6	Backfilling the foundation with Morrom after reconstruction UCRM	LS			
7	Demolishing of the collapsed wall to foundation level, lifting of the dismantled material to stack / move away suitably distantly as per the instructions of m-charge and all related activities required to carry over such renovation / reconstruction type of works. Including miscellaneous expenditure such as dewatering for seven days of the constructed part etc.	LS			

Note: Quantity may vary as per site condition.

TERMS & CONDITIONS: -


1. The quotation must be forwarded to the office in the name of "Executive Engineer", 400kV R.S. (O&M) Division, Babhaleshwar in sealed envelope duly super scribed with all details i.e.
 - (a) Enquiry No. & Date :-
 - (b) Due Date:-
 - (c) Quotation for...
2. The quotation must be written with ink or typewritten, any scratching or over writing must be initialed.
3. The validity period of rates should be mentioned in the offer which should be not less than 90 days from the date of opening of quotation.
4. Income Tax & statutory taxes if applicable shall be deducted from your bills as per prevailing Government rules.
5. Beside all the terms & conditions given in this enquiry, the Board's General Conditions of Contract are applicable to this contract.
6. The undersigned reserves the right to reject any or all quotations or cancel the requirement at his discretion without assigning any reasons thereof.
7. Payment: - Bill will be accepted in triplicate at Division Office for recording by concerned Engineer-in-Charge, auditing and making payment to the agency. Payment will be effected to the contractor as per actual quantities. Payment will made within reasonable period or as per availability of funds from the date of work satisfactorily.
8. Rates should be quoted both in figures and words.
9. Following documents (Xerox copies) must be available with quotation.
 - Valid GST Registration.
 - Valid PAN card copy.
 - Work Experience Certificate in MSETCL.
 - Valid Electrical License..
10. Details of Taxes if any should be mention separately and clearly; otherwise the rates quoted by you will be treated as inclusive of all taxes and no extra tax will be paid.
11. Other charges shall be mentioned separately; otherwise the rates quoted by you will be treated as inclusive of all charges and no extra charge will be paid.
12. The rates should be on firm quotation basis & exclusive of all taxes & any other contingencies etc.
13. You will have to pay Security Deposit of 05% of work order value within 10 days from the date of receipt of work order or before starting of work whichever is earlier. The S.D. shall have to be paid

in cash, in the form of D.D. or B.G. for full amount. Otherwise SD will be recovered from your 1st Bill; the same will be refunded after 06 month from the date of completion of work satisfactorily/ completion of guarantee period.

14 The due date is 24.11.2017 and will be opened on the same day, if possible.

Thanking you,

Yours faithfully,


Executive Engineer
400kV R.S.(O&M) Division
Babhaleshwar

Copy s.w.r.to: (By e-mail)

1) The C.E. EHVPCO&M Zone, Nashik

2) The S.E. EHV (O&M) Circle, Nashik.

Copy to: (By e-mail)

1) The Ad. Ex. Engr. (Maint.) 400kV R.S., BBLR.

2) The Dy. Manager (F&A) 400kV R.S., BBLR.