

**Maharashtra State Electricity Transmission Company LTD.**

CIN NO.U40109 MH 2005 SGC 153646

400kV Receiving Substation, Lamboti, Solapur.

Office of the **Executive Engineer,**  
**400 kV Receiving Station, Dn. Solapur.**  
**Post: Lamboti, Tal.:Mohol, Dist.:Solapur,**  
**Email:ee6220@mahatransco.in**  
**PIN - 413213**

---

**Ref. No. EE/ 400kv/RS (O&M)/ LBT/ T-/No. 315      Date :- 13.12.2017.**

**E-ENQUIRY**

**SUB :-** E- Enquiry for Work of Electrification of rest house at 400KV Lamboti Substation.

**Estimated Amount in Rs:- 2,79,172/- only. (Inclusive of All Taxes)**

**Date of publication Enquiry: - From Dtd. 13.12.2017 To Dtd.20.12.2017.**

**Last Date for submission of Offer: - Dtd.20.12.2017.**

**Technical Opening if possible: - on Dtd.21.12.2017 at 12:00 Hrs.**

Dear Sir,

Sealed and firm **Quotations** are invited by the undersigned for works as detailed below on the following terms and conditions there after:

**TERMS & CONDITIONS:**

- 1) The rate should be quoted on firm quotations basis.
- 2) The rate should be Inclusive of Taxes, duties, Octroi.
- 3) Quotation shall be submitted to this office on or before Dtd: 20.12.2017 positively.
- 4) The offer shall be valid for acceptance for the period of **180 days** from the date of submission.
- 5) All the documents should be submitted along with this office.
  - a) Valid copy of electrical contractor license.
  - b) Valid Shop Act license.
  - c) Pan Card Copy.
  - d) Valid GST Registration
  - e) Proof of Income Tax Return for last FY.-2016-2017.
  - g) The work experience certificate should have been issued during last 3 years only of similar work.

-----Continue-----

**Maharashtra State Electricity Transmission Company LTD.**


CIN NO.U40109 MH 2005 SGC 153646

400kV Receiving Substation, Lamboti, Solapur.

6. All the documents of these Enquiry and other accompanying documents shall bear the authorized signature of agency, failing which the offer will be liable for rejection.
7. The agency in his own interest expected to visit the site of work and acquaint him with the site condition.
8. The right to place an order or to cancel any or all quotations without assigning any reason is reserved with this office.

Thanking You,

Yours Faithfully,

  
Executive Engineer  
400KV RS Division, Lamboti.

**Copy s.w.rs.to:-**

The Superintending Engineer, MSETCL, EHV (O&M) Circle, Solapur

For information please.

**Copy to :-**

Dy. Manager (F&A), MSETCL, 400 KV RS Division Lamboti.

.....M.F. / Notice board.


**WORK OF ELECTRIFICATION TO REST HOUSE AT 400 KV SUB STATION UNDER RS 400 KV SUB  
STATION LAMBOTI, SHOLAPUR  
SCHEDULE-A**

Sr. No.	Description	Qty	Unit	Material Rate	Labour Rate	Amount for supply	Amount for labour
1	Point wiring for light / fan / bell in min 25mm casing – n – capping with 1 sq.mm. FR grade copper wires with modular type switch and required accessories as per specification No. WG-PW/CW DSR I. No. 1-9-9 P. No. 28	120	Point				
2	Wiring for plung on board with Switch socket concealed type and copper wiring, earthing and with modular accessories as per specification No. WG-PW/CW DSR I. No. 1-9-14 P. No. 28	20	Point				
3	Point wiring for independent plug, concealed type in min 20 mm PVC conduit with 1.5 sq.mm FR grade copper wires with modular type switch and socket and required accessories as per specification No. WG-PW/SW DSR I. No. 1-9-11 P. No. 28	36	Point				
4	2 way point	12	Mtr.				
5	Supplying and erecting PVC trunking (PVC casing-n-caping) of size 25mm with accessories on wall / ceiling as per specification No. WG-MA/CON, para no. 1.1.2 DSR I. No. 1-2-11 P. No. 11	275	Mtr.				
6	Supplying and erecting mains with 3 x 2.5 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-14 P. No. 14	300	Mtr.				
7	Supplying and erecting mains with 3 x 4 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-16 P. No. 14	200	Mtr.				
8	Supplying and erecting mains with 3 x 6 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-17 P. No. 14	75	Mtr.				
9	Supplying, erecting & marking SPMCB 6A to 32A, C-series (for motor / power) in provided distribution board as specification No. SW-SWR/MCB DSR I. No. 5-3-2 P. No. 81	17	Nos				
10	Supplying, erecting & marking SPMCB 40A to 63A, C-series (for motor / power) in provided distribution board as specification No. SW-SWR/MCB DSR I. No. 5-3-4 P. No. 81	12	Nos				



11	Supplying, erecting & marking DPMCB 40A to 63A, C-series (for motor / power) in provided distribution board as per specification No. SW-SWR/MCB DSR I. No. 5-3-8 P. No. 82	6 Nos				
12	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface / flush mounted with 2 ways for incoming and 12 ways for outgoing SP MCB's on iron frame / wooden board as per specification No. SW-SWR/MCBDB DSR I. No. 5-4-19 P. No. 85	4 Nos				
13	Supplying and erecting original 1.25 mm CRCA sheet metal enclosures with 20A, 2 pin plug & earth socket and 20A, 3 pin plug top with 20A/30A single pole MCB complete erected on angle iron frame. DSR I. No. 5-4-20 P. No. 85	13 Nos				
15	Supplying and erecting modular type telephone socket two gang with safety shutter ISI mark approved make duly erected on provided plate and box with wiring connection complete DSR I. No. 1-8-16 P. No. 24	12 Nos				
16	Supplying and erecting modular type T.V. socket single outlet ISI mark approved make duly erected on provided plate and box with wiring connections complete. DSR I. No. 1-8-14 P. No. 24	10 Nos				
20	Supplying and erecting modular type computer Jack RJ 45 with safety shutter ISI mark approved make duly erected on provided plate and box with wiring connections complete. DSR I. No. 1-8-17 P. No. 24	8 Nos				
21	Supplying and erecting modular type electronic step regulator for fan two module ISI mark approved make duly erected on provided plate and box with wiring connections complete. DSR I. No. 1-8-23 P. No. 24	10 Nos				
22	Supplying and erecting telephone cable 2 pair 0.5 mm dia laid in provided PVC casing / consult as per specification No. WG/TW DSR I. No. 1-10-2 P. No. 30	200 Mtr.				
23	Supplying & installing Co-axil cable low voltage grade RG-11 as per specification No. WG-TW DSR I. No. 1-10-19 P. No. 31	150 Mtr.				
Total ( Supply +Erection) Inclusive of GST@18%						

- 1 Rate must be quoted including of all taxes.
- 2 Calculation of Taxes: - GST 18%.

  
Executive Engineer  
400 KV R.S. Division, Lamboti.

Dated  
Signature of Contractor with seal  
Address: .....