

Name of Office :- EHV (O&M) DIVISION, NANDED.
**Office Address :- 132 KV S/S JANGAMWADI, CAMPUS, MSETCL
NANDED- 431605**
**Contact No. :- 02462 – 261817 (O), 02462 – 261817 (Fax)
02462 – 261816 (P)**
Email :- ee2240@mahatransco.in ; eenanded@gmail.com

Ref. No. EE/EHV(O&M)/NND/TS/ File No.73/ 1626 Date :- 18 DEC 2017

E-Enquiry

To,

Sub: E-Enquiry for the work of stringing of missing earth wire in between tower loc.no 22 to 30 of 132kV Waghala-Tamsa line under EHV O&M Division, Nanded.

Dear Sir,

Sealed & super scribed quotation are invited from date 19.12.2017, so as to reach this office up to date 28.12.2017 up to 15:00 hrs for Work of stringing of missing earth wire in between tower loc.no 22 to 30 of 132kV Waghala-Tamsa line under EHV O&M Division, Nanded on following terms & conditions:-

TERMS & CONDITIONS :-

- 1) Due date :- The quotations completed in all respect duly sealed & superscribed as QUOTATION for Work of stringing of missing earth wire in between tower loc.no 22 to 30 of 132kV Waghala-Tamsa line under EHV O&M Division, Nanded. should be submitted with Enquiry no. & date to this office upto 15.00 HRS on or before 28.12.2017
- 2) Quoted rates – Rates should be on firm quotations basis. No Freight, Packing & forwarding charges, installation & commissioning charges will be paid extra.
- 3) You must provide the valid documents of copy of Electrical Contractor License issued by Govt. of Maharashtra, copy of PAN no, GST registration certificate, Latest IT return, Shop Act. Registration certificate, experience certificate of having successfully completed similar type of work issued by an officer not below the rank of Executive Engineer. Offer received without above documents will be liable for rejection.
- 4) Validity of offer :- The validity period of rates quoted should be 90 days from the due date of opening of quotations.
- 5) The quotations must be written with ink or type written. Any scratching or overwriting will not be allowed. You will have to pay Security Deposit at rate 5% of the total amount.
- 6) The T&P, labour, machinery, equipment, material required for the work shall be arranged by you.
- 7) The work should be completed by agency on site within 30 days from the date of issue of work order.
- 8) If you fail to complete the work within stipulated period penalty at the rate of ½ % of the order value per delayed week or part thereof subject to maximum of 10% shall be recovered from your bill.

- 9) Bill in triplicate with advance stamp receipt should be submitted to this office with the delivery challan. The VAT tax no. PAN No. should be mentioned on your bill.
- 10) **Income tax** if applicable will be deducted as per rules/ otherwise you will have to submit income tax exemption certificate or income tax registration no. of your firm.
- 11) The undersigned reserved the right to reject any or all quotations without assigning any reasons thereof.
- 12) You should be fully aware of the M.S.E.T.Trans.Co.Ltd. General Condition for execution of work and same is applicable to this contract also. Any of the condition will not exempt you from your liability to abide by the same
- 13) **Guarantee:** The work is to be done should be best & standard quality of work & as per specification should be guaranteed for minimum one year within guarantee period at your risk & cost.
- 14) In case of difference of opinion, misinterpretation of any of the condition of the contract. In connection with or arising out of the condition or during the period work, the decision of the under signed shall be final & binding on you.

Thanking you.

Yours faithfully ,



Executive Engineer
EHV (O&M) Division, Nanded

Copy s. w. rs to:

The Superintending Engineer, EHV (O&M) Circle , Parli

Copy to:

The Dy.Manager (F&A) EHV (O&M) Division, Nanded.

Notice Board / Website; www.mahatransco.in



MAHATRANSCO
MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED
EHV O&M DIVISION, NANDED

Nature of Work: Work of stringing of missing earth wire in between tower loc.no 22 to 30 of 132kV Waghala-Tamsa line under EHV O&M Division, Nanded.

SCHEDULE

Sr No	Description	Unit	Qty	Estimated Rate (per unit qty)	Quote your rates in (Rs.)
1	Mobilization & Demobilization of T & P, labours to the site location to attend work of broken earthwire during "Outage" period.	Per Occasion	1	17910	
2	Stringing of Earth wire of size 7/3.15 sq mm. on top of 132 KV towers with required Hardware such as suspension clamp, Cu flexible earth bond, Tension Clamp Etc. required for suspension/cut point type Locations. as per IS specification / standards including paving out of earth wire, and its final sagging with installation of Earthwire accessories such as fixing of vibration dampers, mid-span joints, Jumpering etc. complete in all respect as per Company's specification and directives of Engineer Incharge. Earth wire, Hardware and accessories will be provided by MSETCL (Single Circuit / Double Circuit dead line)	RMT	3000	20	

Taxes (if any) :- 1) _____
2) _____

Authorised Signatory of agency
(With rubber seal)

Sd--
Executive Engineer
EHV (O&M) Division, Nanded