

**E-ENQUIRY**

**Sub:-** E-enquiry for the work of HT LT line shifting at village Borgaon & Bondale Tal-Malshiras, Dist-Solapur.

Sealed and superscripted quotations are invited for the work as detailed below with subject to following terms & conditions.

**TERMS & CONDITIONS:**

- 1) The rate should be quoted on firm quotations basis.
- 2) The rate should be provided as per schedule A&B format as enclosed with clear bifurcations of taxes.
- 3) The Total work amount should be limited to 1 Lakhs Rupees only.
- 4) Your sealed quotations should reach this office on or before up to **Dt.-02/01/2018**.
- 5) Quotation shall be sent under sealed cover duly subscribed as our Enquiry No & Quotation for "**E-enquiry for the work of HT LT line shifting at village Borgaon & Bondale Tal-Malshiras, Dist-Solapur**" in block letters.
- 6) The service provider should provide similar work experience certificate.
- 7) The offer shall be valid for acceptance for the period of **3** months from the date of submission.
- 8) The entire work as per the scope in schedule "A & B" is to be completed within a period of **15** days from the date of handing over of the clear site for work.
- 9) All the documents i.e. PAN card, GST registration, etc. and other accompanying documents like Shop Act, Electrical Contractor License shall bear the authorized signature of agency, failing which the offer will be liable for rejection.
- 10) The material shall be guaranteed for a period of **One year (01 Year)** from the date of supply. If any defect is observed during guarantee period the same will have to be replaced / attended free of cost or as specified by manufacturer whichever is higher.
- 11) If contractor fails to execute the order, it will be treated as breach of contract & contract will be terminated & order will be cancelled by forfeiting the EMD/Security Deposit.

- 12) The material supplied for this work must be in line with MSETCL specifications & its inspection should be arranged by you before fixing it on site.
- 13) Permission from Electrical Inspector should be arranged from your end.
- 14) Engineer in charge: The Additional Executive Engineer, EHV Lines Projects Subdivision, MSETCL, Pandharpur shall be the Engineer-in-charge for execution of this work
- 15) Material Inspection: The undersigned or our authorized representative will be free to visit the contractor site stores and also verify the materials in custody of the contractor as and when required at any time.
- 16) Manpower & T& P: All the instruments, T&P, vehicles, labors etc. required for this work shall be arranged by agency. No T&P or labour will be provided by the MSETCL.
- 17) Accident & loss: If any accident is occurred to your staff during the execution of work, the whole responsibility lies on you. Also if any loss is occurred during the work to the MSETCL's property, the whole cost of equipments will be recovered from your bills or anywhere pending with MSETCL.
- 18) Contractor's Employees: Contractor should employ & provide only such employees who are skilled & experienced for execution & supervision of such type of works.
- 19) Jurisdiction of court: In case of dispute if any, legal jurisdiction of the Court shall be in Solapur only.
- 20) The undersigned has reserved the right to modify or cancel the order at any stage without assigning any reason thereof and without any liability on MSETCL.

Thanking You,

Sd/-  
(S. K. Gade)  
Executive Engineer  
EHV Proj. Div-III, Solapur

Encl:- Schedule A&B

Copy s.w.rs.to:-

1) The Superintending Engineer, EHV Projects Circle, Pune -

Copy to

1) The Manager (F&A), Proj. Div-III, Solapur

2) The Addl. Executive Engineer EHV S/Stn Proj. S/Dn, Pandharpur

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.  
EHV PROJECTS DIVISION-III, SOLAPUR.**

**Schedule A**

**Sub:-** E-Enquiry for shifting of LT line at village Borgaon Tal-Malshiras, Dist. Sojapur in r/o Location no 16.

Sr. No.	Description of Material	Unit	Qty	Rate / Unit. (Rs.)	Amount
1	Survey	LS	1		
2	PSU Pole - 8 Mtr Long	No.	3		
3	M. S. Flat 50x6 mm	Ka	20		
4	AAC (Ant.) 50 Sq. mm.	Km.	0.54		
5	AAC (Gnat.) 25 So. mm.	Km.	0.18		
<b>6</b>	L. T. Stay Set	Set	3		
7	L. T. Stav Wire (7/10 SWG)	Kg.	30		
8	L.T. Shackle Hardware	Pair	9		
9	L.T. Shackle Insulator	No	9		
10	L. T. Stav insulator	No	3		
11	L.T Earthing set	set	1		
12	Alluminum bobbin	No	3		
13	G.I. wire 8swg	kg	5		
14	Sundries	LS	1		
				<b>Total</b>	
a				<b>Total Cost of the Material</b>	
b				<b>Labour Charges on cost of material "a"</b>	
c				<b>Labour Charges for dismentling of old line</b>	
d				<b>Total Cost of Estimate ( a+b+c)</b>	
e				<b>GST @ 18% as the work is in work &amp; contract</b>	
				<b>Grand Total Estimated cost Rs</b>	
				<b>cost of estimate inclusive of GST (say)</b>	

The unit rates are ex work rates or basic rates  
Tax bifurcation are clearly mentioned

Sd/-  
Executive Engineer  
EHV Projects Div-III, Solapur

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**  
**EHV PROJECTS DIVISION-III, SOLAPUR.**  
**Schedule B**

Sub:- E-Enquiry for shifting of HT line at village Bondale Tal- Malshiras, Dist. Sojapur in r/o  
Location no 35

Sr. No.	Description of Material	Unit	Qty	Rate / Unit. (Rs.)	Amount
1	Survey	LS	1		
2	RSJ 10QX116mm-9 mtr.	No.	1		
3	11 KV Cutpoint Channel with Clamp & Nutbolt	Pair	2		
4	11 Kv Top fitting with clamp	No.	1		
5	11 KV Disc Insulator (45 KN)	No.	6		
6	Strain Hardware Hardware 55 sq.mm	Set	6		
7	55 Sqmm AAAC Conductor or Equivalent	Km.	0.36		
8	Stay Sets H. T.	Set	2		
9	Stay Wire 7/8 SWG.	Kg.	20		
10	Concreting (1:4:8)	Cmt.	1.35		
11	H. T. Earthing Set	Set	1		
12	G. I. Wire 8 SWG.	Kg.	8		
13	Danger Board	No.	1		
14	Barbed Wire	Kg.	4		
15	Red Oxide Paint	Ltr.	1		
16	Aluminum Paint	Ltr.	1		
17	Sundries	LS	1		
				<b>Total</b>	
a				<b>Total Cost of the Material</b>	
b				<b>Labour Charges on cost of material "a"</b>	
c				<b>Labour Charges for dismantling of old line</b>	
d				<b>Total Cost of Estimate ( a+b+c)</b>	
e				GST @ 18% as the work is in work & contract	
				<b>Grand Total Estimated cost Rs</b>	
				<b>cost of estimate inclusive of GST (say)</b>	

The unit rates are ex work rates or basic rates

Tax bifurcation are clearly mentioned

Sd/-  
Executive Engineer  
EHV Projects Div-III, Solapur