

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

Office of the: Superintending Engineer, EHV Project Circle, Nashik. 2nd  
Floor, Near Durga Mata Temple, Old Saikheda Road, Opp.Siddheshwar  
Nagar, Racca Plot, Jail Road, Nashik Road, Nashik 422 101.

E-mail ID:se5600@mahatransco.in

Web Site :-www.mahatransco.in



Ref No.SE/EHV/Proj/C/NSK/Tech/No./

0-0004

Date:- 1 JAN 2018

SRM e-enquiry

Sub: - E-enquiry for reconnaissance Survey of 220KV line for the proposed project of CPRI at Nasik (6Km), through SRM e-tender system of MSETCL.

Ref: RFX No.7000007230

Dear Sir,

With reference to the above, this office invites online offers from vendors registered under e-tender system of MSETCL to quote lowest rates ( item wise ) on or before 11.01.2018, as stipulated in Schedule "A" attached herewith. The terms & conditions are as follows .

For Further details please visit to :- <https://srmetender.mahatransco.in>

**Terms & Conditions:**

- 1) The vendor must be registered in SRM e-tender system of MSETCL.
- 2) The offers must be uploaded in SRM e-tender system of MSETCL with all details .
- 3) The rates ( item wise ) a/w necessary all taxes, GST etc should be clearly mentioned.
- 4) **QUALIFYING REQUIREMENTS FOR THE BIDDERS**

In order to be qualified for award of Contract, the bidder will be required to satisfy the following minimum criteria, which will take precedence over any qualification requirements that may be stated in the specifications or elsewhere in the bidding document. The bidder shall satisfy the following conditions:


- a) The bidder should have PAN No.
- b) The bidder should have registration under GST
- c) The bidder should have executed similar type of work particularly in MSETCL/Govt. Institution.
- d) A copy of transaction for payment of EMD

**Note: Duly attested copies of Certificate should be submitted with bid offer. If required, the original copies will have to be produced.**

- 5) The validity period of rates should be mentioned in the offer that should not be less than 90 days from the date of opening of offers.
- 6) The work should be carried out as per the specifications mentioned in schedule 'A'.

- 7) Besides, all the terms & conditions given this e- enquiry, the MSETCL General conditions of contract are applicable to this contract.
- 8) The bill in triplicate with valid PAN/GST No. for work carried out should be submitted to this office for payment purpose 100% payment will be effected on completion of work satisfactorily within reasonable period as per availability of funds after completion of all formalities.
- 9) Income Tax and WCT of the order amount will be deducted from the bill as per Govt Rules.
- 10) The agency will have to deposit 5 % of the order value as S.D within 08 days from the date of receipt of the LOI. and will be released after satisfactorily completion of work.
- 11) The work completion period should be 30 days from the date of receipt of Order failing which penalty @ ½% per week or maximum up to 10 % value of the order will be imposed
- 12) The right to reject any or all the offers without assigning any reasons thereof are reserved with the undersigned.
- 13) You have to upload copies of all valid certificates & registrations as mentioned above.
- 14) Quantities shown in schedule A are tentative may vary , final quantity will be intimated in work order.
- 15) In case of any dispute out of this contract the jurisdiction will be Hon. Court of Nasik only.
- 16) The E.M.D(Rs.5000/-). and SRM Enquiry Fees(Rs.105/-) is to be paid online only through SRM E-Tenders (New) Portal within the enquiry sale period.

**Note :-** All eligible interested vendors are mandated to get enrolled on SRM e-Tendering portal (<https://srmetender.mahatransco.in>)

  
Superintending Engineer  
EHV Project Circle Nashik.



Copy to

- 1) Manager (F&A), EHV Project Circle, MSETCL, Nasik
- 2) Notice Board




MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

**SCHEDULE "A"**

S No	SAP Code	Description	Unit	Tentative Qty.	Rate.
1	50003232	Preliminary survey with GPS survey, theodolite , Marking route on topo sheets representing actual field conditions etc.complete in all respect.	km	6	
2	50003231	Detailed survey with GPS /Total station / Theodolite etc. including tower spotting and schedules, preparation of tower profiles, approval of alignment, marking of route/corridor on topo sheet, village map and Khasra map, identification of forest, railway crossing, highway crossing, proposed development along the route/corridor etc. , collection of 7/12 along the route/ Corridor.	km	6	
3	50003237	Preparation of PTCC proposal & collection of Village Maps for the 132kV Lines Surveyed & marking of the line on village map required for ROW proposal along with village wise listing of Survey Nos. falling in the final route	km	6	
4	50007987	Providing dressed head stone pillars of size 150mm X 150mm X 600mm for tower centre line reference pillars & fixing in centre line by excavating 450 X 450 X 400mm pit an embedding in cement concrete 1:3:6 mixture including painting of the exposed portion by oil paint & center line marked over the pillars. Embedded pillars will be provided at every angle point with guide pillars at both directions & road, river crossing at every 2 to 3 Nos. per km. As directed by engineer in charge.	Nos.	18	
5	50007972	Excavation in soft strata hard murum for taking trial pit of size 1mtr. x 1mtr. x 3mtr. In depth. Depth restricted up to hard strata met & 1 No. per km including necessary dewatering, back filling etc. along with detail report of strata classification of excavated pit.	Nos.	6	

Note: Above qty is given tentatively & may vary while actual execution of work.

  
Superintending Engineer  
EHV Project Circle Nasik

09/2