



- OFFICE OF THE -
EXECUTIVE ENGINEER (C)
EHV Civil Constn. Cum Maintenance Division,
Maharashtra State Electricity Transmission Company Ltd.
Plot No.P21,132 KV S/Stn. Premises, MIDC, LATUR 413 531.
Tel. No. 02382 – 222373 (Office, Fax),
E_mail : ee2730@mahatransco.in,
Website: www.mahatransco.in
CIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./LTR/T/ 124

Date:- 07.03.2018

E- ENQUIRY

To,

**Sub : - E-enquiry for Providing Y type anticlimbing to compound wall at 132 kV
Sub-station Koyna Dist-Latur**

Dear Sir,

Sealed and super scribed percentage rate quotation is invited form the experienced contractors for executing the above work as per enclosed Scheduled - 'B'. The quotation should reach this office on or before 14.03.2018 up to 16.00 hrs.


Terms and Conditions :-

1. The time limit allowed for completion of the above work is **20 (Twenty)** days from the date of handing over of site, failing which the contractor shall be liable to pay compensation amount equal to 1% of the cost of the whole work or such smaller amount at the discretion of the undersigned, every day that the work remains incomplete or unfinished after due date of completion, subject to the maximum of 10 % of the cost of work order.
2. The quoted rates are inclusive of all taxes. Nothing extra will be paid on any account.
3. Income Tax will be recovered from the bill on the total value of the work done, as per the prevailing rates for which certificate, if needed will be issued from this office.
4. The contractor shall have to enclose Govt. Deptt's registration copy, GST registration copy registration copy along with quotation.
5. The work should be carried as per the standard specification mentioned in the latest edition of PWD standard specification Books, and to the satisfaction of the undersigned.
6. All tools and plants required for the said work shall be contractor's own.
7. Contractor will have to make good damages, if any done by you to Company's property during the execution of entire work at his own cost.
8. The quantity mentioned in the attached Schedule are approximate and may increase or decrease during the course of execution. Contractor has no claim for any alteration. However, Payment will be effected as per the actual measurements of work executed.
9. The undersigned have the right to slightly alter the clause of work without involving financial implications on either side.
10. Rates should be written both in figures and words in ink only. Corrections if any be scratched and rates should be re-written with dated initials.

11. Contractors will have to pay Earnest Money Deposit of **Rs. 5000.00** in cash in Division office or through Demand Draft drawn in favor of Executive Engineer (C) EHV CCCM Division, MSETCL, Latur. Mode of payment of EMD with MR. No. Date etc. should be written on the sealed envelope of quotation.
12. Contractor will have to pay the security deposit equal to 5% of the value of order within Ten days from the date of receipt of work order, in the form of cash at the office of Executive Engineer (C), EHV CCCM Division, MSETCL, Latur.
13. Contractor will be held responsible for accidents during the entire course of work and he will have to pay compensation whatsoever as per the prevailing Workman Compensation Act.
14. All the terms and conditions laid down in “ MSETCL, Booklet for the Works Contract” stands applicable for this work.
15. Security Deposit will be refunded after satisfactory completion of work and expiry of prescribed maintenance period.
16. Maintenance period will be of 90 days.
17. GST will be deducted from your bill as per the prevailing rules.
18. Right to reject any or all quotations without assigning any reasons is reserved by the undersigned.

Thanking you.

Yours faithfully,



Executive Engineer (C)
EHV CCCM Division
MSETCL, Latur.

Copy s.w.r.s to:-

The Superintending Engineer (Civil), EHV CCCM Circle, Aurangabad.

...with ref. to your lr. No. 0239 dt.03.03.2018

Copy to. :-


1. Dy. Manager (F&A)
EHV CCCM Division, Latur.
2. Adnl. Executive Engineer (Civil)
EHV CCCM Sub-division, Latur.
3. Notice Board, EHV CCCM Dn. Latur.
4. Notice Board, EHV CCCM SDn. Latur.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
EHV CIVIL SUB-DIVISION**

ABSTRACT

Name of work :- Providing Y type antilclimbing to compound wall at 132 kV Sub-station Koyna Dist-Latur

Item No.	Activity No.	Brief Description - (DSR ITEM NO/Page No.)	Unit	Qty	Rate	GST 18%	Rate Including GST	Amount
1	50013718	Dismantling R.C.C. concrete work including breaking concrete by chiselling, wedging etc. including cutting the reinforcement, stacking the serviceable materials and the debris separately upto a distance of 50 metre or spreading the debris as directed etc. complete.Specification As directed by Engineer-In-Charge.	Cum.	4.38	862.40	155.23	1017.63	4455.24
2	50013977	Providing and erecting Y type barbed wire fencing with seven rows of wire with 2.45 mm dia G.I. pipe (Rezan/ concentiDeleted ire 0.75 mm dia) with hot dip and G.I. coated hooks as per drawing supported on M.S. angle 50 x 50 x 6 mm at 2.5 mtr. c/c including fixing and fastening with wire, painting M.S. angles with one coat of red lead primer and two coat of oil paint etc. complete.	Rmt	280.00	453.30	81.59	534.89	149770.32
3	50013144	Providing and casting in situ cement concrete M-15 of trap metal for all type of concrete work as per drawings or As directed by Engineer-In-Charge., roughening the exposed faces if special finish is to be provided and curing etc. complete.Spec. No.:BdE -3 Page No. 288	Cum.	1.00	4965.35	893.76	5859.11	5859.11
4	50013156	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/granite/quartzite/gneiss metal for R.C.C. column as per detailed designs and drawing or as directed including centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel), with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V. S.I. quality Artificial Sand	Cum.	4.40	8285.79	1491.44	9777.23	43019.81
5	50013241	Providing sand face plaster externally in two coats using approved screened sand in all positions, including providing base coat of 15 mm thick in cement mortar 1:4 mixing approved water proofing compound at the rate of 1 kilogramme / 50 kg of cement and curing the same for not less than two days and keeping the surface of base coat rough to receive the sand faced treatment 8 mm thick in cement mortar 1:4 and finishing the surface by taking out grains and curing for 14 days including preparing the surface, watering and scaffolding etc. complete.Spec. No.:BdL.-7 Page No.369	Sqm.	77.00	422.87	76.12	498.99	38422.02
6	50013357	Providing and applying apex paint to exterior side of approved quality colour and shade to old and New surfaces in 2 coats including scaffolding preparing the surface by cleaning brooming etc. complete as directed by Engineer in charge. (Item is to be executed prior permission of Superintending Engineer)	Sqm.	77.00	197.50	35.55	233.05	17944.85
7	50006801	Removing Vegetation, grass, shrub, Gagar Gavat etc. and disposing it from building area	Sqm.	250.00	8.80	1.58	10.38	2596.00
Total Rs.:-								262067.36



Executive Engineer (C)
EHV CCCM Division
MSETCL, Latur.

I am ready to execute the above prescribed work worth: _____% (above/ below/ at par)
(in words) _____ above/ below/ at par the estimated cost.

Signatur & stamp of contractor