



(CIN No. U40109MH2005SGC153646)

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
INTRA OFFICE COMMUNICATION

Name of Office	: Executive Engineer, EHV Projects Division, Kolhapur
Office address	: Vidyut Bhavan, Admm. Building, 2 nd Floor, Tarabai Park, Kolhapur.
Contact No.	: 0231- 2665320 (P), 0231- 2655937 (O), 0231-2666798 (FAX)
E-Mail	: ee3610@mahatransco.in

Ref. : EE/EHV Projects/Dn./Kop/E-Enquiry/ 357

Date : 05-04-2018

Sub : E-Enquiry for balance emergency work of 132 KV Chambukhadi - Kale Line.
(Labour Portion)

Dear Sir,

The sealed & subscribed quotations are invited for balance emergency work of 132 KV Chambukhadi - Kale Line (Labour Portion) as per the Schedule 'A' attached herewith subject to following terms & conditions.


TERMS AND CONDITIONS :

- 1) The quotations should reach to this office on or before **16-04-2018 upto 16.00 Hrs.** This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- 2) The contractor has to furnish GST, PAN No. in the offer.
- 3) The following documents shall be submitted with the offer,
 - a. Valid copy of Electrical contractors license issued by Govt. of Maharashtra.
 - b. Registration under works contract Act.
- 4) The bidder should have an experience of more than 3 years in execution of similar work
- 5) **The rates quoted by the bidder, shall be considered as inclusive of GST & all other duties, taxes other levies LBW Cess, IT etc. which are payable by the contractor as per statutory regulations.**
- 6) **The bidder shall quote his overall percentage in terms of (+) or (-) percentage or above/below per on the overall total estimated cost mentioned in schedule 'A' by the Owner.**
- 7) Income tax shall be deducted from the bills at prevailing rates, as per Income Tax Act 1961.
- 8) Bids shall remain valid for 60 days after the date of bid opening prescribed by the employer.
- 9) **Security Deposit**
Within Fifteen (15) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 5% of the contract value by cash/cheque/DD.
- 10) **Period :**The time period for completion of the item under Schedule 'A' under this contract will be **3 Months.** The period shall be entitled from date of handing over of the site.
- 11) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.

- 12) Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer after proper measurements and scrutiny of bills at concerned Sub-Division Office.
- 13) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 14) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost.
- 15) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 16) The contractor shall not sub-let the works awarded on him under this contract.
- 17) The tenderer shall arrange for posting his own security personnel at his own cost to safeguard the material handed over to him not only at his storage yard but also at the work site till such time the complete job is ultimately handed over to Maharashtra State Electricity Transmission Company Ltd.
- 18) **Guarantee - The work executed under this contract shall be guaranteed for 12 months from the date of completion of work.**
- 19) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 20) Quotation incomplete in any respect shall be rejected.
- 21) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 22) Quotation received late or with incomplete details against above clauses will not be considered.
- 23) Labour welfare cess/GST/other statutory payment etc. considered in contract value will be deducted at appropriate rate prevailing during tenure of contract.

Thanking You.

Yours faithfully,


(D.M. Mahajan)

**Executive Engineer,
EHV Projects Dn. Kolhapur.**

Encl. : Schedule A.

Copy s.w.rs. to :

The Suptd. Engineer, EHV Projects Circle, Kolhapur.

- Copy to :
- 1) The Addl. Executive Engineer, EHV Line Projects S/Dn.-II, Kolhapur.
 - 2) The Manager (F&A) EHV Projects Dn. Kolhapur.
 - 3) Notice Board.
 - 4) MSETCL, Website.

M/F.

EHV PROJECTS DIVISION, KOLHAPUR

"SCHEDULE - A"

Name of Work :- Balance emergency work of 132 KV Chambukhadi - Kale Line. (Labour Portion)

Sr. No.	Particulars	Unit	QTY	Ex works (in Rs.)	GST @ 18%	Labour welfare cess @ 1% on (Exworks+F&I+GST)	Unit Rate (in Rs.)	Amount (in Rs.)
1	3	4	5	6	7=6*18%	8=(6+7)1%	9=6+7+8	10=5*8
6	Pipe type earthing: Normal earthing including excavation of pits/ trenches, laying of earthing pipe, strips, flats, etc supplying and laying salt and soft coke as directed and as per the drawing to be furnished by the owner and back filling, complete in all respects. (For loc no 33, 61)			Coal:150 Kg Salt: 15 Kg				-
	Inclusive of G.I. pipe and GI strip / Flat & Nuts and bolts	No.	2	5,050.00	909.00	59.59	6,018.59	12,037.18
7	Counter Poise type Earthing: Including excavation of pits/ trenches, laying of earth wire and fitting plates/ lugs to tower legs including supply of all materials (Viz. GI wire, lugs, nuts and bolts etc) and back filling, complete in all respect (For loc no 35, 50).				-	-	-	-
	Inclusive of G.I. Wire, lugs, nuts & bolts etc.	No.	2	11,110.00	1,999.80	131.10	13,240.90	26,481.80
8	Complete erection of DC/MC with its extensions for EHV Lines with fixing of bolts and nuts, tightening, punching and fitting including attachments including transportation of materials from site stores to work sites, & all allied works	MT of tower weight	3.4	5,555.00	999.90	65.55	6,620.45	22,509.53
10	Stringing of conductors on S/C, D/C, M/C, H/Z towers including transportation of conductor and required material from site store to site locations, laying, paving, jointing, rough sagging, final sagging, clipping, fixing of accessories, hoisting of insulators, jumpering etc. on tower complete in all respect				-	-	-	-
	132kV D/C (with 0.2 ACSR) on DC line	KM	0.70	60600.00	10,908.00	715.08	72,223.08	50,556.16

11	Stringing of Earthwire including transportation of earthwire and required material from site store to site locations, laying, fixing hardware, fixing accessories, paving out earth wire, jointing, tensioning, stringing and clamping of 7/3.15 sq. mm high tensile galvanized steel wire etc.	KM	1.00	12625.00	2,272.50	148.98	15,046.48	15,046.48
14	Dismantling charges for Tower (2 Nos)	MT	8.00	4444.00	799.92	52.44	5,296.36	42,370.87
15	Removal of stubs upto 1.5 mtr.	Set	2.00	7070.00	1,272.60	83.43	8,426.03	16,852.05
16	Dismantling of conductor lines including E/W and Stays wherever required.	KM	1.00	48480.00	8,726.40	572.06	57,778.46	57,778.46
a	Tree cutting work in Normal Area	Span	10.00	2500.00	450.00	29.50	2,979.50	29,795.00
Erection Portion (B) Total :								2,73,427.52

Note : The above rate is inclusive of GST.

I am ready to execute the above work with :

----- % Above (in words ----- % above)

----- % Below (in words ----- % below)

the estimated cost.

Signature of Contractor

Dated: -

(D.M. Mahajan)
Executive Engineer,
EHV Projects Dn. Kolhapur.