

## - OFFICE OF THE -EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division, Maharashtra State Electricity Transmission Company Ltd. Plot No.P21,132 KV S/Stn. Premises, MIDC, LATUR 413 531. Tel. No. 02382 – 222373 (Office, Fax),

el. No. 02382 – 222373 (Office, Fax E\_mail : ee2730@mahatransco.in, Website: www.mahatransco.in CIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./LTR/T/ 272

Date: - 23.05. 2018

E- ENQUIRY

To,			

Sub: - E-enquiry for providing and laying water Supply pipeline from Municipal corporation supply at 132 kV S/S Koyna, Latur Dist-Latur Dear Sir,

Sealed and super scribed percentage rate quotation is invited form the experienced contractors for executing the above work as per enclosed Scheduled - 'B'. The quotation should reach this office on or before 31.05.2018 up to 16.00 hrs.

## Terms and Conditions:-

- 1. The time limit allowed for completion of the above work is 30 (Thirty) days from the date of handing over of site, failing which the contractor shall be liable to pay compensation amount equal to 1% of the cost of the whole work or such smaller amount at the discretion of the undersigned, every day that the work remains incomplete or unfinished after due date of completion, subject to the maximum of 10 % of the cost of work order.
- 2. The quoted rates are inclusive of all taxes. Nothing extra will be paid on any account.
- 3. Income Tax will be recovered from the bill on the total value of the work done, as per the prevailing rates for which certificate, if needed will be issued from this office.
- 4. The contractor shall have to enclose Govt. Deptt's registration copy, GST registration copy along with quotation.
- 5. The work should be carried as per the standard specification mentioned in the latest edition of PWD standard specification Books, and to the satisfaction of the undersigned.
- 6. All tools and plants required for the said work shall be contractor's own.
- 7. Contractor will have to make good damages, if any done by you to Company's property during the execution of entire work at his own cost.
- 8. The quantity mentioned in the attached Schedule are approximate and may increase or decrease during the course of execution. Contractor has no claim for any alteration. However, Payment will be effected as per the actual measurements of work executed.
- 9. The undersigned have the right to slightly alter the clause of work without involving financial implications on either side.
- 10. Rates should be written both in figures and words in ink only. Corrections if any be scratched and rates should be re-written with dated initials.

- 11. Contractors will have to pay Earnest Money Deposit of Rs. 5000.00 in cash in Division office or through Demand Draft drawn in favor of Executive Engineer (C) EHV CCCM Division, MSETCL, Latur. Mode of payment of EMD with MR. No. Date etc. should be written on the sealed envelope of quotation.
- Contractor will have to pay the security deposit equal to 5% of the value of order within Ten days from the date of receipt of work order, in the form of cash at the office of Executive Engineer (C), EHV CCCM Division, MSETCL, Latur.
- Contractor will be held responsible for accidents during the entire course of work and he will have to pay compensation whatsoever as per the prevailing Workman Compensation Act.
- 14. All the terms and conditions laid down in "MSETCL, Booklet for the Works Contract" stands applicable for this work.
- Security Deposit will be refunded after satisfactory completion of work and expiry of prescribed maintenance period.
- 16. Maintenance period will be of 180 days.
- 17. GST will be deducted from your bill as per the prevailing rules.
- 18. Right to reject any or all quotations without assigning any reasons is reserved by the undersigned.

Thanking you.

Yours faithfully,

Executive Engineer (C)
EHV CCCM Division
MSETCL, Latur.

Copy s.w.r.s to:-

The Superintending Engineer (Civil), EHV CCCM Circle, Aurangabad. ...with ref. to your lr. No. 0538 dt.23.05.2018

Copy to.:-

- Dy. Manager (F&A)
   EHV CCCM Division, Latur.
- 2. Adnl. Executive Engineer (Civil) EHV CCCM Sub-division, Latur.
- 3. Notice Board, EHV CCCM Dn. Latur.
- 4. Notice Board, EHV CCCM SDn. Latur.

## MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD. EHV CCCM DIVISION LATUR

Name of work :- Providing and laying Water supply pipeline from Municipal Corporation supply at 132 kV S/S Koyna Latur Dist-Latur.

			Sched	ule b				
_	Last II		Qtr &	& Premice	5			
	No.	Brief Description - (DSR ITEM NO/Page No.)	Unit	Qıy	Rate	GST 18%	Rate Includin g GST	Amount
5		excavation for foundation in earth, soils of all types, and gravel and soft murum including removing the excavated materials upto a distance of 50 metres beyond the building area and lift upto 1.5 mt, stacking and spreading, necessary dewatering unless provided elsewhere, preparing the bed for the foundation and required backfilling, ramming, watering, shoring and strutting etc. complete. as directed. (Spec. No.: Bd A-1 / Page No. 259)	Cum.	62.37	125.00	22.50	147.50	9199.58
2	50013547	Providing and fixing in position 15mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to 1 S., 4985 & of FINOLEX Brand Schedule 40, including necessary fittings confirming to 1 S., 7834, such as P. V.C., bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.00 Kg/Sq cm., pressure) including defect liability period and bond for three years.) Spec. As directed by Engineer-In-Charge.	Rmt.	30.00	226.20	40.72	266.92	8007.48
3	5001355	2 Providing and fixing in position 50mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to I.S. 4985 & of FINOLEX brand Schedule 40, including necessary fittings confirming to I.S. 7834, such as P.V.C. bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.00 Kg/Sq.cm., pressure), including defect liability period and bond for three years )Spec. As directed by Engineer-In-Charge.		196.00	1099.80	197.96	1297.76	254361.74 4609.67
	4 500135	51 Providing and fixing in position 40 mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to 1.S. 4985 & of FINOLEX brand Schedule 40, including necessary fittings confirming to 1.S. 7834, such as P.V.C. bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.0 Kg/Sq.cm pressure() including defect liability perio and bond for three years.) Spec. As directed by Engineer-In-Charge.	0	5.00	781.30	140.63	921.93	
	5 500135	60 Providing and fixing 15 mm dia. screw down bib/sto tap of brass of approved quality and make, including necessary sockets, union nut, testing etc. complete.Spec. No.:BdV8 Page No.554	p Nos	5,00	385.00	69.30	454.30	2271.50
	6 500135	68 Providing and fixing 50mm.dia. screw down wheele stop tap of steel with chromium plating of approved quality and make bearing I.S.I. mark, including sockets, union nut complete. Spec. No.: BdV9 Page No.555	1	2.00	2001.00	360.18	2361.18	4722.36

D:\2014 - 2015\8. D. D. Fere\SRM Tenders\Quotation\Geological\Providing and laying Water supply pipeline at 132 kV Koyna Dist-Latur

1	7	50013718	Dismantling R.C.C. concrete work including breaking	Cum.	1.35	784.00	141.12	925.12	1248.91
			concrete by chiselling, wedging etc. including cutting						I
			the reinforcement, stacking the serviceable materials						
		77	and the debris separately upto a distance of 50 metre or						
			spreading the debris as directed etc.						1
			complete.Specification As directed by Engineer-In-						1
			Charge						
							To	tal Rs.:-	284,421,00

Executive Engineer ( C ), EHV CCCM Division,

I am ready to execute the above prescribed work worth:	% (above/ below/ at par)
(in words)	above/ below/ at par the estimated cost

Signatur & stamp of contractor

D:\2014 - 2015\8. D. D. Fere\SRM Tenders\Quotation\Geological\Providing and laying Water supply pipeline at 132 kV Koyna Dist-Latur