

#### OFFICE OF THE :-EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division.
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,



E-mail: ee2710@mahatransco.in CIN: U40109MH2005SGC153646

No.:EEC/EHV/CCCM/Dn./ABD//Tech/ 16 0 6 1 1

Date:- 2 9 JUN 2018

Ta	<b>Quotation</b>
To,	

Sub: Renovation in existing RTC Training center for 3 Suits, Hall and Computer Room in A Block at RTC Waluj, Aurangabad.

Dear Sir,

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Mahatransco Administration Building, first Floor,

wing no.102, Aurangabad on or before dated 06/07/2018 Time13.00 Hrs.

## TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer incharge and to the satisfaction of the undersigned.
- The quantities mentioned in the attached schedule are approximate and likely to vary However payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- The work should be completed within (15) days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost. and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.

- The contractor will have to make good the damages if any made by him during the execution of work at his own cost
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division II Aurangabad to the undersigned. Payment will be made within 30 days period from the date of receipts of bill to this office. To the work which you funds
- The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- You will have to deposit 13500.00 (5% of quotation value) as security deposit in cash/ DD/FDR of any nationalized Bank within 3 days from the date of receipt of work order, failing which EMD will stand forfeited.
- The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractors responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- The contractor has to pay earnest money to Rs. 3,000.00/- in cash/In form of DD/FDR of any
  Nationalized Bank in favor of EE (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. If the EMD of
  required amount is not found in the envelop the quotation will be rejected
- The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- Special condition: The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.

The estimated cost of the work is "Rs. 2, 61,330.00 only. (Inclusive of all Taxes)

Encl: Schedule'B'

Executive Engineer (C) EHV CCCM Division. MSETCL, Aurangabad

#### Copy S.W.R.S. to:

- 1. The Chief Engineer EHVP.C. (O&M) Zone MSETCL Aurangabad
- The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
   ...This is as per approval vide Ltr. No.685 Dtd. 28.06.2018

### Copy to:

- 1. The Addl. Executive Engineer (C) EHV CCCM Sub Division-II, Aurangabad
- The Dy. Manager(F&A) EHV CCM Division Aurangabad / The amount of this work is Chargeable to sanctioned estimate No. T-11/18-19 Dt.22.06.2018 under R&M Budget
- 3. Notice Board



#### OFFICE OF THE :-EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad,Ph. No. (0240) 2331429,
E-mail: ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/

10-0611

Date:- 2 9 JUN 2018

# (e-Enquiry) **QUOTATION NOTICE**

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Mahatransco Administration Building, first Floor, wing no.102, Aurangabad on or before Dtd. 06.07.2018 up to 13.00 hrs.

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Q. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	Renovation in existing RTC Training center for 3Suits, Hall and Computer Room in A Block at RTC Waluj, Aurangabad.		Rs 3,000.00/-	15 Days

Executive Engineer (C) EHV CCCM Division. MSETCL, Aurangabad

#### Copy S.W.R.S. to:

- 3. The Chief Engineer EHVP.C. (O&M) Zone MSETCL Aurangabad
- 4. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
  - ... This is as per approval vide Ltr. No.685 Dtd. 28.06.2018

#### Copy to:

- 3. The Addl. Executive Engineer (C) EHV CCCM Sub Division-II, Aurangabad
- The Dy. Manager(F&A) EHV CCM Division Aurangabad / The amount of this work is Chargeable to sanctioned estimate No. T-11/18-19 Dt.22.06.2018 under R&M Budget
- 3. Notice Board



#### OFFICE OF THE :-EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,



E-mail: ee2710@mahatransco.in CIN: U40109MH2005SGC153646

No.:EEC/EHV/CCCM/Dn./ABD//Tech/No.Date: - 10 =

No-067

2 9 JUN 2018

Name of Work: Renovation in existing RTC Training center for 3Suits, Hall and Computer Room in A Block at RTC Waluj, Aurangabad.

Estimated Amount: -Rs 2, 61,330.94/- (Inclusive of All Taxes)

Executive Engineer (C) EHV CCCM Division. MSETCL, Aurangabad

# **Declaration of Contractor:**

I/We hereby quote for the execution of the specified in the above written memorandum within time
specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words)
percent above/Below/Estimated rate (to be struck whichever is not
applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried
out) in accordance in all instruction in writing from the Engineer - in - Charge.
I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the
same are binding on us.

Signature of the contractor

Full Address:

# MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD. EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION, AURANGABAD SCHEDULE B

Name of work: Estimate for renovation in existing RTC Training center block "A" civil works for 3 suits, hall & computer room at RTC Waluj Aurangabad.

Est. Item NO.	Particulars	Qty	Unit	Rate Rs.	GST 18%	Final Rate	Amount Rs
1	2	3	4	5.			6
1	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.Spec. No.:BdW8 Page No.587	13.00	No	84.00	15.12	99.12	1288.56
2	Removing Any type of Flooring /dado from floor / wall without bed concrete including stacking the material as directed with all lead and lifts. Spec.No.: As directed by Engineer-in-charge.	37.00	Sqm	24.00	4.32	28.32	1047.84
3	Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts, complete. As directed by engineer incharge	1.00	Cum	502.00	90.36	592.36	592.36
4	Removing cement or lime plaster including disposing of the spoils as directed with all leads, lifts, complete. Spec. no. As directed by Engineer in Charge		Sqm	15.00	2.70	17.70	106.20
5	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc. complete. Spec.No.: As directed by Engineer-in-charge.	4.00	Cum	181.00	32.58	213.58	854.32
6	Providing second class Burnt Brick masonry with conventional / I.S. type bricks in cement mortar 1:4 in half brick thick wall including mild steel longitudinal reinforcement of 2 bars of 6 mm. diameter/2 hoop iron strips 25 mm x 1.6 mm placed at every third course, properly bent and bounded at ends scaffolding, racking out joints and watering complete. Spec.No.: Bd.G.7/Page No.316	7.00	Sqm	669.00	120.42	789.42	5525.94
7	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing complete. Spec. No. Bd.L.2 Page No.368	23.00	Sqm	190.00	34.20	224.20	5156.60
8	Providing and laying coloured vitrified tiles of approved quality colour and size of 600mm x 600mm x 10mm for flooring in required position, pattern / design laid on cement mortar (1:4) including filling joints with neat cement slurry mixed with pigment to match the colour of tiles curing rubbing and polishing complete as directed by engineer in charge. Spec. No. As directed by Engineer in charge	85.00	Sqm	1456.00	262.08	1718.08	146036.80

Est. Item NO.	Particulars	Qty	Unit	Rate Rs.	GST 18%	Final Rate	Amount Rs
1	2	3	4	5			6
9	Providing and fixing polished green marble sills, jams, treads, rise of steps including chamfering, nosing and antiskid groove as required, 25mm to 35mm thick of required size on a bed of 1:4 in C.M. including cement float filling joints with net cement slurry, curing, polishing, and cleaning complete Spec. No. As directed by Engineer in charge		Sqm	1591.00	286.38	1877.38	35670.22
10	Providing and applying Acrillic emulsion paint including priming coat on concrete / masonry/ Asbestos Cement/ plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required. Spec. No. As directed by Engineer in charge	216.00	Sqm	76.00	13.68	89.68	19370.88
11	Providing and fixing solid core flush door shutter commercial in single leaf 32 mm thick without ventilator commercial type of exterior grade as per detailed drawings with wrought iron hold fast, stainless steel fixtures and fastenings and handles on both sides and finishing with oil painting 3 coats complete.	17.00	Sqm	1665.00	299.70	1964.70	33399.90
	Providing, laying and fixing jointing Supreme Ecodrain 160 mm SN 4 Nu- Drain Upvc pipes or of equivalent make, manufacture as per EN 13476 or equivalent as per I.S.15328 with fittings such a bends, tees, coupler, etc, jointing with rubber lubricant including necessary excavation, trench refilling with selective excavated materialetc. complete.	6.00	Rmt	447.00	80.46	527.46	3164.76
	Providing and fixing in position aluminium fixed window fully glazed of any size as per detailed drawing and as directed by Engineer in charge with all necessary alluminium sections including necessary fixtures and fastenings such as 5mm thick clear float glass etc. complete. b) With powder coating Note While arriving at the rate of item of item weight at 6.90 kg/Sqm is considered.	2.10	Sqm	3679.00	662.22	4341.22	9116.56
	Estimate c						

Executive Engineer (C)
EHV CCCM Division
MSETCL Aurangabad