

 MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.	MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD. (CIN U40109MH2005SGC153646) (GST NO 27AAECM2936N1Z2)	
	Phone : (0257) 2270047 (O) Fax : (0257) 2270057 E-mail : ee5620@mahatransco.in	Executive Engineer, EHV Project Division, MSETCL, Near Old 132 KV Sub station Old MIDC, Ajintha Road, Jalgaon-425003.

No. EE/EHV/Project/JLG/Tech/ No. **114** Date: **13.0 OCT 2018**

E-Enquiry05/2018-19

Sub.: - Reconnaissance Survey and preparation of detail survey report of 132kV Transmission lines in Nandurbar District under jurisdiction of under EHV Projects Division, Jalgaon.

Dear Sir,

Please offer reasonable rates for the subject work as per the enclosed schedule 'A'. The detailed scopes of works are given below. Please note the following.

TERMS AND CONDITIONS:-

- 1 Rate shall be quoted on firm quotation basis **Exclusive of all Taxes** and shall be given in words & figures separately. The site should be visited before quoting the rates. Rate shall be valid for 60 days from the date of quotation.
- 2 Your sealed quotation should reach this office on or before **06.11.2018 by 17:00 Hrs.**
- 3 The work shall be completed within **10 days** from the date of handing over of site.
- 4 Quotation shall be sent under sealed cover duly super scribed as Quotations for _____ & Your Enquiry No. _____.
- 5 Your GSTN Registration number shall be mentioned on the quotation.
- 6 You will have to pay Security Deposit of 10% of the total work order amount and the same will be refunded after successful completion of work.
- 7 No T&P & Labour will be provided by the MSETCL.
- 8 Taxes will deducted as per prevailing act & rules or modified & levied by government time to time from your bills.
- 9 Proof regarding registration under shop & establishment Act 1978, GSTN no. Contractor License registration issued by Government of Maharashtra should be Enclosed.
- 10 The contractor should have the experience of similar work in the EHV transmission line survey during last two years. The experience certificate should be enclosed with quotation.
- 11 Penalty @ $\frac{1}{2}\%$ per week subject to maximum 10% of order value will be imposed on you for the delay in completion of work after the due date.
- 12 If any damages occur to the MSETCL property during execution of work, you will have to make them good at your own cost.
- 13 Payment will be effected by this office by cheque after satisfactory completion of work.
- 14 The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.
- 15 Please quote your PAN in the quotation.
- 16 The contractor shall ensure the safety of all the workmen, materials and equipment either belonging to him or to other working at site. The contractor shall be responsible for providing of all safety notices and safety equipment required. If any accident occurs


- during the work, the complete responsibility of the accident will be of Contractors. The M.S.E.T.Co.Ltd. shall not pay any type of compensation for any type of accident
- 17 MSETCL general Terms and Conditions for works are applicable to this contract. The undersigned reserves the rights to accept or reject any or all the Quotation without assigning any reason thereof.

Documents required to be attached along with offer:-

- I. Following are the list of qualifying documents required please attached for qualifying in the Techno-Commercial Bids for opening of the price Bids. (If yes please attach the following documents)
- Bombay shop & Establishment Act (Shop Act)
 - Valid Contractor license / Survey Registration.
 - Valid EPF registration (if applicable or undertaking thereof)
 - Valid workman compensation policy
 - Income Tax Returns of last 3 years & PAN card.
 - Performance certificate from the officer not below the rank of EE for similar experience in MSETCL
 - GST registration.

Enclosed :- Schedule 'A'

Yours Faithfully,


(M.R. Mahajan)
Executive Engineer
EHV Projects Division,
MSETCL, Jalgaon.

Copy s.w.r. to: -

The Superintending Engineer, EHV Projects Circle, Nasik.

Copy to:-

- The Manager [F&A], EHV Projects Division, Jalgaon.
- The Web Master, MSETCL.
- Notice Board.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
EHV (O&M) DIVISION, JALGAON.**

Schedule 'A'

Sub.: - Reconnaissance Survey and preparation of detail survey report of 132kV Transmission lines in Nandurbar District under jurisdiction of under EHV Projects Division, MSETCL, Jalgaon.

Sr. No.	Particulars of the material	Unit	Qty. required	Rate in Rs.	Amount in Rs
1	Reconnaissance survey of the proposal tower alignment on the field to ensure that there are no any structures, forest, grave yard irrigation tank & project location & non-agriculture land etc. are involved in the route & proposed the most economical & feasible alignment for the afore said work.	RkM	12		
2	Carrying out alignment survey with the help of standard theodolite & fixing the alignment to the satisfaction of Engineer-in-charge	RKM	12		
3	Carrying out detailed survey by standard levelling instruments at every 30 Mtr. interval or less and details of physical features such as nallas channels forest telephone and electric levies, distance of pole from tower centre line taking levels and lateral distances or raised ground and preparing field book including tracing of route map etc. complete as directed.	RkM	12		
4	Preparation of ground profile (L sector) on standard scale graph tracing paper showing all details and marking the tower spotting on ground profiles by using the approved sag template, tower spotting data and preparation of tower schedule submitting one sag template original profiles and two prints of tower schedule etc. complete.	RkM	12		
6	Providing dressed head store pillars of size 150 mm x 150 mm x 600 mm for tower centre line reference pillars and fixing in centre line by excavating 450x450x400mm pit and embedding in cement concrete 1:3:6 mix including painting exposed portion by oil paint and center live marked over pillars embedded pillars will be provided at every angle point with guide pillars at both directions and road, river crossing at every 2 to 3 nos per km. As directed by Engineer-in-charge.	Nos	36		
7	Excavation in soft strata hard murum for taking trail pit of size 1mx1mx3mtr. In depth, Depth restricted upto hard strata met at 1 No. per Km including necessary dewatering back filling etc. complete along with detailed report of strata classification of excavated pit.	Nos	12		
				Total Rs.	
				Add GST @18%	
				Work order value Total Amt Rs.	



(M.R. Mahajan)
Executive Engineer
EHV Projects Division,
MSETCL, Jalgaon.