



MAHATRANSCO



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of the Executive Engineer,
EHV Projects Division, MSETCL, Nashik
2nd Floor, Block No.08, New Administrative Building, Old Saikheda Road, Near Durga Mata
Mandir, Sailanibaba Bus Stop, Jail Road, Nashik Road, Nashik. 422 101.
Contact No.: 0253-2403141 (O), 2403143 (Fax).
e-mail: ee5610@mahatransco.in

EE/EHV/PROJ/DIV/NSK/Tech/ 1698

Date: 30.11.2018

Srm e-enquiry

To,

Sub: SRM e-enquiry for work of shifting of HT line (0.12 Km) which obstructing the work of compound wall and gantry erection work for upgradation of 132KV Manmad SS to 220KV level.

Ref: Addl.EE/EHV/Proj./SS/Sub-Dn/NSK/175 Dt 12.11.2018

Dear Sir,

Online bids through Mahatransco SRM e-enquiry system from registered agencies in MSETCL SRM E-tendering system (website <https://srmetender.mahatransco.in>) are invited for work of shifting of HT line (0.12 Km) which obstructing the work of compound wall and gantry erection work for upgradation of 132KV Manmad SS to 220KV level.

Last date of bid is **12.12.2018**

TERMS & CONDITIONS:

1. **Scope of work:** The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule-B**.
2. The rates should be quoted on firm quotation basis including T&P, vehicle, transportation charges etc required for execution of the work, & taxes if any.
3. All the instruments, T&P, vehicles, labors etc. shall be arranged by agency. No T&P or labor will be provided by the MSETCL.
4. The Contractor should furnish details of i) Experience of similar nature of work of HT/LT line in the organization MSETCL/MSEDCL/Govt/Semi Govt, ii) Electrical Contractor License, iii) Bombay shop act certificate, iv) GST Registration certificate, v) PAN,TAN etc. along with online bid.
5. Taxes will be applicable as per rule.
6. The rates should be quoted in figures as well as in words.
7. 5% Security Deposit is to be deposited in Cash/Crossed DD/Cheque before commencement of work. The same shall be refunded to you after the satisfactorily Completion of the work.

8. MSETCL will not be responsible If any damage is occurred to the contractor's equipment/T&P OR any accident to contractor's labors /personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.
9. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labor due to wrong operation shall be recovered from the bill.
10. Income tax will be deducted as per prevailing rules from the bill & a certificate to that effect will be issued to the contractor.
11. The work should be completed within 10 days from the date of handing over of clear work site, failure of such; penalty equal to ½ % per delayed week subject to the maximum of 10% of the ordered value will be levied.
12. The work should be strictly carried out as per standard specifications and up to the entire satisfaction of the Engineer-In charge.
13. The contractor will be abiding by the Rules & Regulations in force in respect of his employees & workmen under the Workmen's Compensation Act & the Contract Labor Act etc. He should be a registered contractor & documentary evidence of the same should be produced.
14. As per provision of 'Mumbai Mudrank Adhinyam, 1958 clause No.34' an agreement on appropriate value (Not less than Rs.100/-) of stamp paper shall have to be executed with MSETCL for execution of contract satisfactorily before commencing work. The amount of the fees for such an agreement shall be borne by contractor.
15. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved by the undersigned.
16. The quantities enumerated in attached Schedule 'B' are approximate & payment will be made against actual executed quantities.
17. The rates quoted should be valid for 60 days.
18. Idle charges for any reason will not be accepted.
19. Not contained herein all other terms and conditions of MSETCL will be applicable to this enquiry
20. In case of any dispute regarding this contract, the jurisdiction of the court will be Nashik.

Thanking you,

Your's faithfully,


Executive Engineer
EHV Projects Division
MSETCL, Nasik.

Copy s.w.r.to,

The Superintending Engineer, EHV Projects Circle, MSETCL, Nasik.

Copy to,

1) The Manager (F&A), EHV Projects Division, MSETCL, Nasik.

2) Notice Board.

Schedule B

Shifting of HT line (0.12 Km) which obstructing the work of compound wall and gantry erection works for upgradation of 132KV Manmad SS to 220KV level.

Sr. No	Particulars	Unit	Qty	Rate/Unit Rs.	Amount Rs.
Cost of material					
1	RSJ pole 152x152, 11m long	No.	2		
2	RSJ pole 116x100, 10m long	No.	2		
3	11KV guarding channel MS 75x40	Kg	60		
4	M.S. Channel 75x40x6 mm	Kg	60		
5	M.S. Angle 50x50x6 mm	Kg	60		
6	M.S. Flat 50x10 mm	Kg	24		
7	11KV V cross arm with clamp	No.	2		
8	11KV Top fitting with clamp	No.	2		
9	G.I. nuts Bolts	Kg	15		
10	11KV Pin insulators with GI pins	No.	12		
11	Disc insulators 11KV 7000KG	No	6		
12	Strain Hardware for 55 Sq mm AAAC	Set	6		
13	AAAC 55 mm ²	Rmt	360		
14	Sleeve joints	No.	2		
15	HT Stay set	Set	2		
16	Stay wire 7/8	Kg	14		
17	Earthing Sets H.T.	Set	2		
18	G.I. Barbed wire 'A' type	Kg	10		
19	Danger board	No.	2		
20	Concreting ration 1:4:8	Cmt	4		
21	G.I. wire 8 SWG/6SWG	Kg	15		
22	Black Bituminus Paint	Ltr	1		

23	Red Oxide Paint for 2 coats	Ltr	2		
24	Aluminium Paint for 1 coat	Ltr	1		
25	Sundries	LS	4		
A	Total Cost of material				
B	Erection cost on material - 15%				
	Total cost of estimate (A+B)				

Note-

The quantities enumerated in Schedule 'B' are approximate.


 Executive Engineer
 EHV Projects Division (111)
 MSETCL, Nasik.