

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

Name of Office	: 400 KV R.S O&M Dn. Karad.
Office Address	: Administrative Building, Ground Floor, Vijaynagar, Post – Supane, Tal – Karad Dist – Satara, Pin No. 415114
Contact No.	: 02164-255182 Fax. No. 02164-255182
Email ID	: ee3130@mahatransco.in
Website	: www.mahatransco.in.
CIN No.	: U40109MH2005SGC153646

**To Whom So Ever It May Concern**

- 1. E-Enquiry No.** :- 797 Dtd.01.12.2018.
- 2. Name of the work** :- Annual maintenance & Running of Central AC Plant at 400 KV Karad Sub-station under 400 KV R.S.(O&M) Dn.Karad.
- 3. Estimated cost** :- Rs.02,00,000/- (Approx) Including all.
- 4. E-Enquiry start date** :- 01.12.2018 at 15.00 Hrs.
- 5. E-Enquiry end date** :- 10.12.2018 at 15.00 hrs.
- 6. Last date & time of submission** :- 10.12.2018 at 15.00 hrs.
- 7. Jurisdiction** :- Division.
- 8. Name of Jurisdiction** :- 400 KV R.S.(O&M) Dn. Karad.
- 9. Department** :- Technical department.

**Sd/-**  
**(Vijaykumar H.Patil) Charge**  
**Executive Engineer**  
**400 KV R.S.(O&M)Dn.Karad.**

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

Name of Office	: 400 KV R.S O&M Dn. Karad.
Office Address	: Administrative Building, Ground Floor, Vijaynagar, Post – Supane, Tal – Karad Dist – Satara, Pin No. 415114
Contact No.	: 02164-255182 Fax. No. 02164-255182
Email ID	: ee3130@mahatransco.in
Website	: www.mahatransco.in.
CIN No.	: U40109MH2005SGC153646

No.EE/400KV RS O&M/Dn/KRD/T/N **0 0 7 9** Date : **11 DEC 2018**  
**E- ENQUIRY**


PR No. :-				
Sr. No.	VENDOR No.	NAME OF VENDOR	RFQ No.	COLL No.
01				
02				
03				
04	The Manager EHV O&M Circle, Karad			
05	Notice Board/webmaster@mahatransco.in			
06	M/F			

Sealed and superscripted quotations are invited for **Annual maintenance & Running of Central AC Plant at 400 KV Karad Sub-station under 400 KV R.S.(O&M) Dn.Karad**. The quotation giving full details of your terms and conditions for work, validity of the rates Govt. and Sales Tax etc, shall reach this office on or before **Dtd.10.12.2018 upto 15.00 Hrs. Date of opening of the quotations on the same day after 16.00 Hrs. if possible. The Estimated cost is Rs. 02,00,000/- Including All.**

You are requested to quote your reasonable rates with due consideration of the following points.

- 1) The rates quoted must be exclusive of all taxes for **Annual maintenance & Running of Central AC Plant at 400 KV Karad Sub-station under 400 KV R.S.(O&M) Dn. Karad**. Otherwise it will presume that the rates are inclusive of all taxes.
- 2) The envelope should be super scribed **QUOTATION for Annual maintenance & Running of Central AC Plant at 400 KV Karad Sub-station under 400 KV R.S.(O&M) Dn. Karad**.
- 3) Quantity mentioned is subject to variations.
- 4) Rates should be quoted both in words and figures, overwriting /surcharges should be attested.
- 5) Rates should be valid at least for 60 days.
- 6) All other general terms & conditions of MSETCL work contract are applicable to this E-enquiry.
- 7) This office reserves the right of rejecting the any or all of the E-quotations, without the assigning any reason thereof.

Yours faithfully,

  
 (Vijaykumar Hingurao Patil)  
**Executive Engineer(Charge)**  
**400 KV R.S.(O&M) Dn. Karad**

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**  
**400 KV R.S. (O&M) DN. KARAD**

**SCHEDULE 'A'**

**Sub :- Annual maintenance & Running of Central AC Plant at 400 KV Karad Sub-station  
under 400 KV R.S.(O&M) Dn.Karad.**


Labour Portion						
Sr. No.	Particulars	Unit	SAC/HSN code	Applicable rate of GST	Qty.	Net Total Rs.
A	The order for Running & Maint. of Central A.C. Plant at 400 KV R.S. Karad round the clock. The scope of work i.e. check list of A/c plant is as under :	No.	998717	18%	01	---
1	Condenser servicing					
2	Checking of high pressure cut out					
3	Checking of low pressure cut out					
4	Checking of oil pressure cut out					
5	Operation of A.H.U (Air handling unit)					
6	Checking of suction pressure					
7	Checking of discharge pressure					
8	Condensing unit fan motor checking					
9	Coupling condition					
10	A.H.U filter cleaning					
11	Compressor oil level					
12	Abnormal sound/noise etc					
13	Leakage testing					
14	Safety control checking					
15	Checking electrical interlock					
16	Checking compressor					
17	Checking foundation bolts					
18	Lubrication of bearing					
19	Compressor oil bearing					
20	Down calls					

Supply Portion						
Sr. No.	Particulars	Unit	SAC/HSN code	Applicable Rate of GST	Qty.	Net Total Rs.
<b>B.</b>	<b>Supply of material for AMC of Central A.C. Plant if required.</b>					
1.	Compressors suitable for Central Air Conditioner	No.	84148011	28%	01	---
2.	Bearing with base mounting	No.	84148011	28%	04	---
3.	Fuse	No.	85361090	28%	10	---
4.	Ferron gas R-22	No.	29037100	28%	Approx 80 Kg.	---

Note :-Quantity may vary in Sr No. B depending on actual site conditions.

**SCOPE OF THE WORK:-**

- a) You will have to run & maintain the Central A.C. Plant at 400 KV R.S. Karad round the clock. You must visit & inspect the Central A.C. Plant at 400 KV R.S. Karad daily for monitoring of the healthiness of the centralized AC plant. If any call from the concern regarding the centralized AC plant you will have to attend the same immediately.
- b) The preventive maintenance of the Central A.C. plant should be carried out once in a month as per Schedule 'A' with skilled and qualified personnel having experience of A.C. plant under supervision of Addl.Ex.Engineer (Maintenance) unit 400 KV R.S.Karad.
- c) You have to attend the break down work within 12 Hrs. from the receipt of telephonic message from concerned office. No any T&P, manpower, transportation will be supplied by MSETCL.
- d) There is no limitation for attending break-downs.

  
 (Vijaykumar Hindurao Patil)  
 Executive Engineer(Chrg)  
 400 KV R.S.(O&M) Dn. Karad