

- OFFICE OF THE -EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad,Ph. No. (0240) 2331429,
E-mail: ee2710@mahatransco.inCIN: U40109MH2005SGC153646

RIGHT

No.: EEC/EHV/CCCM/Dn./ABD//Tech/No.

1 - 1242 Date: -

Corrigendum to E-enquiry

Please refer to E-enquiry published vide T.O ltr No.1240 Dtd. 19.12.2018, In this connection the schedule attached with e-enquiry is excluding GST. Hence, please find herewith the detail schedule with GST.

Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Copy S.W.R.S. to:

The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
 ...This is as per approval vide Ltr. No. 1312 Dtd. 01.12.2018

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD. EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION, AURANGABAD SCHEDULE B Name of work :- Providing & Fixing Submersible pump along with accessories at RTC Waluj under 400 KV RS Division Waluj

| Sr.No | DSR Ref. | Particulars of Item | Qty. | Unit | Rate | Add 18% GST | Final Rate | Amount Rs. |
|-------|----------|---|--------|-----------|----------|----------------|------------|------------|
| 1 | 12-2-36 | Supplying and erecting submersible pumpset of 1.5 KW/2 HP with 230 V, 50 c/s AC supply suitable for 100 mm dia. borewell suitable for 10 to 50 LPM discharge at 54 to 15 m head & (max. efficiency at 39 m head & 30 lpm) discharge & delivery pipe of Size-40 mm diameter with a necessary H type clamps as per specification no. WP-SMP | 1.00 | No | 18822.00 | 3387,96 | 22209 96 | 22209 96 |
| 2 | 12-4-20 | Supplying and erecting D.O.L. Starter400V. 3 phase, 50 cycles with no volt coil and overload element with necessary materials and connected to supply upto 7.5 H.P. (Similar to L& T make MK-1 DOL Model) | 1.00 | No. | 1790.00 | 322.20 | 2112.20 | 2112.20 |
| 3 | 12-4-9 | Supplying and erecting flat flexible 3 core 4 sq mm PVC sheathed submersible type copper cable suitably clamped at fixed intervals with column pipe assembly complete. | 130.00 | Rmt | 164 00 | 29.52 | 193.52 | 25157.60 |
| | | | - | Total Rs. | | | | 49479.76 |

Executive Engineer (C)
EHV CCCM Division MSETCL Aurangabad