


**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn/ABD//Tech/

16-006Z

Date:-

16-006Z

Quotation

To,

.....
.....
.....

Sub: Renovation of toilet block at 132kv S/stn Ambad, Dist- Jalna.

Dear Sir,


Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or **before dated 24/01/2019 Time 16.30 Hrs.**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within (15) days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost. and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost
- 9) The material should be got approved prior to fixing from the Engineer in-charge.

- Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
 - 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
 - 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-II Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
 - 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
 - 15) You will have to deposit **13,500.00** (5% of quotation value) as security deposit in cash or DD of any nationalized Bank within 10 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
 - 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
 - 17) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
 - 18) The contractor has to pay earnest money to **Rs. 3,000.00/-** in cash/In form of DD/FDR of any Nationalized Bank in favor of EE (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. If the EMD of required amount is not found in the envelop the quotation will be rejected
 - 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
 - 20) GST will be recovered from your bill as per GST norms.
 - 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
 - 22) The estimated cost of the work is **Rs. 2,71,633.10** only. (Inclusive of all Taxes)
 - 23) The Contractor has to submit the Civil Works Registration Certificate, GST Registration and PAN card.

Encl: Schedule 'B'


Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad


Copy S.W.R.S. to:

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.

...This is as per approval vide Ltr. No. 089 Dtd. 11.01.2019

**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
Wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD/Tech/

Date:-

**(e-Enquiry)
QUOTATION NOTICE**

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Aurangabad on or before Dated **24/01/2019 Time 16.30 Hrs.**

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Q. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	Renovation of toilet block at 132kv S/stn Ambad, Dist- Jalna	Rs. 2,71,633.10	Rs. 3,000.00	15 Days


Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Copy S.W.R.S. to :

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
...This is as per approval vide Ltr. No. 089 Dtd. 11.01.2019-

**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**


EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/No.Date: -

Name of Work: Renovation of toilet block at 132kv S/stn Ambad, Dist- Jalna.

Estimated Amount: - Rs. 2,71,633.10(Inclusive of All Taxes)


Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Quotation for Works

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor

Full Address:

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

EHV CCCM Division Aurangabad.

Name Of Work: Renovation of toilet block at 132kv S/stn Ambad, Dist- Jalna.

SCHEDULE B

Sr. No.	Service Activity No.	Particulars	Qty.	Rate	Add 18% GST on Col 4)	Final Rate (Col.4 + Col.5)	Unit	Amount Rs. (Col.4 x Col.7)
1	2	3	4	5	6	7	8	9
1	50013698	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	79.00	37.00	6.66	43.66	Sqm	3449.14
2	50013238	Providing internal cement plaster 20 mm thick in two coat in cement mortar 1:4 without neeru finish concrete or brick surfaces, in all positions including scaffolding and curing complete. (Spec. No. Bd.L-4, Page No. 368)	67.00	396.55	71.38	467.93	Sqm	31351.31
3	50003687	Providing and applying Two coats of wall care Putty of 2mm thickness for plastered surface and 5-6mm thickness finished concrete surface to Ceiling and Walls to prepare surface even and smooth of Brands BERLA WHITE, BERGER, BISION, J.K., make, etc complete. a) For plastered walls/ceiling 2mm	79.00	112.00	20.16	132.16	Sqm	10440.64
4	50013345	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	79.00	28.00	5.04	33.04	Sqm	2610.16
5	50013351	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.	79.00	35.40	6.37	41.77	Sqm	3299.83
6	50013701	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	56.00	32.00	5.76	37.76	Sqm	2114.56
7	50013138	Providing and laying in situ cement concrete of 1:4:8 proportion with trap/ granite/ quartzite/ gneiss metal in foundation including necessary form work, compacting and curing etc. complete. (with reversible drum type mixer with SCADA with Natural / VSI standard Artificial Sand)	2.00	4674.60	841.43	5516.03	Cum	11032.06
8	50005835	Providing and laying ceramic tiles of having size 30 cm x 30 cm conforming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	15.00	979.64	176.34	1155.98	Sqm	17339.70
9	50005844	Providing and laying ceramic tiles of having size 30 cm. x 30 cm. and conforming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	49.00	1030.64	185.52	1216.16	Sqm	59591.84
10		Removing urinal pans or wash hand basins with frame including disconnecting the sanitary and water supply connections, removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc complete	1.00	68.00	12.24	80.24	No	80.24
11		Providing and fixing White Glazed Earthenware full stall type Urinal with P.V.C. flushing cistem of 5 liters capacity with fitting, inlet pipes and stop tap, brackets for fixing the cistem, 32 mm dia. P.V.C flush pipe with fittings and flushing arrangement including lead soil pipe, lead trap, soil pipe connection to the outside face of the wall	1.00	7240.00	1303.20	8543.20	No	8543.20
12		Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	1.00	4165.00	749.70	4914.70	No	4914.70
13		Providing and fixing 15 mm diameter PVC Aqua kraft type of approved make super Pillar tap with flange including all accessories etc complete	1.00	432.00	77.76	509.76	No	509.76
14	50013306	Providing sills of required material 20mm to 25mm thick, on a bed of cement mortar 1:4 including cement float, filling joints with neat cement slurry, curing, polishing, rounding edges, cleaning complete. b) Granite	6.00	3302.64	594.48	3897.12	Sqm	23382.72
		Providing and fixing FRP Door Shutter 35 mm thick Factory Made Shutter as per detailed drawings approved all necessary stainless steel fixtures and fastenings, etc. complete.	4.00	2678.12	482.06	3160.18	Sqm	12640.72
15	50013453	Providing and fixing in position anodised (as per IS 1868/1982) Aluminium fixed staggered (Z Type)Ventilator with aluminium rectangular pipe 63 mm x 38.10 mm x 1.22 mm at weight 0.650 Kg/Rmt, Aluminium angle of size 15 mm x 15 mm x 1 mm, aluminium channel of 9 mm sizes, S.S.mosquito net of 304 Grade, 4 mm thick float glass per detailed drawing and as directed by Engineer in charge etc.complete.	2.00	2805.00	504.90	3309.90	Sqm	6619.80
16	50013514	Providing and fixing mild steel grill work for windows, ventilators etc. 20 kg/sqm as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.	2.00	1468.00	264.24	1732.24	Sqm	3464.48
17	50013215	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	15.00	381.64	68.70	450.34	Sqm	6755.10

Sr. No.	Service Activity No.	Particulars	Qty.	Rate	Add 18% GST on Col 4)	Final Rate (Col.4 + Col.5)	Unit	Amount Rs. (Col.4 x Col.7)
18	50013213	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, flooring using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing (and filling joints of Nahani trap and any outlet by properly) etc. complete.	71.00	389.73	70.15	459.88	Sqm	32651.48
19	50013692	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	3.00	111.00	19.98	130.98	No	392.94
20	50013714	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed con-crete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materials out side etc. carefully and throwing out the refusal outside etc. complete.	1.00	147.00	26.46	173.46	No	173.46
21	50013583	Providing and fixing 1st class white glazed earthenware Orissa Type W.C. Pan 580 mm dia including P or S trap cast iron soil and vent pipe upto the outside face of the wall (1:5:1 0) cement concrete bedding 15 mm thick, 10 liter P.V.C. flushing cistern with all necessary pipe connection etc. complete.	1.00	5588.00	1005.84	6593.84	No	6593.84
22	50013613	Providing and fixing 10cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete.	2.00	874.00	157.32	1031.32	No	2062.64
23	50013643	Providing and fixing 15cm x 10cm salt glazed stoneware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stoneware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	2.00	1084.00	195.12	1279.12	No	2558.24
24	50013625	Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm conforming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number, filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete. (The contractor shall give 3 yrs guarantee bond for payment)	12.00	408.00	73.44	481.44	Rmt	5777.28
25	50006176	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	25.00	194.00	34.92	228.92	Rmt	5723.00
26	50013560	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.	4.00	540.00	97.20	637.20	No	2548.80
27	50014106	Engaging of labours for various civil maintenance works unskilled male labour	3.00	464.00	83.52	547.52	Per Man day	1642.56
28	50014107	Engaging of labours for various civil maintenance works unskilled female labour	3.00	464.00	83.52	547.52	Per Man day	1642.56
29	50014095	Conveying materials, obtained from road cutting, including all lifts, laying in layers breaking clods, dressing to the required lines, curve, grades and sections for a lead of over 50 m. to 300 m. inclusive from the site of excavation to the site of deposition etc. complete. as directed by Engineer in charge. Spec. No.: Rd. 18 Page No. 197.	11.00	133.00	23.94	156.94	Cum	1726.34
							Total Rs.	271633.10


 Executive Engineer (C),
 EHV CCM Division,
 MSETCL, Aurangabad.