

<b>Name of Office</b> : Office of the Chief Engineer, EHV PC O&M Zone, M.S.E.T.C.L. ,Nashik
<b>Office address</b> : 2 <sup>nd</sup> Floor, Administrative Building, Old Saikheda Road, Sailanibaba Stop, Jail Road, Nashik Road :- 422 101
<b>Contact No</b> : 0253-2403010 (O), FAX : 0253- 2403000
<b>Email Id</b> : cenashik@mahatransco.in
<b>Website</b> : <a href="http://www.mahatransco.in">www.mahatransco.in</a>

Ref :-CE/EHV Projets cum O&M/Zone/ Nashik/T-30/No.289

Date: **07.02.2019**

**e- Enquiry**

**Sub:** - Providing & installation audio system for Auditorium Hall at Administrative Building, Racca Plot, Jail Road, Nashik Road.

**Dear Sir,**

Please offer your reasonable rates for the subject work. The detailed scope of work is given as per Annexure "A" and as given below:-

- 1) DUE DATE:** - The quotations complete in all respects, duly sealed & super scribed should be submitted to this office on or before **16.02.2019** up to **17:00 Hrs** positively.
- 2) SCOPE OF WORK :-**  
The detailed scope of work is given as per Schedule "A" and as per technical specification attached herewith.
- 3) QUOTED RATES:** - The quoted rates should include all skilled and unskilled labour and also the requisite T & P, consumable, incidental charges etc. Also the cost of items strictly as per specification. Taxes & Charges shall be mentioned clearly. If not mentioned it will be considered inclusive of all taxes & charges.
- 4) Offer** shall be submitted alongwith the catalogue with duly marking the product quoted and technical specification, manufacturer/make of materials.
- 5) COMPLETION PERIOD:** - The total period of contract is 30 days from the date of handing over of site.
- 6) PAYMENT:-** The Bills in triplicate should be submitted to concern office. After recording of measurements by concerned engineer in-charge, the bill will be certified by concern Executive Engineer or his representative. The payment will be made within a reasonable time by Concern Office.
- 7) SCURITY DEPOSIT:** - The successful bidder will have to pay an amount equivalent to 5% of contract value towards Security Deposit at Concern office.
- 8) GUARANTEE:** Material must be guaranteed for at least for 1 Year from the date of successful installation.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**

---

**9) VALIDITY OF OFFER:** - The offer should be valid for **30 days** from the due date

**10) DOCUMENT REQUIRED:-** The rate offer must be accompanied with following documents duly attested & signed by vender-

- i) GST registration certificate
- ii) PAN Card
- iii) Previous Order copies, if any

**11)** The undersigned have the reserve right for relaxation of any condition mention above.

**12)** The undersigned reserved the rights for cancellation of any or all quotations without assigning any reason.

**Encl:** Schedule A & Technical specification

**Yours faithfully,**

**-S/d-**

**Chief Engineer**

**EHV Projects Cum O&M Zone, Nashik**

**Copy to:-**

- 1) The Superintending Engineer, MSETCL, CCCM Circle, Nashik.
- 2) The AGM (F&A), MSETCL EHV PC O&M Zone, Nashik.
- 3) The Executive Engineer (Admin), MSETCL, EHV PC O&M ZONE, Nashik
- 4) Notice Board

**Schedule 'A'**

**Sub:-** Providing & installation audio system for Auditorium Hall at Administrative Building,  
Racca Plot, Jail Road, Nashik Road

<b>Sr. No</b>	<b>Particular</b>	<b>Unit</b>	<b>Basic Rate (Ex Works) in Rs.</b>	<b>GST rate in %</b>	<b>GST Amount</b>	<b>Rate Including GST</b>
1	Audio Mixer	No.				
2	Loud Speaker (wall mounted)	No.				
3	Speaker Ceiling	No.				
4	Professional Power Amplifier	No.				
5	MIC- Cordless	No.				
6	Collar Microphone	No.				
7	Cable MIC	No.				
8	Trolley	No.				
9	Cables/Connectors	No.				

-S/d-

**Chief Engineer**  
**EHV Projects Cum O&M Zone Nashik**

**Technical Specification**

**Sub:-** Providing & installation audio system for Auditorium Hall at Administrative Building, Racca Plot, Jail Road, Nashik Road

<b>Sr. No.</b>	<b>Description</b>	<b>Minimum Technical Specification required</b>
1	Audio Mixer	AC 100-240V, 50-60 Hz, 16 channel mixer with 2 Auxiliary
2	Loud Speaker (wall mounted)	450 Watts, Frequency response: 60Hz - 20kHz, Size: 10 inch
3	Speaker Ceiling	30 Watts, Frequency range: 50Hz - 16kHz, Sensitivity 97dB (1kHz-8kHz)
4	Professional Power Amplifier	250 Watts, Impedance 4 and 8 Ohm, Frequency 50 (+-5%), Frequency Response 50-15000 (+-3db)
5	MIC- Cordless	Dual Channel, 2 x 1.5V AA, Frequency range: 50Hz - 16kHz, Receiver: 240V AC 50Hz for AC Adaptor
6	Collar Microphone	Frequency response 50-50000Hz AC:220-240 V for adapter, RF Output:10mW
7	Cable MIC	Impedance. : 350 $\Omega$ , Sensitivity. : 50dB $\pm$ 3dB. Frequency Response. : 50Hz-15kHz
8	Trolley	Wooden trolley, open on both side, with wheel
9	Cables/Connectors	Standard audio cable.

-S/d-  
**Chief Engineer**  
**EHV Projects Cum O&M Zone Nashik**