



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
(CIN No.U40109MH2005SGC153646)

Office of the Executive Engineer 400KV RS Division Khadka (MSETCL) Khadka-Bhusawal ,Pin-425201 Mobile No.8554989396		
Phone No (02582) (O) 247308,	(Control Room) 247 698	Fax No-(02582) 247 308
Email : ee5240@mahatransco.in		Web Site- www.mahatransco.in

Ref. No. EE/400KV/RS/Dn/KDK/BSL/ **NO=0.115** Date: **11 FEB 2019**
E-Enquiry

Subject: - E- Enquiry for Work of P&F of Electrical wiring material of 32 Nos. of Air conditioners in 400 GCR control room with removing of existing wiring at 400 kV RS Dn. Khadka-Bhusawal.

Dear Sir,

Sealed and super scribed quotations are invited for the above work as per enclosed schedule 'A'. You are requested to quote your rates for the above work. The terms and conditions are as follows.


TERMS AND CONDITIONS

- 1. Due Date:** - The quotation complete in all respect, duly sealed & super scribed should be submitted to this office on or before **Dt.18.02.2019 up to 15:00 Hrs** Positively.
- 2. Scope of work :-** As detailed in schedule 'A'
- 3. Quoted Rates:** - The quoted rates should include the cost of material, all skilled and unskilled labour and also the requisite T & P, incidental charges etc. The Taxes will be clearly mentioned, & if the Taxes are not clearly mention, then it will be considered as Inclusive of all taxes.
- 4. Validity of Offer:** - The offer should be valid for a period of 180 days from the date of the work order.
- 5. Security Deposit:** - The successful contractor shall have to deposit the security deposit @5% of contract value towards security deposit in this office by Cash/DD/B.G./FDR before commencement of the work. The same shall be refunded to you after satisfactorily completion of work and Guarantee period as per availability of funds.& if the work is not satisfactory/completed the same should be forfeited by MSETCL.
- 6. Agreement:-** An Agreement is required to be executed by the person with the companies on stamp paper of Rs. 500/- containing all the terms and conditions of the order before its execution as per Mumbai Stamp Duty 1958 Clause No. 63.
- 7. Supervision Officer:** - The work shall be supervised by the Add. Executive Engineer S/Stn. Maintenance Khadka or his representative and it should carry out to the satisfaction of Engineer in charge. In case of any dispute, decision of undersigned shall be final and binding on the contractor.
- 8. Work Completion Period:** - The Work completion period is 90 days from the site handed over/ instructions from incharge.
- 9. Submission & Payment of Bills –** You should have to submit the Original bill in Triplicate to this office under the name of undersigned along with Work completion report, Guarantee Certificate etc.. After that 100% Bill payment will be paid to you by account payee Cheque in reasonable time and as per the availability of funds after the satisfactory completion of work and as per Bill Certified by Add.E.E. (M) 400 kV R.S.Khadka-Bhusawal.
- 10. Please quote your PAN No. and GST No. on your quotation/Bill, otherwise, Taxes as per rules will be deducted from your bill.**
- 11. Taxes:** - According to the financial Act 194 (C) of 1972 Income tax & 1% Labour Cess will be deducted from your Bill at the applicable rate of the contract value and certificate to that effect will be issued to you.

- 12. Document required:** - The offer rate must be accompanied with following documents.
- I. Valid Electrical Contractor License.
 - II. Firm Registration copy or Shop Act establishment Copy or NOC of Gram Panchayat.
 - III. Valid GST Registration Copy if applicable.
 - IV. PAN Card Xerox.
 - V. Work order copies/Performance certificate issued by authority not below the Rank of Executive Engineer of similar type of works or any type of electrical work of HT/ LT line as a Proof of experience in any type of Govt. /Semi-Govt. utilities.
- 13.** Undersigned reserved the right to accept any quotation or to reject/ accept all the quotation without assigning any reason. For any dispute/differences arised, that will be subjected to jurisdiction of Bhusawal court only.
- 14. PENALTY:** - In case the work are nor carried out in time, the supplier shall be liable to pay penalty @ ½ % of the price per week delayed, or part thereof, subject to a maximum of 10% reckoned on the contract value of such complete portion or section of the plant, equipment or material including the portion supplied which could not be brought in to commission due to any part thereof not being delivered in time. The penalty will be levied subject to **force majors'** conditions, for which documentary evidence will have to be produced to the satisfaction of the competent authority of the Board. In the event of failure to supply, our Company may purchase the ordered materials at the cost & risk of the supplier in the open market.
- 15.** MSETCL Reserve rights to add more terms during the contract period if found necessary.
- 16.** For any accident of your staff, public and MSETCL staff while carrying out the work; you will be responsible for any compensation etc.
- 17.** If any damage occurs to the company's property during execution of above work, contractor will have to make them good at his cost.
- 18.** Agency should have to pay **Rs. 100** against enquiry Quotation Fees by cash to this office & copy of receipt attached with quotation.

Thanking You.

Yours Faithfully.


(A.M. Dalela)
Executive Engineer
400 kV RS Dn, MSETCL,
Khadka- Bhusawal.


Copy s.w.r. to: -The Superintending Engineer, EHV (O&M) Circle, Bhusawal.
-For information please.

Copy to:-1. The Addl.Executive Engineer, SM S/Dn., 400 kV R/S., Khadka-Bhusawal.
2. The Dy. Manager (F&A) 400KV R.S. Division, Khadka -Bhusawal.

SCHEDULE 'A'

Subject: - Work of P&F of Electrical wiring material of 32 Nos. of Air conditioners in 400 kV GCR control room with removing of existing wiring at 400kV RS Dn. Khadka-Bhusawal.

Sr. No.	Specification	Unit	Qty.	Rate	Total Amount
1	Supplying and erecting PVC box trunking of size 75x50 mm. with accessories on wall/ceiling as per specification No: WG-MA/BOX.	Mtr.	200		
2	Supplying & erecting mains with 3x6 sq.mm F.R.L.S copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WG-MA/BW	Mtr	1150		
3	Supplying and erecting flush type shockproof plug socket 6A & 16A (6 pin) with 16A switch combined with indicator lamp and fuse with gang box on wooden board.	Each	32		
4	Supplying & erecting 16 amps 3 pin plug Top Bakelite type of 230VA.C. Supply	Each	32		
5	Supplying and erecting 16 to 32 A DPMCB suitable to fix in 2 module of modular switch in provided box complete & duly concealed with necessary material and connections.	Each	32		
6	Dismantling the existing Aluminum/copper mains, submains wiring up to 10 sq.mm. Along with accessories etc. Complete as per specification No: WG-DM/PW	Mtr	1150		
				Total	
				GST 18% on above amount	
				Total Amount Including of GST taxes	
				Labour Cess 1% on Total amount	
				Grand Total Including of all taxes, Otherwise tax will be paid as per Prevailing rates	


Executive Engineer
400kV RS O&M Dn.MSETCL
Khadka-Bhusawal.