



MAHA TRANS CO



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of the Executive Engineer,
EHV Projects Division, MSETCL, Nasik
2nd Floor, Block No.08, New Administrative Building, Old Saikheda Road, Near Durga Mata
Mandir, Sailanibaba Bus Stop, Jail Road, Nashik Road, Nashik. 422 101.
Contact No.: 0253-2403141 (O), 2403143 (Fax).
e-mail: ee5610@mahatransco.in

EE/EHV/PROJ/DIV/NSK/Tech/

No 4 03 - 3
SRM e-enquiry

Date: 6 MAR 2019

To,

Sub: SRM e-enquiry for work of shifting of 33kV Belha line which obstructing the construction work for 132kV Alephata-Ghargaon line.

Ref: Addl.EE/EHV Line Project/SDn/BBLR/28 Dt 31.01.2019

Dear Sir,

Online bids through Mahatransco SRM e-enquiry system from registered agencies in MSETCL SRM E-tendering system (website <https://srmetender.mahatransco.in>) are invited for for work of shifting of 33kV Belha line which obstructing the construction work for 132kV Alephata-Ghargaon line.

RFx No. 7000012039

Last date of bid is 19.03.2019


TERMS & CONDITIONS:

1. **Scope of work:** The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule-B**.
2. The rates should be quoted on firm quotation basis including labor charges, T&P etc. required for execution of the work, transportation charges, & taxes if any.
3. All the instruments, T&P, vehicles, labors etc. shall be arranged by agency. No T&P or labor will be provided by the MSETCL.
4. The Contractor should furnish details of i) Experience of similar nature of work of HT/LT line in the organization MSETCL/MSEDCL/Govt/Semi Govt, ii) Electrical Contractor License, iii) Bombay shop act certificate, iv) GST Registration certificate, v) PAN,TAN etc. along with online bid.
5. Taxes will be applicable as per rule.
6. 5% Security Deposit is to be deposited in Cash/Crossed DD/Cheque before commencement of work. The same shall be refunded to you after the satisfactorily Completion of the work.

7. MSETCL will not be responsible If any damage is occurred to the contractor's equipment/T&P OR any accident to contractor's labors /personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.
8. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labor due to wrong operation shall be recovered from the bill.
9. Income tax will be deducted as per prevailing rules from the bill & a certificate to that effect will be issued to the contractor.
10. The work should be completed within 10 days from the date of handing over of clear work site, failure of such; penalty equal to ½ % per delayed week subject to the maximum of 10% of the ordered value will be levied.
11. The work should be strictly carried out as per standard specifications and up to the entire satisfaction of the Engineer-In charge.
12. The contractor will be abiding by the Rules & Regulations in force in respect of his employees & workmen under the Workmen's Compensation Act & the Contract Labor Act etc. He should be a registered contractor & documentary evidence of the same should be produced.
13. As per provision of '**Mumbai Mudrank Adhinyam**, 1958 clause No.34' an agreement on appropriate value (Not less than Rs.100/-) of stamp paper shall have to be executed with MSETCL for execution of contract satisfactorily before commencing work. The amount of the fees for such an agreement shall be borne by contractor.
14. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved by the undersigned.
15. The quantities enumerated in attached Schedule 'B' are approximate & payment will be made against actual executed quantities.
16. The rates quoted should be valid for 60 days.
17. Idle charges for any reason will not be accepted.
18. Not contained herein all other terms and conditions of MSETCL will be applicable to this enquiry
19. In case of any dispute regarding this contract, the jurisdiction of the court will be Nashik.

Thanking you,

Your's faithfully,


Executive Engineer (I/c)
EHV Projects Division
MSETCL, Nasik.

Copy s.w.r.to,

1) The Superintending Engineer, EHV Projects Circle, MSETCL, Nasik.

Copy to,

1) The Manager (F&A), EHV Projects Division, MSETCL, Nasik.

2) Notice Board.

Schedule B

Work of shifting of 33kV Belha line which obstructing the construction work for 132kV Alephata-Ghargaon line.

Sr. No	Particulars	Unit	Qty	Rate/Unit Rs.	Amount Rs.
Cost of material					
1	RSJ pole 152x152, 11m long	No.	2		
2	M.S. Channel 100x50x6 mm	Kg	54		
3	M.S. Angle 75x40x6 mm	Kg	24		
4	M.S. Flat 50x10 mm	Kg	18		
5	33kV Pin insulators with G.I.pins	No.	3		
6	Disc insulators 11kv 7000KG	No	9		
7	HT Stay set	Set	4		
8	GI stay wire 7/4mm (8SWG)	Kg.	40		
9	33kV, 300sqmm XLPE cable OD joints	No.	2		
10	Sand	Cmt.	100		
11	Concreting ration 1:4:8	Cmt.	5		
12	G.I. wire 8 SWG/6 SWG	Kg.	20		
13	G.I. nuts Bolts	Kg.	6		
A	Total Cost of material				
B	Erection cost on material - 15%				
	Total cost of estimate (A+B)				

Note-

The quantities enumerated in Schedule 'B' are approximate.


Executive Engineer (I/c)
EHV Projects Division
MSETCL, Nasik.