

EHV Construction Division-I, Pune
925, Kasba Peth Admn. Building, 3rd Floor, PUNE-11.

Tel No. 020-24579223 Fax No. : 020-24573602 E mail : ee6610@mahatransco.in

No. EE/EHVPD-I/PN/T/ Enquiry/ 784

Date 16.04.2019

Sub : Extension Enquiry (Rfx no- 7000012379) for detail survey for balance work of 132kv Kothrud-Phursungi line.

Dear Sir,

Please quote your lowest percentage rates for the works indicated in schedule 'A' enclosed on following terms & conditions:

TERMS & CONDITIONS :

1. Rate shall be quoted inclusive of taxes. The site should be visited before quoting the rate. Rate shall be valid for 60 days from the date of quotation.
2. Quote your percentage rate through SRM (Rfx no- 7000012379) for detail survey for balance work of 132kv Kothrud-Phursungi line on or before **22.04.19** (upto 17:30hr). You should upload the PAN card copy, Shop act license copy, GST registration copy and experience certificate.
3. No T & P & Labour will be provided by the Company.
4. The work shall be completed within **60 Days from the date of handing over of site** otherwise penalty @ 1/2% per week subject to max.5% of the order amount will be levied at the discretion of the Competent Authority.
5. Income tax will be recovered from your bill as per rule.
6. If any damages occur to the MSETCL property during execution of work. You will have to make them good at your own cost.
7. 100% payment will be effected by this office by cheque after satisfactory completion of work.
8. The contractor should have the experience of similar work in the EHV transmission line survey during last two years.
9. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.

Thanking you.

Yours faithfully,

SD/-
Executive Engineer
EHV Projects Division-I, Pune

Encl: 1) Schedule 'A'

Copy to: 1. The Addee , S & I S/Dn, Pune
2. The Manager (F&A), EHVPD-I,Pune
3. Mf

Schedule 'A'

Sub: Detail survey for balance work of 132kv Kothrud-Phursungi line.

SN	PERTICULARS OF ITEM	QTY	UNIT	RATE	GST @18%	Total	Labour Cess @ 1%	Unit Rate in Rs.	AMOUNT
1	Carrying out chaining and leveling & on approved /existing/ previously fixed line/alignment at 30m interval. Chainage & level at each detail like bund, HT/TP line, EHV line, railway line, road, hill slopes, canals, line details, including vertical clearances at crossings so as to get a profile of the ground existing along the alignment, preparing angle location sketches and submitting the same along-with any other details as may be required. as per directives of engineer incharge.	17.00	KM.	4644.00	835.92	5479.92	54.80	5534.72	94090.23
2	Preparing ground profile (L- Section) on standard scale graph paper with a scale of H,1cm=20m and vertical 1cm = 2m showing each detail such as nalla road, railway, Telephone, Power line, in plan as well as in elevation also dividing the section i.e. profile starting from 'O' chainage from one angle point to angle point final chainage of next angle point (GPS co-ordinates of angle points should be provided) and submitting the original profiles and two blue prints each as per directives of engineer incharge.	17.00	KM.	1452.00	261.36	1713.36	17.13	1730.49	29418.39
3	Spotting of towers on profiles by approved template including showing sag marking, tower no., clearance to crossing details i.e. Road, LT,HT,EHV lines, railway lines, road and ground etc.and marking of weight span and sum of the span and strengthening of cross arms if required giving all details of same and preparing tower schedule in two copies etc.completed as directed by engineer incharge.	17.00	KM.	929.00	167.22	1096.22	10.96	1107.18	18822.10
4	Collecting village map from revenue authority and joining them with proper scale (1:10000) and marking the surveyed line belt, forest area, 35 G forest, N.A. plots and as per scale on it for preparing ROW, forest proposal submitting the maps on tracing paper etc. complete as per directives of engineer incharge.	17.00	KM.	1451.00	261.18	1712.18	17.12	1729.30	29398.13
Total in Rs									171728.85

(RS: One Lakhs Seventy One Thousand Seven Hundred Eighty Nine only)

SD/-
Executive Engineer
EHV Projects Division-I, Pune