



EHV Projects Division-I, Pune
925, Kasba Peth Admn. Building, 3rd Floor, PUNE-11.
Tel No. 020-24579223 Fax No. : 020-24573602 E mail: ee6610@mahatransco.in
(CIN NO.U40109MH2005SGC153646)

No. EE/EHVPD-I/PN/T/ Enquiry/876

Date : 09.07.2020

Sub: Work of detailed survey of LILO on existing 132 KV S/C Mahindra forge-Vignhar line near Kalamb for existing 132 KV Pimpalgaon S/S

Dear Sir,

Please quote your lowest percentage rates for the works indicated in schedule 'B' enclosed on following terms & conditions:

TERMS & CONDITIONS :

1. Rate shall be quoted on firm quotation basis inclusive of all Taxes and shall be given in words & figures separately. The site should be visited before quoting the rates. Rate shall be valid for 120 days from the date of quotation.
2. Your sealed quotation should be uploaded in SRM tendering portal on or before dt: **16.07.2020** upto **11.59 Hrs.**
3. The work shall be completed within **30 Days from the date of handing over of site** otherwise penalty @ 1/2% per week subject to max.5% of the order amount will be levied at the discretion of the Competent Authority.
4. You will have to pay **Security Deposit of 10%** of the total work order amount and the same will be refunded after one month of work completion.
5. No T & P & Labour will be provided by the Company.
6. Income tax will be recovered from your bill as per rule.
7. Proof regarding registration under shop & establishment Act 1948, GST registration copy and PAN card copy should be enclosed.
8. The contractor should have the experience of similar work in the EHV transmission line survey during last five years. The experience certificate should be uploaded with quotation.
9. If any damages occur to the MSETCL property during execution of work you will have to make them good at your own cost.
10. 100% payment will be effected by this office by cheque after satisfactory completion of work.
11. You will have to pay EMD of amount Rs. 5000/- online during SRM processes and same will be refunded to lowest bidder after payment of SD. EMD will be refunded to other bidder within a

week period after finalizing the order. However due to any reason if enquiry is cancel , the EMD will be refunded online within week.

12. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.

Thanking you.

Yours faithfully,

SD

Executive Engineer
EHV Projects Division-I, Pune

Encl: 1) Schedule 'B'

2) % Rate format

Copy to: 1. The AddEE, S & I S/Dn, Pune

- Mf

SCHEDULE-B

Sl. No.	PERTICULARS OF ITEM	QTY	UNIT	RATE	GST @18%	Total	Labour Cess @ 1%	Unit Rate in Rs.	AMOUNT
1	Carrying out alignment as per approved route map by using precision total station, fixing of alignment with Total station...etc complete	11	KM.	3858	694.44	4552.44	45.52	4597.96	50577.61
2	Carrying out chaining and leveling & on approved /existing/ previously fixed line/alignment at 30m interval. Chainage & level at each detail like bund, HT/TP line, EHV line, railway line, road, hill slopes, canals, line details, including vertical clearances at crossings so as to get a profile of the ground existing along the alignment, preparing angle location sketches and submitting the same along-with any other details as may be required. as per directives of engineer incharge.	11.00	KM.	4786	861.48	5647.48	56.47	5703.95	62743.50
3	Preparing ground profile (L- Section) on standard scale graph paper with a scale of H, 1cm=20m and vertical 1cm = 2m showing each detail such as nalla road, railway, Telephone, Power line, in plan as well as in elevation also dividing the section i.e. profile starting from 'O' chainage from one angle point to angle point final chainage of next angle point (GPS co-ordinates of angle points should be provided) and submitting the original profiles and two blue prints each as per directives of engineer incharge.	11.00	KM.	1593	286.74	1879.74	18.8	1898.54	20883.91
4	Spotting of towers on profiles by approved template including showing sag marking, tower no., clearance to crossing details i.e. Road, LT, HT, EHV lines, railway lines, road and ground etc. and marking of weight span and sum of the span and strengthening of cross arms if required giving all details of same and preparing tower schedule in two copies etc. completed as directed by engineer incharge.	11.00	KM.	1070	192.60	1262.60	12.63	1275.23	14027.45
5	Collecting village map from revenue authority and joining them with proper scale (1:10000) and marking the surveyed line belt, forest area, 35 G forest, N.A. plots and as per scale on it for preparing ROW, forest proposal submitting the maps on tracing paper etc. complete as per directives of engineer incharge.	11.00	KM.	1593	286.74	1879.74	18.80	1898.54	20883.91
Total in Rs									169116.4

sd
Executive Engineer
EHV Projects Division-I, Pune

FORM FOR QUOTING % RATE FOR ITEM INCLUDED IN SHEDULE B FOR

Work of detailed survey of LILO on existing 132 KV S/C Mahindra forge-Vignhar line near Kalamb for existing 132 KV Pimpalgaon S/S

Estimated Cost- Rs 169116.42 /- (including GST & labour cess)

I am ready to execute the work to

_____ % above (In words _____ % above)

_____ % below (In words _____ % below)

the estimated cost.

Dated _____

Signature _____

Note: 1] If the percentage variation is more than 5% detailed rate analysis should be submitted along with the quotation.

2] The rate should be inclusive of all taxes. Rate shall be mention with tax bifurcation