

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	: Executive Engineer, EHV O&M Division, Latur.
Office Address	: 132 kV Latur(MIDC) S/s Premises, Near Kirti Gold Mill, MIDC Road, Latur-413512
Contact No.	: 02382-245208(O), 8554994957
Email ID	: eelaturdn@gmail.com, ee2220@mahatransco.in.

Ref. No. : EE/EHV/O&M/LTR/TS/ No 1 0 3 7 - Date: - 11 DEC 2020

E-Enquiry

Sub :- E-Enquiry for Control room lightening work at 132 KV Ujani S/s under EHV O&M Dn, Latur

Dear Sirs,

Sealed and super scribed quotations are invited for the work as specification given below. The quotation giving full particulars should reach this office on or before 12.12.2020, up to 15.00 Hrs positively. The Taxation liability should show separately. Rights of cancellation/modification of E-Enquiry at any stage, is reserved at this office.

Schedule 'A'

SN	Description	Unit	Quantity	Rate (Supply+Labour) (Excluding GST)	Rate (Supply+Labour) (Including GST)	Amount.
1	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25 mm with accessories on wall/ceiling as per specification No: WG MA/CON.	RMT	450			
2	Supplying and erecting exhaust fan heavy duty 440 V A.C. 50 cycles 900 RPM 375/380 mm complete erected in position as per specification no. FG-FN/EXF	no.	3			
3	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	no.	12			
4	Supplying & erecting decorative pre-wired box type fitting/batten suitable for 4 feet, T8	no.	20			

SN	Description	Unit	Quantity	Rate (Supply+Labour) (Excluding GST)	Rate (Supply+Labour (Including GST)	Amount.
	LED tube light (excluding tube light).					
5	Supplying and erecting LED street light fitting suitable above 26W to 36W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminum alloy and heat sink extruded aluminum complete as per specification No FGODF/FLS2.	no.	12			
6	Providing & erecting 3 Pole MCCB of 200A, 415V capacity with short circuit rating 25 kA (Ics=100% of Icu) adjustable thermal (overload) setting and fixed magnetic setting with provided leads, provision for installation of shunt/ UV/ trip alarm contact and MCCB should have phase barriers both sides, in provided enclosure on iron /GI frame as per specification no. SW- SWR/MCCB	no.	1			
7	Supplying and erecting 6 to 32 A SPMCB suitable to fix in 1 module of modular switch in provided box complete & duly concealed with necessary material and connected.	no.	15			
8	Supplying, erecting & marking TPN MCB 40A to 63A, C- series in provided distribution board as per specification no. SW- SWR/MCB	no.	2			
9	Supplying & erecting mains with 2x2.5 sq.mm. and earth wire	RMT	685.00			

SN	Description	Unit	Quantity	Rate (Supply+Labour) (Excluding GST)	Rate (Supply+Labour) (Including GST)	Amount.
	1.5 sq.mm FR PVC copper wire, in HMS PVC conduit min. 20mm dia, as per specification No: WG-MA/PC.					
10	Supplying & erecting mains with 2x4 sq.mm. and earth wire 2.5 sq.mm FR PVC copper wire in HMS PVC conduit min. 20mm dia, as per specification No: WG-MA/PC.	RMT	430.00			
11	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface/flush mounted with 2 ways for incoming and 10 ways for outgoing SP MCB's on iron/ G.I. frame/wooden board as per specification No. SW-SWR/MCBDB	nos	3.00			
Grand Total (Including Taxes) Rs.						

Estimated amount for the above work: Rs. 2,95,372.88/- (Including all Taxes).

Note:- 1. Zerox signed copies of below mentioned documents should be attached along with quotation.

- a) PAN Card. b) GST registration Certificate c) Bombay Shop Act License
d) Electrical Contractor License. e) Experience certificate of similar work (The experience certificate from the officer not below the rank of Executive Engineer)


**Executive Engineer,
EHV O&M Division Latur**