

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)  
EHV Civil Construction cum Maintenance Division Nashik  
"Administrative Building", Block No.6, 1<sup>st</sup> floor, Racca Plot,  
Old Saikheda Road, Jail Road, Nashik Road-422 101.  
Ph No:-0253-2403101 (O), Extension Phone No, 0253-2403110  
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

Date:- 09 FEB 2021

No - 150

**e- Quotation**

Sealed and superscripted e- quotations are invited for the work of "Providing and fixing French doors, aluminum chequered plate covers, partition for cabin etc. in control room of 220 KV Babhaleshwar Sub station, Dist:- Ahmednagar." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

**Name of Work:-** Providing and fixing French doors, aluminum chequered plate covers, partition for cabin etc. in control room of 220 KV Babhaleshwar Sub station, Dist:- Ahmednagar.

The quotations should reach to this office on or before 15/02/2021 up to 15.00 Hrs.

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

**(a) Compulsory Primary Documents in 1<sup>st</sup> Envelop:(Technical Bid)**

- (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) E.P.F. Registration Certificate – issued by competent authority of Govt.
- (iv) Experience of having successfully completed similar civil works.
- (v) Payment of EMD Rs. 3000.00 to be made by bidder off-line only upto 14.00 hrs of 15/02/2021 in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope.

**(b) Documents in 2<sup>nd</sup> Envelop:(Price Bid)**

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

**NOTE:-** Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- 6) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule B
- 7) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 8) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 9) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 10) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to, agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)  
**Executive Engineer (Civil)**  
**EHV Civil CCM Dn.Nashik.**

Copy s.w.r.t.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer (Civil) EHV CCCM Sub Division Babhaleshwar.
- 2) Dy. Manager (F&A) EHV CCCM Division Nashik.
- 3) Master File/Notice Board.


**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**  
**EHV CCCM DIVISION, NASHIK**

**Name of work-**Providing and fixing French doors, aluminum chequered plate covers, partition for cabin etc. in control room of 220 KV Babhaleshwar Sub station, Dist:- Ahmednagar.

**SCHEDULE 'B'**

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
1	P/L aluminum chequered plates for cable trench cover of thickness 3.15 mm plain plus 0.85 mm Chequered fixed to M.S. angle frame of Size 25x25x3 mm both side diagonal and at border including fabrication, painting to angles in three coats of silver painting revetting and making grooves to the chequered plate for handling etc. complete. (Sanctioned rate PO No 5600035527 )	29.00	Sq.M.	3310.00	595.80	3905.80	113268.20
2	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	0.40	M.T	80532.00	14495.76	95027.76	38011.10
3	Providing and fixing of colour coated Zinc aluminium ( R ) AZ150 ( min 150 gms/sq.mt. total on each side ) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness ( BMT ) (0.5 mm TCT ), Hi-strength steel with min.550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND ( R ) steel quality super durable polyester paint coat ( with inorganic pigment). The paint shall have a total coating thickness of nominal 35 um, comprising of nominal 25um exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with subtle square fluting in the five pan at nominal 180-250 mm center- to-center. The end rib shall be designed for anti-capacity groove. and return leg. The feed material should have coil manufacturers product details marked a regular interval. including fasteners with min. fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. complete. (weight of profile 4.52 Kilogram/Square Metre) 900 mm girth (Surface Width).	14.00	Rmt	1005.00	180.90	1185.90	16602.60
4	Providing and fixing in position anodised extruded aluminum partitions, partly glazed and partly laminated having frame made out of extruded tubular section of size 40 mm x 60 mm with 12 mm thick three layered flat pressed teak wood particle board bonded with BWP type exterior grade phenol formaldehyde synthetic resin conforming to IS 12823:1990, laminated on both sides, Novatekor equivalent and 5 mm thick selected quality plain/ float glass panels fixed with aluminum glass clips 12 mm x 12 mm and rubber cushioning beading to glass partitions as per approved drawing etc. complete	19.50	Sqm.	3206.00	577.08	3783.08	73770.06

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
5	Providing & fixing in position french of Infinity Basic design Double / three panel french door with Main frame and SS aldrop or its equivalent includes SS finished tower bolt, Handle, Aldrop , 3.5mm clear glass, with square Bright bar of 10 sq.mm with 100 mm bar spacing & GI sheet 1mm (Jindal 120 gsm , SKIN Pass ) for shutter & 1.2mm ( Jindal 120 gsm SKIN Pass) for frame with Pure Polyster powder Coating (make Asian)in Morning glory shade. etc complete as directed by Engr In charge	6.50	Sq.M.	4717.00	849.06	5566.06	36179.39
6	Removing old paint from steel and other metal surfaces and making the surfaces even with hand scrapping, scaffolding etc. complete.	121.00	Sqm.	17.00	3.06	20.06	2427.26
7	Providing and applying one coat of lead/zinc base oil paint/ bituminous paint of approved colour and shade to old wood work previously painted and fiber boards including if necessary scaffolding, preparing surface excluding primer coat etc. complete.	121.00	Sqm.	46.00	8.28	54.28	6567.88
8	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	37.00	Sqm.	85.00	15.30	100.30	3711.10
9	Providing and applying french polish to new wood work, for required finishing including. knotting, preparing the surfaces, scaffolding etc. complete as directed.	26.00	Sqm.	238.00	42.84	280.84	7301.84
10	Removing the RCC cable trench covers in control room building and dispossing off manually in the sub station premises as directed.	28.65	Sqm.	52.00	9.36	61.36	1757.96
<b>Total Rs.</b>							<b>299597.40</b>
<b>Say Rs.</b>							<b>299597.00</b>

  
**Executive Engineer (Civil)**  
**EHV CCCM Division Nashik.**

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.