



MAHA TRANSCO

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenances Division Nashik

"Administrative Building", Block No. 6, 1st floor, Racca Plot,

Old Saikheda Road, Jail Road, Nashik Road-422 101.

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

No - 2 0 7 6

Date:- 09 DEC 2021

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Electrification and plumbing work for Testing Office at 220 KV Satana Staff quarter, Satana, Nashik." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Electrification and plumbing work for Testing Office at 220 KV Satana Staff quarter, Satana, Nashik.

The quotations should reach to this office on or before 16/12/2021 up to 15.00 Hrs

1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) **Compulsory Primary Documents in 1st Envelop:(Technical Bid)**

- (i) Valid Certificate of Electrical Contractor License.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) Experience of having successfully completed similar types of works.
- (iv) PAN card.
- (v) Shop Act certificate/ Udyog Adhar Registration.
- (vi) Payment of **EMD Rs. 1670.00** to be made by bidder off-line only upto 14.00 hrs of 16/12/2021 in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

(b) **Documents in 2nd Envelop:(Price Bid)**

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.**

Copy s.w.r.to.-

- 1) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) The Dy. Manager [F&A] Dn. Office, Nashik.
- 2) Master File/Notice Board.

MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV CIVIL CONSTRUCTION DIVISION, NASHIK

Name of work:-Electrification and plumbing work for Testing Office at 220 KV Satana Staff quarter, Satana, Nashik

SCHEDULE 'B'

Sr.	Description	Qty.	Unit	Rate	Amount
1	Supplying & erecting mains with 2x4 sq.mm F.R copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WGMA/BW	110.00	Mtr	112.00	12320.00
2	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	131.00	Mtr	86.00	11266.00
3	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire with 1x1.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	25.00	Mtr	60.00	1500.00
4	Supplying & laying HMS PVC conduit 20 mm dia with necessary accessories in RCC work/false ceiling/false flooring	25.00	RMT	88.00	2200.00
5	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 20 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	156.00	RMT	36.00	5616.00
6	Supplying and erecting Ceiling rose / Batten holder / Slanting holder / hanging cord switch / hanging bell push / pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box	22.00	EA	35.00	770.00
7	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 3 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background. (2 Or 3 As per Site Condition)	16.00	EA	231.00	3696.00
8	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 6 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	1.00	EA	301.00	301.00
9	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 8 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	1.00	EA	375.00	375.00
10	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 12 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	9.00	EA	476.00	4284.00

Sr.	Description	Qty.	Unit	Rate	Amount
11	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 16/18 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	1.00	EA	537.00	537.00
12	Supplying and erecting ISI mark modular type switch 16 / 20 A with indicator, duly erected on provided plate and box with wiring connections complete.	7.00	EA	134.00	938.00
13	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	*7.00	EA	166.00	1162.00
14	Point wiring for light/fan/bell concealed type in min 20 mm ISI marked HMS PVC conduit with 1.5 sq.mm. (2+1E) FR grade copper wires, modular type switch, earthing and required accessories as per specification No: WG-PW/CW	22.00	Point	635.00	13970.00
15	Point wiring for independent plug, concealed type in min 20 mm ISI marked HMS PVC conduit with 1.5 sq.mm (2+1E) FR grade copper wires, modular type switch and socket, earthing and required accessories as per specification No WGPW/ SW	26.00	EA	687.00	17862.00
16	Supplying & erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete.	8.00	EA	926.00	7408.00
17	Supplying and erecting corridor/passage light fitting (2 feet) including 18W LED lamp, comprises of extruded channel in plastic silver grey colour & with same plastic end cap on provided PVC block / wooden board.	2.00	EA	730.00	1460.00
18	Supplying and erecting ISI marked modular type telephone socket one gang with safety shutter, duly erected on provided plate and box with wiring connections complete	6.00	EA	106.00	636.00
19	Supplying and erecting ISI mark modular type computer jack RJ 45 with safety shutter, duly erected on provided plate and box with wiring connections complete,	6.00	EA	109.00	654.00
20	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface/flush mounted with 2 ways for incoming and 10 ways for outgoing SP MCB's on iron/ GI frame as per specification no. SW-SWR/MCBDB	1.00	EA	1347.00	1347.00
21	Supplying, erecting & marking DPMCB 6A to 32A, C- series (for motor/power) in provided distribution board as per specification no. SW-SWR/MCB	1.00	EA	488.00	488.00
22	Supplying, erecting & marking SPN MCB 6A to 32A, C- series (for motor/power) in provided distribution board as per specification no. SW-SWR/MCB	7.00	EA	451.00	3157.00
23	Supplying & erecting telephone copper cable 2 pair with 0.5 mm dia. laid in provided PVC casing capping/ conduit as per specification No. WG-TW	85.00	Mtr	23.00	1955.00
24	Supplying & installing co-axial copper cable low voltage grade RG-11 as per specification No. WG-TW	45.00	Mtr	68.00	3060.00
25	Supplying and erecting LED street light fitting suitable above 26W to 36W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/FLS2.	2.00	EA	2751.00	5502.00

Sr.	Description	Qty.	Unit	Rate	Amount
26	Supplying and erecting street light Wall bracket made from 40 mm. dia 'B' class G.I. pipe 1.2 m in total length complete as per specification no. FG-BKT/WB	2.00	EA	712.00	1424.00
27	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	3.00	EA	2042.00	6126.00
28	Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete.	3.00	EA	368.00	1104.00
29	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density polythylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	2000.00	LTR	13.00	26000.00
30	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	Metre	246.00	2460.00
31	Plumber With Tools - Skilled	2.00	Day	641.00	1282.00
32	Helper Un Skilled	1.00	Day	611.00	611.00
				Total Rs.	141471.00
				Add GST 18%	25464.78
				Total Rs.	166935.78
				Say Rs.	166936.00


Executive Engineer (Civil)
EHV CECM Division Nashik.

I / We hereby agree to carryout the above work as under :-

- a) At estimated cost.
- b) Above.....% in words.....Of Estimated cost in Schedule "B"
- c) Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.